

DRAFT

**RECORD OF DECISION AMENDMENT
FOR OPERABLE UNIT 4 SILO 3 REMEDIAL ACTIONS**

AT THE

**UNITED STATES DEPARTMENT OF ENERGY
FERNALD CLOSURE PROJECT
FERNALD OHIO**

40430-RP-0026
Revision A

June 2003

000001

TABLE OF CONTENTS

8243

DECLARATION STATEMENT.....DS-1

1 INTRODUCTION.....1-1

1.1 BACKGROUND1-1

1.2 ORIGINAL OU4 RECORD OF DECISION.....1-2

1.3 REASON FOR RECORD OF DECISION AMENDMENT1-2

2 SITE BACKGROUND2-1

2.1 OVERVIEW OF SILO 32-2

2.2 PURPOSE AND NEED FOR DECISION2-4

2.3 ORIGINAL SELECTED REMEDY FOR SILO 3 MATERIAL.....2-4

2.4 1998 SILO 3 ESD MODIFICATION TO THE 1994 ROD2-5

2.5 TREATMENT CRITERIA FOR SILO 3 MATERIAL.....2-6

3 BASIS FOR MODIFYING THE OU4 RECORD OF DECISION3-1

3.1 WASTE ACCEPTANCE CRITERIA FOR THE NEVADA TEST SITE3-1

3.2 EMERGENCE OF POTENTIAL COMMERCIAL DISPOSAL OPTIONS FOR DOE 11E.(2) MATERIALS.....3-2

4 DESCRIPTION OF SIGNIFICANT DIFFERENCES OR NEW ALTERNATIVES.....4-1

4.1 DETAILED DESCRIPTION OF THE REVISED REMEDY.....4-2

5 EVALUATION OF ALTERNATIVES5-1

5.1 THRESHOLD CRITERION NO. 1: OVERALL PROTECTION OF HUMAN HEALTH AND THE ENVIRONMENT5-2

5.2 THRESHOLD CRITERION NO. 2: COMPLIANCE WITH ARARS5-3

5.3 BALANCING CRITERION NO. 1: LONG-TERM EFFECTIVENESS AND PERMANENCE.....5-4

5.4 BALANCING CRITERION NO. 2: REDUCTION OF TOXICITY, MOBILITY, OR VOLUME THROUGH TREATMENT5-5

5.5 BALANCING CRITERION NO. 3: SHORT-TERM EFFECTIVENESS5-6

5.6 BALANCING CRITERION NO. 4: IMPLEMENTABILITY5-8

5.7 BALANCING CRITERION NO. 5: COST5-10

5.8 MODIFYING CRITERION NO. 1: STATE ACCEPTANCE5-11

5.9 MODIFYING CRITERION NO. 2: COMMUNITY ACCEPTANCE.....5-11

6 STATUTORY DETERMINATIONS6-1

6.1 PROTECTION OF HUMAN HEALTH AND THE ENVIRONMENT.....6-1

6.2 COMPLIANCE WITH ARARS.....6-2

6.3 COST EFFECTIVENESS.....6-2

6.4 UTILIZATION OF PERMANENT SOLUTIONS AND ALTERNATIVE TREATMENT TECHNOLOGIES OR RESOURCE RECOVERY TECHNOLOGIES TO THE MAXIMUM EXTENT PRACTICABLE6-3

6.5 PREFERENCE FOR TREATMENT AS A PRINCIPAL ELEMENT.....6-3

6.6 NATIONAL ENVIRONMENTAL POLICY ACT.....6-4

7 COMMUNITY PARTICIPATION7-1

APPENDIX A APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS

APPENDIX B RESPONSIVENESS SUMMARY

000002

8243

1 **DECLARATION STATEMENT**

2
3 **SITE NAME AND LOCATION**

4 Fernald Closure Project -- Operable Unit 4 (OU4), Silo 4, Fernald, Hamilton County, Ohio.
5

6 **STATEMENT OF BASIS AND PURPOSE**

7 This Record of Decision Amendment for Remedial Actions at Silo 3 [hereinafter called the
8 ROD Amendment] addresses the re-evaluation of the treatment component of the selected
9 remedy for the remediation of the OU4 Silo 3 material at the Fernald Closure Project (FCP)
10 in Fernald, Ohio. The remedial action identified in this ROD Amendment was selected in
11 accordance with the Comprehensive Environmental Response, Compensation, and Liability
12 Act, as amended (CERCLA) and the National Oil and Hazardous Substances Pollution
13 Contingency Plan (NCP) [40 Code of Federal Regulations (CFR) Part 300].

14 The decision presented herein is based on the information available in the administrative
15 record established and maintained for OU4 in accordance with CERCLA. This decision is
16 also based on input received from the United States Environmental Protection Agency
17 (EPA), the Ohio Environmental Protection Agency (OEPA), and the public during review of
18 the Proposed Plan for Silo 3. The Department of Energy (DOE) has considered all
19 comments received during the public comment period in the preparation of this ROD
20 Amendment.

21 The State of Ohio concurs with the remedy and the applicable or relevant and appropriate
22 requirements (ARARs) put forth in this ROD Amendment for the remediation of OU4 Silo 3
23 material.

24 **ASSESSMENT OF THE SITE**

25 Actual or threatened releases of hazardous substances from OU4, if not addressed by
26 implementing the response action selected in this ROD Amendment, may present an
27 imminent and substantial endangerment to public health, welfare, or the environment.

000003
June 2003

8243

1 **DESCRIPTION OF THE REMEDY**

2 On the basis of the evaluation documented in the Proposed Plan for Silo 3, the selected
3 remedy addressing Silo 3, a portion of OU4 at the Fernald Closure Project, has been
4 modified to the following:

- 5 • Removal of material from Silo 3 by pneumatic and/or mechanical processes
- 6 • Treatment to the extent practical, by addition of a chemical stabilization reagent and a
7 reagent to reduce dispersability
- 8 • If above treatment step is deemed unimplementable, a contingency backup would be
9 implemented to double package the waste

10 In addition, the remedy for Silo 3 continues to include the following components, which
11 were not reevaluated, and remain as documented in the original OU4 ROD, and
12 subsequent Explanation of Significant Differences (ESD) for Silo 3:

- 13 • Maintain transportation risk less than 1×10^{-6}
- 14 • Off-site disposal of Silo 3 material at the Nevada Test Site or a permitted commercial
15 facility
- 16 • Removal of Silo 3 structure, remediation facilities, and associated systems and
17 components.
- 18 • Cleanup of soil in Silo 3 area to meet final remediation levels in Operable Unit 5 ROD
- 19 • Appropriate treatment and disposal of all secondary wastes at the Nevada Test Site or
20 an appropriately licensed off-site facility.
- 21 • Collection of perched water encountered during remedial activities for treatment at OU5
22 water treatment facilities.
- 23 • Continued access controls and maintenance and monitoring of the stored waste
24 inventories.
- 25 • Institutional controls of the OU4 area such as deed and land-use restrictions.

26 A comparison of the revised Silo 3 remedy and the previous remedy specified in the Silo 3
27 ESD, using the nine criteria specified by the NCP in 40 Code of Federal Regulations (CFR)
28 Part 300, is presented in Section 5 of this ROD Amendment. The selected remedy
29 satisfies both of the threshold criteria specified by the NCP and represents the best
30 balance between the alternatives with respect to the five primary balancing criteria. This
31 remedy will achieve substantial risk reduction by removing the sources of contamination,
32 treating the material that poses the highest risk, shipping the treated material off-site for
33 disposal, and managing the remaining contaminated soils and debris consistent with the
34 site-wide strategy for the Fernald Closure Project.

000004

8243

1 **STATUTORY DETERMINATIONS**

2 As documented in Section 6 of this ROD Amendment, the selected remedy satisfies all of
3 the statutory requirements specified by the NCP [40 CFR Part 300.430(f)(5)(ii)]. The
4 selected remedy is protective of human health and the environment, complies with all
5 federal and state requirements that are legally applicable or relevant and appropriate to the
6 remedial action. This remedy uses permanent solutions and alternative treatment (or
7 resource recovery) technologies to the maximum extent practicable, is cost effective, and
8 adequately addresses the statutory preference for remedies which include treatment as a
9 principal element.

10 The selected remedy includes treatment to reduce the dispersability and mobility of
11 contaminants, and thereby satisfies the statutory preference for treatment as a principal
12 element. The selected remedy also provides risk reduction proportional to the cost of the
13 remedy. If the treatment step cannot be satisfactorily implemented due to overriding
14 technical or short-term worker risk impediments, then the formal contingency action
15 explained in Section 4 of this ROD Amendment (additional double packaging of materials in
16 the protective shipping containers) is also deemed to provide an appropriate balance of risk
17 reduction, effectiveness, and cost. The contingent remedy satisfies Section 121
18 requirements and preferences under the site-specific circumstances giving rise to the need
19 for the contingency action.

20 The Silo 3 remedy defined in this ROD Amendment has costs proportional to its overall
21 effectiveness, and therefore meets the statutory requirement for cost-effectiveness.

22 This remedy will result in contaminated debris and soil being dispositioned in accordance
23 with the EPA-approved RODs for OU3 and OU5, respectively. This remedy may result in
24 pollutants or contaminants, as defined by CERCLA, [i.e., contaminated soil and debris in
25 the Onsite Disposal Facility (OSDF)] remaining on-site. Therefore, a review will be
26 conducted every five years after commencement of remedial actions to ensure that the
27 remedy continues to provide adequate protection of human health and the environment.

000005

June 2003

1 The change documented in the ROD Amendment is bounded by the alternatives evaluated
2 in the original Feasibility Study/Proposed Plan/Environmental Impact Statement (FS/PP/EIS)
3 and the subsequent Supplemental Analyses. Therefore, it is DOE's determination that
4 potential National Environmental Policy Act (NEPA) issues associated with the change
5 have been adequately evaluated and that no additional NEPA documentation or evaluation
6 is necessary.

Robert Warther, Manager
United States Department of Energy – Ohio Field Office

Date

William E. Muno, Director
Superfund Division
United States Environmental Protection Agency – Region V

Date

000006

8243

1 **1.2 Original OU4 Record of Decision**

2 The decision documented by the original OU4 ROD was based on the information available
3 in the Administrative Record for OU4 and maintained in accordance with CERCLA. The
4 major documents prepared through the CERCLA process include the OU4 Remedial
5 Investigation (RI), the original OU4 FS, and the original Proposed Plan PP for OU4. The
6 original selected remedy of vitrification was selected (after the original FS/PP-Draft EIS
7 was issued) with consideration of input received from public hearings held on March 21,
8 1994, in Harrison, Ohio and on May 11, 1994, in Las Vegas, Nevada. In preparation of
9 the original OU4 ROD, DOE considered the comments received both during the public
10 comment period for the original FS/PP-Draft EIS and those following issuance of the final
11 EIS. The original OU4 ROD was approved by DOE and EPA in December 1994.

12 In March 1998, DOE and EPA signed an ESD for Silo 3, which formally approved the shift
13 from vitrification to chemical stabilization/solidification or polymer encapsulation for
14 treating the Silo 3 residues to achieve disposal facility waste acceptance criteria and the
15 associated quantitative Toxicity Characteristic Leachate Procedure (TCLP)-based
16 performance standards adopted by the 1994 ROD.

17 **1.3 Reason for Record of Decision Amendment**

18 Since the Silo 3 ESD was issued in 1998, DOE and EPA have received new information
19 concerning (1) the waste acceptance criteria for the Nevada Test Site disposal facility, and
20 (2) the potential availability of other commercial facilities that can accept the Silo 3
21 residues for disposal as 11e.(2) regulated materials. This new information demonstrates
22 that it is now permissible to permanently dispose of the Silo 3 residues in an untreated
23 form at the Nevada Test Site, and that a commercial facility may also be able to accept
24 the untreated Silo 3 material in the near future. As previously stated treatment will be
25 applied to the degree reasonably implementable to address the dispersability and mobility
26 of the heavy metals.

000008

1 Pursuant to Section 117 of CERCLA and the NCP [40 CFR Part 300.435(c)(2)(ii)], a ROD
2 Amendment should be processed when "differences in the remedial or enforcement action,
3 settlement, or consent decree fundamentally alter the basic features of the selected
4 remedy [in the original ROD] with respect to scope, performance, or cost."

5 DOE is issuing this ROD Amendment as part of its public participation responsibilities
6 under Section 117(a) of CERCLA, and 40 CFR 300.430(f)(2) of the NCP. The intent of
7 this ROD Amendment is to inform the public on the revision of the previously approved
8 remedy for Silo 3 material.

9 This ROD Amendment summarizes key information that can be found in greater detail in
10 the *Revised Proposed Plan for Silo 3*. This ROD Amendment, along with the PP for Silo 3
11 and other supporting documentation, will become part of the Administrative Record
12 pursuant to 40 CFR Part 300.825(a)(2). The addresses for the Administrative Record
13 locations are as follows:

<p>Public Environmental Information Center 7400 Willey Road Cincinnati, OH 45013-9402 513-648-7480</p> <p>Tuesday and Thursday, 7:30 a.m. to 4:30 p.m.</p>	<p>U.S. EPA Region V, SRF-5J 77 W. Jackson Blvd. Chicago, IL 60604 312-886-0992</p>
--	---

Key Documents From Administrative Record File

- 1993a, *Remedial Investigation Report for Operable Unit 4*. Prepared under contract for the U.S. Department of Energy: Fernald Field Office, Fernald, OH. (AR Index Numbers Vol. I-III: U-006-304.15 – 17)
- 1994a. *Feasibility Study for Operable Unit 4*. Prepared under contract for the U.S. Department of Energy: Fernald Field Office, Fernald, OH. (AR Index Numbers No. U-006-405.3)
- 1994b. *Proposed Plan for Remedial Actions at Operable Unit 4*. Prepared under contract for the U.S. Department of Energy: Fernald Field Office, Fernald OH. (AR Index Numbers Vol. I-IV: No. U-006-404.13 –16)
- 1994. *Record of Decision for Operable Unit 4*. EPA ID OH6890008976: ROD ID EPA/ROD/R05-65/287. (AR Index No. U-006-501.5) [abstract at <http://www.epa.gov/superfund/sites/rodsites/0504934.htm>]
- 1998b. *Final Explanation of Significant Differences for Operable Unit 4 Silo 3 Remedial Action at the Fernald Environmental Management Project*. 40400-RP-0004. Prepared under contract for the U.S. Department of Energy: Fernald Field Office, Fernald, OH. (AR Index No. U-006-503.11)

8243

2 SITE BACKGROUND

1
2 The Fernald Closure Project, formerly known as the Fernald Environmental Management
3 Project and the Feed Materials Production Center, is a 1050-acre DOE facility located
4 approximately 18 miles northwest of Cincinnati. Fernald, Ohio is a small rural community
5 located just south of the FCP. The FCP is a government-owned facility that operated from
6 1952 to 1989 providing in excess of 500 million pounds of high-purity uranium metal
7 products in support of U.S. Defense initiatives. In 1992 the site was renamed the Fernald
8 Environmental Management Project and the mission was formally changed to
9 environmental restoration under the Comprehensive Environmental Response,
10 Compensation, and Liability Act (CERCLA), commonly known as Superfund. Its current
11 name, the Fernald Closure Project, was adopted in 2003 to reflect a continuing emphasis
12 on the completion of restoration activities and achieving the final closure end state safely
13 and efficiently.

14 To facilitate restoration, the CERCLA work scope for the 1,050-acre facility was divided
15 into five operable units: the waste pits (Operable Unit 1); other waste units (Operable Unit
16 2); the production area facilities and legacy-waste inventories (Operable Unit 3); Silos 1&2
17 and Silo 3 (Operable Unit 4); and contaminated environmental media (Operable Unit 5).

18 The selected remedial actions documented in the RODs for the five operable units include:
19 production facility decontamination and dismantlement (D&D); on-site disposal of the
20 majority of contaminated soil and D&D debris; off-site disposal of the contents of the two
21 K-65 silos (Silos 1&2), Silo 3, waste pit material, legacy waste inventories, and limited
22 quantities of soil and D&D debris not meeting on-site waste acceptance criteria; and
23 treatment of contaminated groundwater to restore the affected portions of the Great
24 Miami Aquifer underlying the FCP. Ultimately, approximately 975 acres of the 1,050-acre
25 property will be restored to beneficial use as an undeveloped park, and approximately 75
26 acres will be dedicated to the footprint of the On-site Disposal Facility. Contaminated
27 portions of the aquifer will be restored to beneficial use as a drinking water supply, and
28 long-term stewardship actions will be put in place consistent with the final designated land
29 use.

000010

8243

1 **2.1 Overview of Silo 3**

2 Silo 3, located adjacent to the K-65 silos (Silos 1&2) on the western periphery of the site,
3 is an unbermed concrete silo that contains 5,088 cubic yards of cold metal oxides, a by-
4 product material generated during Fernald's uranium processing operations. The
5 predominant radionuclide of concern identified within the material is thorium-230, which is
6 produced from the natural decay of uranium-238. The overall objective of the Silo 3
7 remedial action is to safely retrieve the residues from the concrete silo and package and
8 transport the materials for off-site disposal in a manner compliant with regulatory
9 requirements.

10 The materials contained in Silo 3 consist of relatively dry, powder-like residues that were
11 placed in the silo over the time period 1954 to 1957. The residues consist of the metallic
12 and non-metallic impurities that remained following the extraction of uranium from ore and
13 ore concentrates in Fernald's refinery operations during the mid-1950s. The residues were
14 prepared for storage following a volume reduction and concentration step known as
15 calcining, which is a roasting process in the presence of lime that serves to remove
16 moisture and convert the impurities to their more stable (less leachable) oxide form.
17 Following calcining, the dry residues were pneumatically conveyed to Silo 3 for longer-
18 term interim storage as part of DOE's ongoing custodial responsibility for the materials.

19 Although both residues share similar uranium processing origins and the same regulatory
20 status, the Silo 3 residues have different engineering properties and are radiologically
21 different from the Silos 1&2 K-65 residues. As "cold" residues (a term of engineering
22 convenience used to reflect the residual radium-bearing content of the residues), the Silo 3
23 materials have a much lower radium content than the K-65 materials, and therefore Silo 3
24 exhibits a much lower direct radiation field and has a substantially lower radon-222
25 emanation rate compared to Silos 1&2. The K-65 materials in Silos 1&2 are also moisture-
26 rich, silty, and clay-like materials, whereas the Silo 3 materials are dry and powdery.
27 Ambient moisture contents for the materials in Silo 3 range from 3 to 10 percent by
28 weight, which reflect their dry condition.

000011

1 On an activity basis, the predominant radiological constituent in the Silo 3 material is
2 thorium-230. The thorium contaminated Silo 3 residues do not present the same level of
3 direct radiation exposure potential as the radium-bearing Silos 1&2 residues, and exhibit
4 significantly lower emissions of radon gas (which forms as a radium decay product).
5 However, the residual thorium content and the relatively dry powdery condition of the Silo
6 3 residues together represent a dispersability hazard and an inhalation and ingestion hazard
7 to workers and the public if proper control and containment measures are not in place
8 during material handling and transportation steps.

9 DOE has designated the residues contained in Silo 3 and Silos 1&2 as Section 11e.(2)
10 byproduct materials under the Atomic Energy Act of 1954, as amended (AEA). This
11 regulatory classification acknowledges the origin of the materials and identifies that they
12 consist of tailings and wastes that were produced by the extraction and concentration of
13 uranium from ores that were processed primarily for their source material content. As
14 11e.(2) byproduct materials, the residues are statutorily excluded from the definition of
15 solid and hazardous waste under the Resource Conservation and Recovery Act (RCRA) of
16 1976; this statutory exclusion is described in the RCRA regulations under
17 40 CFR 261.4(a)(4). Specific regulatory requirements for management of the byproduct
18 materials are defined through the AEA regulations and accompanying policies and
19 directives.

20 As a point of reference, although they are statutorily excluded from formal RCRA
21 hazardous waste definitions and administrative requirements, the Silo 3 residues do
22 contain sufficient quantities of four RCRA regulated metals (arsenic, cadmium, chromium,
23 and selenium) such that they can exceed RCRA thresholds for leachability as measured
24 through the RCRA TCLP) laboratory test. As explained further below, this condition was a
25 consideration in establishing remedy-specific quantitative performance levels in the 1994
26 Operable Unit 4 ROD for rendering the Silo 3 residues suitable for off-site disposal through
27 treatment.

000012

June 2003

8243

1 **2.2 Purpose and Need for Decision**

2 Facilities and environmental media at the Fernald Closure Project, including OU4, contain
3 radioactive and chemical constituents at levels that exceed certain federal and state
4 standards, and guidelines for protecting human health and the environment. Currently,
5 DOE maintains custody of the property and restricts access with fences and security
6 forces, precluding a member of the public from being exposed to site areas that have
7 contamination.

8 The EPA has established a formalized risk assessment process to determine the necessity
9 for implementation of cleanup actions. Under this process, several hypothetical scenarios
10 that could expose members of the public to site contamination were examined. One of
11 these scenarios assumed that site access was not controlled (i.e., unrestricted) and a
12 member of the public could be exposed to the higher contamination areas. Results of the
13 risk assessment performed for this hypothetical, unrestricted access scenario indicated
14 that an individual establishing residence within the highly contaminated portions of the
15 OU4 area, under existing conditions, would be subjected to an increased risk of incurring
16 an adverse health effect. Risk assessment calculations performed for OU4 indicate the
17 projected level of increased risk exceeds established federal regulatory guidelines. Based
18 on the results of the baseline risk assessment, the DOE concluded in the RI that existing
19 site conditions warrant remedial action.

20 **2.3 Original Selected Remedy for Silo 3 Material**

21 The major components of the selected remedy documented in the original OU4 ROD are:

- 22 • Removal of the contents of the Silos 1, 2, 3 and the decant sump tank sludge.
23 • Treatment of the Silos 1, 2, and 3 material and sludges removed from the silos and the
24 decant sump tank by vitrification to meet disposal facility WAC.
25 • Off-site shipment of the vitrified contents of Silos 1, 2, 3 and the decant sump tank for
26 disposal at the Nevada Test Site.
27 • Demolition of Silos 1, 2, 3 and 4 and decontamination, to the extent practicable, of the
28 concrete rubble, piping, and other generated construction debris.
29 • Removal of the earthen berms and excavation of the contaminated soils within the
30 boundary of OU4, to achieve remediation levels. Placement of clean backfill to original
31 grade following excavation.

000013

June 2003

8243

- 1 • Demolition of the remediation and support facilities after use. Decontamination or
2 recycling of debris before disposition.
- 3 • On-property interim storage of excavated contaminated soils and contaminated debris
4 in a manner consistent with the approved *Work Plan for FEMP Removal Action No. 17*
5 *- Improved Storage of Soil and Debris* (DOE 1996)¹, pending final disposition of soil and
6 debris in accordance with the RODs of OUs 5 and 3, respectively.
- 7 • Continued access controls and maintenance and monitoring of the stored waste
8 inventories.
- 9 • Institutional controls of the OU4 area such as deed and land-use restrictions.
- 10 • Potential, additional treatment of stored OU4 soil and debris using OU5 and OU3 waste
11 treatment systems.
- 12 • Pumping and treating, as required, of any contaminated perched groundwater
13 encountered during remedial activities.
- 14 • Disposal of the OU4 contaminated debris and soils consistent with the RODs for OUs 3
15 and 5, respectively.

16 **2.4 1998 Silo 3 ESD Modification to the 1994 ROD**

17 In early 1998, an ESD was developed for Silo 3 to replace the vitrification technology with
18 chemical stabilization/solidification or polymer encapsulation as the preferred treatment
19 option for treating the Silo 3 wastes to achieve the TCLP-based waste acceptance limits
20 for off-site disposal. This modification was adopted to address implementability concerns
21 with vitrification that were revealed in pilot scale tests of the technology on surrogate
22 materials chosen to emulate the salient engineering properties of the silos materials.

23 The Silo 3 ESD, which was signed by DOE and EPA in March 1998, acknowledged that
24 the adoption of a chemical stabilization/solidification or polymer encapsulation alternative
25 for Silo 3 (as a replacement for vitrification) would not be a fundamental change to the
26 original remedy identified in the 1994 ROD, provided that the alternate process continued
27 to meet all remedial objectives and performance standards of the approved ROD for a cost
28 roughly equivalent to the original remedy, and that the remedy includes disposal at a
29 protective, appropriately permitted off-site disposal facility.

¹ This component of the selected remedy was documented in the original Operable Unit 4 record of Decision (ROD) in 1994. However, for purposes of this ROD Amendment the reference has been updated to the most recent revision.

000014

1 The Silo 3 ESD also acknowledged that the waste treatment step could be implemented
2 either off site or on site to achieve the intended TCLP-based waste acceptance criteria
3 requirement. If the treatment step were to be conducted off site, on-site pretreatment
4 would be conducted at the Fernald Closure Project as necessary to reduce the
5 dispersability of the thorium-bearing particulates and render the material acceptable for
6 transportation. The ESD required that on-site pretreatment, in combination with packaging
7 in accordance with Department of Transportation (DOT) regulations, must reduce the
8 dispersability of the thorium-bearing particulates and result in a transportation risk less
9 than 1×10^{-6} Incremental Life-time Cancer Risk.

10 The modified Silo 3 remedy specified by the 1998 ESD consisted of:

- 11 • Removal of the wastes From Silo 3
- 12 • Treatment, either on site or off site using chemical stabilization/solidification or a
13 polymer-based encapsulation process, to stabilize RCRA-regulated metals to meet RCRA
14 TCLP limits and attain disposal facility waste acceptance criteria
- 15 • If off-site treatment is employed, off-site shipment must be preceded by on-site
16 pretreatment and/or packaging such that the risk to the public from transportation of
17 the material to the off-site facility is less than 1×10^{-6}
- 18 • Off-site disposal at either the Nevada Test Site or a permitted commercial disposal
19 facility
- 20 • Removal and disposal of the Silo 3 structure and the waste handling, packaging, and
21 treatment systems
- 22 • Cleanup of the soil underlying the Silo 3 area to the final remediation levels defined in
23 the Operable Unit 5 ROD.

24 **2.5 Treatment Criteria for Silo 3 Material**

25 At the time of the 1994 ROD, the Nevada Test Site was the only available disposal
26 location that could accept the vitrified silo materials for permanent disposal. As part of its
27 waste acceptance criteria, the Nevada Test Site required in 1994 that all treated or
28 untreated waste accepted for disposal at the facility -- regardless of its statutory exempt
29 or non-exempt status -- meet TCLP limits for toxicity-characteristic constituents regulated
30 under RCRA. Based on this disposal-facility-specific requirement, the 1994 OU4 ROD
31 adopted the TCLP limits as quantitative performance standards for treating (in this case
32 vitrifying) the materials prior to off-site disposal.

000015

1 In the 1994 ROD, the RCRA TCLP limits were adopted as performance requirements for
2 waste treatment, due to the requirement that the material meet the Nevada Test Site's
3 formal TCLP-based waste acceptance criteria (versus broader adoption as *applicable*
4 requirements, since the materials continued to retain their statutorily exempt legal status).
5 The Nevada Test Site TCLP limits therefore became the relevant and appropriate
6 performance standard in the 1994 ROD for treating the Silo 3 wastes to achieve an
7 acceptable disposal condition for the four RCRA metals of concern (arsenic, cadmium,
8 chromium, and selenium) contained within the Silo 3 waste.

9 At the time of the 1998 ESD for Silo 3, the Nevada Test Site waste acceptance criteria
10 limits continued to require that all treated and untreated waste accepted for disposal meet
11 the TCLP limits for RCRA regulated constituents (again regardless of the waste's
12 statutorily exempt or non-exempt RCRA status). The 1998 Silo 3 ESD therefore continued
13 to adopt the facility-specific TCLP limits as a performance standard for designing a
14 satisfactory treatment process to render the Silo 3 residues acceptable for off-site
15 disposal.

000016

June 2003

8243

1 **3 BASIS FOR MODIFYING THE OU4 RECORD OF DECISION**

2 Since the Silo 3 ESD was issued in 1998, DOE and EPA have received new information
3 concerning (1) the waste acceptance criteria for the Nevada Test Site disposal facility, and
4 (2) the potential availability of other commercial facilities that can accept the Silo 3
5 residues for disposal as 11e.(2) regulated materials.

6 **3.1 Waste Acceptance Criteria for the Nevada Test Site**

7 In February 2002, the Nevada Test Site, in conjunction with the state and federal
8 regulatory agencies that oversee the facility's waste disposal operations, updated the
9 waste acceptance criteria for the facility. As part of the February 2002 revision, the
10 acceptance requirements for RCRA-regulated materials were clarified. In essence, the
11 revision requires TCLP-based acceptance levels only for those wastes that are statutorily
12 regulated under RCRA. Statutorily exempt materials, such as 11e.(2) materials, no longer
13 need to meet TCLP-based acceptance criteria, provided the waste is otherwise disposed of
14 in a manner that is protective of human health and environment. As part of an eligibility
15 evaluation, a waste profile for each statutorily exempt waste must be reviewed individually
16 to ensure that protective requirements are met for the constituents that would otherwise
17 be regulated under RCRA.

18 During May 2002, Nevada Test Site regulatory personnel completed a draft waste profile
19 review for the statutorily exempt Silo 3 material, and deemed the material to be acceptable
20 for disposal at the facility without the need for further treatment. A letter indicating the
21 eligibility of the untreated Silo 3 material for disposal at the Nevada Test Site was formally
22 issued by the facility in June 2002, a copy of which is included in the technical
23 supplement to the Proposed Plan.

000017

8243

1 **3.2 Emergence of Potential Commercial Disposal Options for DOE 11e.(2) Materials**

2 Also since the time that the 1998 Silo 3 ESD was prepared, potential commercial disposal
3 options have been identified for disposal of untreated Silo 3 material. Similar to the
4 revised waste acceptance criteria requirements at the Nevada Test Site, a commercial
5 facility would be able to accept Silo 3 material in an untreated state provided the material
6 is deemed eligible for disposal by the regulatory agency, a waste-specific profile review is
7 conducted, and all other waste acceptance criteria requirements that are applicable to the
8 waste are met. For purposes of comparison of alternatives in the Proposed Plan, the
9 Envirocare facility, in Clive, Utah was assumed as a representative permitted commercial
10 disposal facility.

11 This new development may result in additional off-site disposal site options for DOE and
12 EPA to consider in evaluating disposal at a protective, appropriately permitted off-site
13 disposal facility as allowed by the 1998 ESD. The actual disposal facility will be selected
14 as part of the design process and may include the Nevada Test Site, an appropriately
15 permitted commercial facility that can accept the materials, or a combination of both. In
16 the Proposed Plan, one option (the Nevada Test Site) was utilized to illustrate the costs
17 and logistics of off-site disposal, and permit a fair comparison of the proposed revised
18 remedy with the 1998 Silo 3 ESD remedy (previous remedy).

19 **3.3 Rationale for Proposed Change**

20 The new information summarized above demonstrates that it is now permissible to
21 permanently dispose of the Silo 3 residues in an untreated form at the Nevada Test Site,
22 and that a commercial facility may also be able to accept the untreated Silo 3 materials in
23 the near future. DOE and EPA conclude based on this new information that the TCLP-
24 based waste treatment performance standard, adopted in both the 1994 ROD and the
25 1998 Silo 3 ESD as a facility-specific criterion for treatment, is no longer necessary for the
26 purposes of maintaining long-term protectiveness and regulatory compliance with disposal
27 facility waste acceptance requirements. DOE and EPA are removing the quantitative
28 TCLP performance standard as a criterion for execution of the Silo 3 remedy.

000018

1 As a result of this new development, members of the public have expressed a concern
2 that if the primary requirement for treatment (to satisfy waste acceptance criteria
3 obligations) is removed through the proposed ROD Amendment, other secondary benefits
4 of waste treatment -- such as the further incremental control of the dispersability of the
5 Silo 3 material, in the unlikely event of a severe transportation accident that subsequently
6 damages the protective shipping containers during transit -- could be overlooked. DOE and
7 EPA have taken these comments into consideration in the development of the modification
8 to the Silo 3 remedy that is proposed in this document. Similarly, DOE and EPA recognize
9 that, irrespective of the recent waste acceptance criteria revision, any new modifications
10 to the remedy must continue to meet the 1×10^{-6} ILCR transportation risk threshold for
11 the remedy adopted by the 1998 Silo 3 ESD.

8243

1 4 **DESCRIPTION OF SIGNIFICANT DIFFERENCES OR NEW ALTERNATIVES**

2 This section describes the revised Silo 3 remedy, and provides a side-by-side comparison
3 with the components of the previous 1998 ESD remedy for Silo 3. The following section
4 then evaluates the revised remedy against the nine criteria specified in the National
5 Contingency Plan. The focus of the description in this section, and the evaluation in the
6 following section, is on that component of the plan that is proposed to be changed,
7 specifically the treatment portion of the remedy. The previous and the revised remedies
8 are summarized below, and compared in detail in the following sections.

9 **Previous 1998 ESD Remedy**

- 10 • Removal of the wastes From Silo 3
- 11 • Treatment, either on site or off site using chemical stabilization/solidification or a
12 polymer-based encapsulation process, to stabilize RCRA-regulated metals to meet RCRA
13 TCLP limits and attain disposal facility waste acceptance criteria
- 14 • If off-site treatment is employed, off-site shipment must be preceded by on-site
15 pretreatment and/or packaging such that the risk to the public from transportation of
16 the material to the off-site facility is less than 1×10^{-6}
- 17 • Off-site disposal at either the Nevada Test Site or a permitted commercial disposal
18 facility
- 19 • Removal and disposal of the Silo 3 structure and the waste handling, packaging, and
20 treatment systems
- 21 • Cleanup of the soil underlying the Silo 3 area to the final remediation levels defined in
22 the Operable Unit 5 ROD.

23 **Revised Remedy**

- 24 • Removal of the wastes from Silo 3 (*this element remains unchanged from the previous*
25 *plan*)
- 26 • Treatment, to the degree reasonably implementable, to address material dispersability
27 and metals mobility. Potential implementability and worker exposure concerns with this
28 treatment are discussed under "Contingency Backup Actions in the next section
29 (*change from the previous plan*).
- 30 • Double packaging of the untreated waste, as a contingency backup, in the event the
31 selected treatment approach is deemed unimplementable as a result of operational
32 difficulties which cannot be practically overcome (*change from the previous plan*)
- 33 • Requirement to maintain the transportation risk to the public of less than 1×10^{-6}
34 Incremental Life-time Cancer Risk [ILCR] (*this element remains unchanged from the*
35 *previous plan*)

000020

June 2003

8243

- 1 • Off-site disposal at either the Nevada Test Site or a permitted commercial disposal
2 facility (*this element remains unchanged from the previous plan*)
- 3 • Removal and disposal of the Silo 3 structure and the waste handling, packaging, and
4 treatment systems (*this element remains unchanged from the previous plan*)
- 5 • Cleanup of the soil underlying the Silo 3 area to the final remediation levels defined in
6 the Operable Unit 5 ROD (*this element remains unchanged from the previous plan*).

7 **4.1 Detailed Description of the Revised Remedy**

8 **Waste Removal.** Under the revised remedy the waste will be removed from Silo 3
9 employing both pneumatic and mechanical systems. These waste retrieval systems
10 remain unchanged from the previous remedy. As a result of the relatively high
11 concentration of thorium-230 (an alpha emitter) and the dry powdery consistency of the
12 waste, special attention will be necessary during design to ensure the construction of
13 waste handling systems, which would minimize the release of particulates from the waste
14 material to the work area or the environment. This same design consideration would be
15 necessary for either the previous or the revised remedy.

16 To address this concern, containment structures and high efficiency air filtration systems
17 will be employed during waste retrieval. A strict radiological control program will be
18 implemented during all Silo 3 operations to reduce worker exposures to As Low As
19 Reasonably Achievable (ALARA) levels.

20 This control program will include engineering controls such as the filtration and
21 containment systems, administrative controls such as project specific training and detailed
22 operational procedures for workers, and personnel protective equipment such as protective
23 clothing and air-supplied respirators. A thorough personnel and environmental monitoring
24 program will also be implemented to assess the effectiveness of the controls.

000021

June 2003

1 **Waste Treatment.** As was the case with the previous remedy, the material will be
2 removed from the silo in its dry form. The previous remedy would require the construction
3 and operation of a chemical stabilization/solidification processing system, which includes
4 the wetting of the material and addition of one or several chemical reagents. With the
5 previous plan, the chemical stabilization/solidification step would involve the addition of
6 sufficient chemical reagents and post-treatment testing to ensure the treated waste form
7 no longer exceeded TCLP limits for the four RCRA-regulated metals (cadmium, arsenic,
8 chromium, and selenium) that are of concern with the Silo 3 materials. Under the revised
9 remedy, this chemical processing system will not be constructed; in its place a system will
10 be installed to add a liquid solution to the dry waste material as it enters the package, in
11 order to reduce the waste's dispersability and mobility.

12 As previously discussed, the acceptance criteria of the Nevada Test Site have been
13 modified to permit receipt of the Silo 3 waste material in an untreated form. The basis for
14 the modified WAC is recognition of the classification of the material as 11e.(2) byproduct
15 material coupled with the material-specific waste profile review and protectiveness
16 evaluation conducted by the Nevada Test Site regulatory personnel. Full compliance with
17 the DOT transportation requirements, Nevada Test Site waste acceptance criteria, and
18 1998 Silo 3 ESD requirements pertaining to the risk during routine transportation (i.e., less
19 than 1×10^{-6} ILCR) can be attained by the direct load out, transport, and disposal of the
20 untreated waste material. Bench scale testing applied to Silo 3 materials has identified a
21 potentially cost-effective and implementable approach to providing a beneficial level of
22 treatment to the waste material prior to off-site transport. These tests yielded
23 encouraging results indicating that a liquid solution could be successfully added to the
24 waste as it was loaded into the packages. The results indicate that a meaningful reduction
25 in the dispersability of the waste can be gained through the addition of the liquid to the
26 waste as it is packaged. Considering these results, it is also anticipated that the addition
27 of a chemical stabilization reagent to this same solution could offer some companion
28 benefits of further reducing the mobility of radioactive and non-radioactive RCRA-regulated
29 metals in the waste.

000022

June 2003

1 As a result of the test data, the DOE has committed to install the necessary process
2 equipment to add a liquid solution to the waste materials as it is delivered into the final
3 packages. This solution is envisioned to include both a liquid reagent to aid in reducing
4 the dispersability of the waste material (a material crusting agent, which also raises the
5 moisture content of the material) in the event of an unforeseen severe accident during
6 transport, and a second component (a chemical stabilization agent) to yield a beneficial
7 reduction in the mobility of some, if not all, of the metals present in the Silo 3 residues.

8 The addition of the additives to treat the waste for dispersability and for metals mobility is
9 being implemented to address concerns expressed by involved stakeholders, and is not a
10 necessary prerequisite to comply with legal ARAR-driven requirements or DOT-driven
11 transportation requirements. As such, the DOE remains committed to applying a "best
12 management practice" effort to ensure the successful addition of the liquid additives to
13 the waste material.

14 The criteria for addition of liquid additives will consist of operational criteria applied in a
15 best management approach (utilizing the final equipment and operational configuration to
16 apply the specified additive formulation). Given the absence of any regulatory requirement,
17 no analytical criteria (e.g., treated waste metals analyses) are necessary part of the best
18 management approach to demonstrate the degree of treatment.

000023

June 2003

1 **Contingency Backup Actions.** As previously stated, the DOE has committed to a best
2 effort to successfully implement the addition of the treatment solution to the waste
3 material on the basis of best-available information gleaned from laboratory-scale studies.
4 As such, significant questions remain on the ability to apply this system in a practical and
5 reliable manner to the full-scale waste packaging system. It is believed that the mock up
6 test program will provide more objective data on the viability of such a treatment system
7 and may provide useful information on the means and methods to overcome any or most
8 operational difficulties created by the addition of the liquid solution. Operability concerns
9 associated with the liquid delivery system which have been identified to date include: (1)
10 plugging of the liquid delivery spray nozzles and/or waste delivery chute; (2) inability to get
11 the treated waste product to effectively fill the packages; (3) pull back of moisture laden
12 air into the screw conveyor causing plugging; (4) difficulties created by the mixture of the
13 two chemical additives into a single solution for delivery to the packaging system; and (5)
14 moisture related caking or binding of filters in the air handling equipment.

15 In the event one or all of these concerns were to materialize during full-scale operations
16 the on-line efficiency, capacity and cost of the remedy would be impacted. For example
17 the plugging of the spray nozzles or the plugging of the conveyor screws would require the
18 shutdown of operations and the performance of intrusive maintenance. Maintenance
19 workers would be required to don fully encapsulating protective clothing and supplied air
20 respirators and then come in direct contact with the waste material. These actions would
21 delay operations and subject workers to potential exposures to thorium bearing material,
22 with resultant schedule and cost increases.

23 DOE will interact with EPA, OEPA, and the involved stakeholders during the future mock
24 up efforts to implement this treatment system. In the event that one or both of the waste
25 additives cannot be practically applied, DOE will consult with the regulatory agencies and
26 involved stakeholders on the details of the operational difficulties. The results of mock up
27 testing, startup, and initial operations will be made available to EPA, OEPA, and other
28 stakeholders, as will adequate opportunity for input to any decision to alter the scope of
29 treatment or to pursue the contingency plan. Regulatory approval will be obtained prior to
30 finalizing such a decision.

000024

June 2003

1 Under the conditions where the costs and/or projected worker exposures associated with
2 the application of one or both of the additives become disproportionate with the potential
3 benefits gained, DOE will cease efforts to apply that portion of the liquid solution to the
4 waste that is causing the operational impediments. If the operational impediments result
5 in the decision to discontinue all steps of the liquid treatment process, then a contingency
6 backup action will be implemented. This contingency action will involve the use of a
7 double packaging system as a backup means to further reduce the potential dispersability
8 of waste material released under a hypothetical severe accident involving material transit.
9 The contingency plan will meet all Remedial Action Objectives, ARARs, and other criteria
10 specified for the Revised Remedy. Upon completion of the previously discussed interaction
11 with the EPA, OEPA, and the public, and receipt of regulatory agency approval, the basis
12 and rationale for the contingency-action decisions will be documented in a formal post-
13 decision memorandum, and will be documented for the public in a Remedial Design Fact
14 Sheet.

15 **Waste Packaging and Shipping.** Once the waste is retrieved from the silo it will be
16 transferred by screw conveyor to a load hopper for direct delivery into the selected
17 packaging configuration. The previously described chemical solution will be added as the
18 waste enters the package.

19 The packaging and mode of transportation remain unchanged from the previous remedy.
20 The soft-sided containers will be placed into steel Sea/Land containers and placed on
21 trucks for off-site transport. Other modes of transportation are available for this same
22 packaging configuration, including direct load onto rail flatbed cars with rail transport to a
23 truck offloading station closer to the disposal facility (intermodal transport) or direct rail
24 transport from the Fernald Closure Project to the disposal facility. The Nevada Test Site
25 can only receive waste containers by truck, therefore only direct truck transport or
26 intermodal transport with offloading from rail to truck is acceptable for disposal at this
27 location. In the event rail transport were to be implemented as the mode of
28 transportation, dedicated unit trains would be used to the maximum extent practical.

000025

June 2003

1 **Waste Disposal** This component of the remedy remains unchanged from the 1998 Silo 3
2 ESD remedy. Although the remedy will continue to allow disposal at either the Nevada
3 Test Site or an appropriately permitted commercial disposal facility, a representative waste
4 transportation mode (truck transport) and disposal location (Nevada Test Site was utilized
5 as the representative option for comparison and costing in the Proposed Plan.

6 During the design and implementation of the Silo 3 remedy, DOE will select the
7 transportation mode(s) and compliant disposal location(s) that provide the best overall
8 balance of reduced transportation risk and cost effectiveness. Only disposal facilities that
9 meet the regulatory compliance requirements of the CERCLA off-site rule (40 CFR
10 300.440) will be considered.

11 **Silo Demolition and Soil Cleanup.** This component of the remedy remains unchanged
12 from the 1998 Silo 3 ESD remedy. This Silo 3 structure will be demolished with the debris
13 properly disposed of in the On-site Disposal Facility or off site at the Nevada Test Site or
14 an appropriately permitted commercial disposal facility. Contaminated soil underlying the
15 facility will be cleaned up to achieve the final remediation levels in the Operable Unit 5
16 ROD.

17 The excavated soil will be disposed of in the On-site Disposal Facility (or off site, as
18 appropriate) depending on whether the On-site Disposal Facility waste acceptance criteria
19 levels for the contaminated soil are met.

5 EVALUATION OF ALTERNATIVES

Comparative evaluations of the revised Silo 3 remedy and the Silo 3 ESD remedy (previous remedy) were conducted employing the nine evaluation criteria defined in the National Contingency Plan as the framework for identifying technical and administrative differences between the alternate plans.

The first two evaluation criteria -- overall protection of human health and the environment and compliance with ARARs -- are considered threshold criteria that must be attained by the selected remedial action. The next five criteria include short-term protectiveness, long-term effectiveness and permanence, reduction of toxicity, mobility, or volume through treatment, implementability, and cost.

These criteria are considered primary balancing criteria, which are looked at collectively to arrive at the best overall solution that offers the best balance of tradeoffs among the criteria. The final two criteria -- state acceptance and community acceptance -- are evaluated following receipt of comments on the Proposed Plan, and are incorporated, as appropriate, into the final remedy selection in the ROD Amendment.

The OU4 FS, PP, ROD, and Silo 3 ESD documented a detailed evaluation of a full range of alternatives against these same criteria to arrive at the selected previous remedy contained in the 1998 Silo 3 ESD. The discussion in this section therefore focuses on a specific comparative analysis for the two alternative Silo 3 remedies, aimed at those components that are different.

In addition to the nine criteria comparative analysis, Section 121 of CERCLA and the NCP (40 CFR 300.430) require that the remedy selection process consider and address a statutory preference for remedies that employ treatment to permanently and significantly reduce the volume, toxicity, or mobility of hazardous constituents as a principal element.

The DOE and EPA are required to reach a finding in the proposed amendment to the ROD documenting whether the selected remedy satisfactorily fulfills this statutory preference. This statutory preference is addressed in Section 6 of this ROD Amendment.

000027

June 2003

1 As part of the original RI/FS for OU4, formal remedial action objectives were identified to
2 guide the overall remedial action alternative development and evaluation process. The
3 original remedial action objectives for the cleanup of the Silo 3 residues as defined in the
4 OU4 FS Report are:

- 5 • Prevent direct contact with or ingestion of Silo 3 material
- 6 • Prevent release or migration of waste materials to soil, groundwater, surface water or
7 sediment
- 8 • Prevent exposures to Silo 3 material that may cause an individual to exceed applicable
9 dose limits.

10 These original remedial objectives remained unchanged in the 1998 Silo 3 ESD and are
11 again being maintained as the basis for the revised remedy. The revised remedy was
12 developed fully considering these formal remedial action objectives.

13 **5.1 Threshold Criterion No. 1: Overall Protection of Human Health and the Environment**

14 Both the previous and the revised remedies provide for the protection of human health and
15 the environment by removing the high concentration waste residues from the site and
16 properly disposing of them at the Nevada Test Site or a permitted commercial disposal
17 facility. Off-site disposal will be conducted in accordance with the waste acceptance
18 criteria for the receiving facility. The representative disposal facility selected for purposes
19 of evaluating the alternate remedies is the Nevada Test Site. The Nevada Test Site
20 incorporates engineering and institutional controls into the facility design and is situated in
21 a climatic, demographic, and hydrogeologic setting that minimizes the potential for
22 exposures to human or environmental receptors. The licensing process for a permitted
23 commercial disposal facility ensures a similar level of protectiveness to the Nevada Test
24 Site through the location, design, and acceptance criteria of the disposal facility.

1 The Nevada Test Site waste acceptance criteria establishes a set of requirements that
2 must be fulfilled to permit acceptance of a waste stream for safe, protective disposal. DOE
3 submitted a draft profile to the Nevada Test Site describing the untreated Silo 3 residues
4 and has gained approval of the waste steam for disposal at the facility. This approval by
5 the Nevada Test Site was in part based upon a review of the characteristics of the Silo 3
6 waste and a determination that the disposal of the material untreated would provide a
7 compliant, protective, and permanent disposal solution. A final waste profile must be
8 submitted to the Nevada Test Site prior to shipping the Silo 3 waste. A copy of the
9 general acceptance letter from the Nevada Test Site is provided in the supplement to the
10 Proposed Plan.

11 Both remedies specify that all surrounding soil will be excavated to meet the final
12 remediation levels in the Operable Unit 5 ROD. The residual risk that will remain at the
13 site following completion of the remedial action is consistent with that described in the
14 original Operable Unit 4 Feasibility Study and would remain unchanged by the
15 implementation of the revised remedy. This residual risk would be expected to be in the
16 range of 10^{-6} to the undeveloped park user as described in the Operable Unit 5 Feasibility
17 Study and ROD.

18 **5.2 Threshold Criterion No. 2: Compliance with ARARs**

19 Both the previous and the revised remedies will attain compliance with ARARs. The
20 ARARs identified in the Operable Unit 4 Feasibility Study and 1994 ROD, and were not
21 changed by the 1998 ESD for Silo 3, and have been maintained as the criteria for the
22 evaluation documented in this ROD Amendment. One requirement has been revised since
23 issuance of the Silo 3 ESD -- the selection of the RCRA TCLP limits as a quantitative
24 performance requirement for treatment of the Silo 3 waste. As described earlier, as a
25 result of a change in the waste acceptance criteria for the Nevada Test Site, the RCRA-
26 regulated metals in the waste no longer need to be treated to attain TCLP levels as a
27 necessary condition for waste acceptance. As a result of this changed condition, the
28 application of this former requirement is no longer considered a relevant criteria for the Silo
29 3 remedy. With this change, the revised remedy will attain all identified ARARs, and

1 performance criteria. A detailed compilation of the ARARs for the revised Silo 3 remedy is
2 provided in Appendix A of this ROD Amendment.

3 **5.3 Balancing Criterion No. 1: Long-term Effectiveness and Permanence**

4 The previous remedy and the revised remedy both provide a remedy that is effective in the
5 long term and a permanent solution for the Silo 3 wastes. Both alternatives provide for
6 the removal of the Silo 3 waste from the site and the cleanup of any contaminated soil
7 from the silo area. The waste will be shipped from the site and disposed of at an off-site
8 facility in full compliance with the waste acceptance criteria and any relevant licensing
9 restrictions for the receiving facility. The design of these facilities, in concert with their
10 waste acceptance criteria and regional climatic, demographic, and hydrogeologic setting
11 provide a waste disposal solution that is both effective in the long term and permanent.

12 The previous remedy provides an incremental increase in long-term effectiveness by
13 including treatment to the TCLP levels as a performance requirement of the remedy. The
14 revised remedy includes the application of a binding agent and a stabilizing reagent to the
15 waste, which is expected to provide a meaningful level of reduction in both the
16 dispersability of the packaged waste and the leachability of the metals. It is not
17 anticipated or expected that the application of this treatment approach will fully reduce the
18 leachability of the four RCRA regulated metals of concern within the Silo 3 waste (arsenic,
19 selenium, chromium, and cadmium) to below TCLP levels in all cases. The additional
20 incremental reduction in metals leachability provided by the previous remedy over and
21 above that anticipated by the proposed approach is not considered significant relative to
22 health-based thresholds, in that the mobility of nonradioactive metals in the incoming
23 waste is already a consideration in the siting, design, and health-protective acceptance
24 criteria for the receiving disposal facilities. The Silo 3 waste will be disposed in the off-
25 site facilities with other byproduct or low level radioactive wastes shipped by other
26 generators with similar characteristics to those exhibited by the treated or untreated cold
27 metal oxides in the silo. Adherence to the waste acceptance requirements of the receiving
28 disposal facility ensures full compliance with prevailing state and federal environmental

1 and health protection regulations governing the long-term performance of these waste
2 disposal systems.

3 As previously discussed, any identified contaminated soil in the area of Silo 3 will be
4 cleaned up to attain the final remediation levels in the Operable Unit 5 ROD, consistent
5 with other areas of the Fernald site. These cleanup levels were developed to help ensure
6 the long-term protectiveness and permanence of the Fernald cleanup. These cleanup
7 levels were set following a consensus building process that involved the DOE, regulatory
8 agencies, and the community. These cleanup levels have been designed to provide a site-
9 wide remedy that will reduce the residual risk following cleanup to the range of 10^{-6} to the
10 undeveloped park user. The detailed exposure assumptions underlying this risk analysis
11 can be found in the Operable Unit 5 Feasibility Study and ROD.

12 **5.4 Balancing Criterion No. 2: Reduction of Toxicity, Mobility, or Volume Through**
13 **Treatment**

14 Both the previous and the proposed remedies provide for treatment of the waste materials
15 prior to disposal at the Nevada Test Site or a permitted commercial disposal location. The
16 previous plan would provide some incremental decrease in the mobility of the waste over
17 that provided by the revised remedy.

18 This incremental additional decrease is not considered significant for health or
19 environmental reasons and is not required to comply with the acceptance criteria of the
20 receiving facility. The chemical stabilization approach envisioned under the previous plan
21 would provide for an increase (approximately 50 percent) in volume over the revised plan
22 due to the type and quantity of waste additives necessary to ensure attainment of the
23 TCLP limits imposed under the previous remedy. The revised plan contemplates the
24 addition of waste additives to the degree attainable in a practical and implementable
25 manner. Bench scale studies demonstrated that a dilute lignosulfonate solution could be
26 effectively added to the waste as it enters the packages to reduce the dispersability of the
27 material. These tests were aimed at adding the lignosulfonate solution to the waste such
28 that the moisture content of the waste was increased by up to 20 percent. These bench
29 tests proved successful and DOE has committed to applying this system in the revised

000031

June 2003

1 remedy. A second chemical reagent, aimed at reducing the leachability of the
2 nonradioactive metals, is also planned to be applied to the waste through the same
3 delivery system. The operability of such a waste additive and liquid delivery system at full
4 scale is not yet proven. As previously discussed, the DOE will make a best effort to
5 ensure the success of the process. In the event the process cannot be applied at full
6 scale, DOE will first attempt to modify or, if need be, eliminate one or both of the additives
7 in the liquid delivery system, if that is the source of the interference. As the next step, in
8 the event the liquid delivery system cannot be successfully operated at all (with or without
9 additives), the contingency action will be implemented following the regulatory and
10 stakeholder consultation process previously described. Under the contingency action, a
11 backup double packaging requirement will be imposed as a tradeoff for elimination of the
12 liquid delivery step.

13 5.5 Balancing Criterion No. 3: Short-term Effectiveness

14 The National Contingency Plan identifies the considerations for which the short-term
15 effectiveness criterion should be evaluated as risks to the community during
16 implementation of the alternative, potential impacts to workers during remedial actions,
17 potential environmental impacts during implementation, and time until protection is
18 achieved. Overall, this criterion favors the revised remedy due to its advantages in worker
19 risk and implementation schedule.

20 Due to the dispersible nature and high thorium-230 content of the Silo 3 material, a
21 primary short-term effectiveness issue is the potential for worker exposures due to Silo 3
22 material becoming airborne during retrieval, processing, and packaging. Equipment and
23 operational controls, such as ventilation through dust collection equipment, dust control
24 measures during bulk retrieval, and contamination control practices, must be implemented
25 at each unit operation to minimize the risk of worker exposure to airborne Silo 3 material.
26 These considerations would be designed into the waste handling systems of both the
27 current and revised remedies.

000032

June 2003

key consideration in the analysis of the short-term effectiveness of the two remedies is the risks attributable to the transportation of the packaged materials to the off-site disposal facility.

A detailed transportation risk analysis was completed evaluating the potential risks associated with routine (no accidents) waste transportation and to hypothetical accident scenarios for both the previous and the revised remedies. The following table presents the results of the transportation risk analysis.

RESULTS OF THE TRANSPORTATION RISK ANALYSIS

	Previous Remedy Routine Transport ILCR	Revised Remedy Routine Transport ILCR
Truck to NTS	8.3×10^{-10}	1.8×10^{-9}
Rail to Ecare	2.9×10^{-10}	4.4×10^{-10}
	Previous Remedy Accident Scenario ILCR	Revised Remedy Accident Scenario ILCR
Truck to NTS	3.1×10^{-11}	4.4×10^{-8}
Rail to Ecare	1.6×10^{-10}	2.3×10^{-7}

Additional details concerning the assumptions, methodology, and results of the analysis are documented in the Silo 3 Proposed Plan.

These risk estimates compare favorably to the criteria of being below a risk of 1×10^{-6} ILCR for routine transportation established by the 1998 Silo 3 ESD. The calculated risk attributable to the revised remedy is slightly higher than the previous remedy due to the increased waste loading in the shipping containers resulting in higher direct radiation levels on the outside of the package.

1 **5.7 Balancing Criterion No. 5: Cost**

2 A detailed cost evaluation of the previous and revised remedies is documented in the
3 Proposed Plan for Silo 3 and detailed in the Supplement to the Proposed Plan. The
4 accuracy of both estimates is considered +50/-30 percent, consistent with CERCLA
5 guidance. For purposes of comparative analysis, treated waste is assumed to be shipped
6 by truck to the Nevada Test Site for each alternative. The following summarizes the major
7 cost elements for the previous plan and the revised remedy alternatives. Costs associated
8 with the D&D of the Silo 3 structure have not been included. Similarly, the costs for
9 addressing any contaminated soil in the Silo 3 area have been excluded from both options.

Summary Cost Data (\$ Million)		
Alternative	Previous Cleanup Plan	Revised Cleanup Plan
Capital Cost	20.0	14.0
Engineering, Proj. Mgmt., Const. Mgmt. and Startup Cost	15.0	15.0
Operation and Maintenance Cost	7.0	4.0
Transportation and Disposal Cost	11.0	7.0
D&D Cost	2.0	2.0
Total Cost	55.0	42.0

10 Due to the incremental life-cycle costs of providing treatment to stabilize arsenic,
11 cadmium, chromium, and selenium to achieve TCLP limits, the estimated cost for the
12 previous remedy is estimated at \$13 million greater than the revised plan. These
13 incremental costs include additional capital costs to support the installation of the
14 chemical stabilization system, increased operational costs attributable to additional staff
15 and analytical demand, and increased shipping costs due to the almost 50 percent
16 increase in volume to be shipped under the previous remedy.

000034

1 It should be noted that the difference between the two alternatives (\$13 million) is within
2 the errors expected from estimating (plus 50 percent, minus 30 percent), and therefore
3 should not be heavily relied upon in decision making. While a more precise estimate of the
4 cost differences between the two alternate remedies cannot be made without the benefit
5 of more detailed engineering, it can be reasonably expected that the cost to implement the
6 previous remedy will be higher than that to implement the revised plan. These added
7 costs would be attributable to the added design, construction, operation and demolition
8 scope associated with the more complex treatment approach dictated by the previous
9 remedy.

10 **5.8 Modifying Criterion No. 1: State Acceptance**

11 The OEPA has had an opportunity to review and participate in the revision of the Silo 3
12 remedy and concurs with the revised remedy.

13 **5.9 Modifying Criterion No. 2: Community Acceptance**

14 DOE's recommendation to implement the revised remedy for Silo 3 was documented in the
15 Proposed Plan for Silo 3, which was made available for public comment from April 30,
16 2003 through May 30, 2003. A public hearing was held in the vicinity of the Fernald
17 Closure Project on May 13, 2003. DOE and EPA have considered comments provided by
18 the community in making the final alternative selection documented in this ROD
19 Amendment. Comments received during the public comment period are addressed in the
20 Responsiveness Summary, contained in Appendix B of this ROD Amendment.

6 STATUTORY DETERMINATIONS

The NCP [40 CFR Section 300.430(f)(5)(ii)] specifies that a ROD shall describe the following statutory requirements as they relate to the scope and objectives of the action:

- How the selected remedy is protective of human health and the environment;
- How the remedy will comply with all ARARs established under federal and state environmental laws (or justify a waiver);
- How the remedy is cost-effective (i.e., provides overall effectiveness proportional to its costs);
- How the remedy will use permanent solutions and alternative technologies or recovery technologies to the maximum extent practicable; and
- How the remedy will satisfy the statutory preference for remedies that employ treatment that permanently and significantly reduces the toxicity, mobility, or volume of the hazardous substances, pollutants, or contaminants as a principle element, or if it is not satisfied, explain why a remedy providing reductions in toxicity, mobility, or volume was not selected.

In addition, CERCLA requires five year reviews to determine if adequate protection of human health and the environment is being maintained where RAs result in hazardous substances remaining on-site. A discussion is provided below of how the revised remedy for Silo 3 satisfies these statutory requirements.

6.1 Protection of Human Health and the Environment

The revised remedy achieves the requirement of being protective of human health and the environment by: (1) removing the sources of contamination, (2) treating, to the extent reasonably technically feasible, the materials giving rise to the principle threats from Silo 3 (3) disposing of treated materials at an off-site location that provides the appropriate level of protectiveness; and (4) remediating contaminated soils and debris to protective levels. The contents of Silo will be removed, treated to the extent reasonably implementable to reduce the dispersability and mobility of contaminants, and transported in a protective manner to an offsite facility for disposal. The location, design, and waste acceptance criteria of the offsite disposal facility will assure that the disposal of the Silo 3 material

000036

June 2003

1 provides long-term protection of human health and the environment. Concrete from the
2 Silo 3 structure and the associated remediation facilities will be removed from OU4 and
3 disposed of in a manner consistent with the approved OU3 ROD. Contaminated soil will
4 also be removed and disposed in a manner consistent with the approved OU5 ROD.

5 Baseline cancer risks from current conditions exceed the 10^{-4} to 10^{-6} acceptable risk range.
6 Under the future land use scenario of continued federal ownership, the residual cancer risk
7 from Silo 3 will be reduced to less than 1×10^{-6} . There are no short-term threats
8 associated with the selected remedy that cannot be readily controlled. In addition, no
9 adverse cross-media impacts are expected from the remedy.

10 **6.2 Compliance with ARARs**

11 The revised remedy for Silo 3 will comply with all ARARs. As described earlier, as a
12 result of a change in the waste acceptance criteria for the Nevada Test Site, the RCRA-
13 regulated metals in the waste no longer need to be treated to attain TCLP levels as a
14 necessary condition for waste acceptance. As a result of this changed condition, the
15 application of this former requirement is no longer considered a relevant criteria for the Silo
16 3 remedy. With this change, the revised remedy will attain all ARARs and performance
17 criteria identified for the Silo 3 remedy. A detailed compilation of the ARARs for the
18 revised Silo 3 remedy is provided in Appendix A of this ROD Amendment.

19 **6.3 Cost Effectiveness**

20 DOE has determined that the revised remedy for Silo 3 has costs that are proportional to
21 the overall effectiveness of the remedy. Therefore, the revised remedy meets the
22 statutory requirement for cost effectiveness, as defined by the NCP [40 CFR
23 300.430(f)(1)(ii)(D)].

000037

June 2003

8243

1 **6.4 Utilization of Permanent Solutions and Alternative Treatment Technologies of**
2 **Resource Recovery Technologies to the Maximum Extent Practicable**

3 DOE has determined, with the concurrence of the EPA and the OEPA, that the revised
4 remedy for Silo 3 represents the maximum extent to which permanent solutions and
5 treatment technologies can be used in a cost-effective manner. Of the alternatives that
6 are protective of human health and the environment and comply with ARARs, DOE has
7 determined that this selected remedy provides the best balance of tradeoffs among the
8 alternatives in terms of long-term effectiveness and permanence, reduction in toxicity,
9 mobility, or volume through treatment, short-term effectiveness, implementability, and
10 cost. As documented in the next section, the revised remedy also meets the statutory
11 preference for treatment as a principle element.

12 **6.5 Preference for Treatment as a Principal Element**

13 Under Section 121 of CERCLA, DOE and EPA are required to reach a finding for the that
14 the selected remedial alternative satisfies a statutory preference for remedies that employ
15 treatment to permanently and significantly reduce the volume, toxicity, or mobility of
16 hazardous constituents as a principal element. The finding is to be made through the
17 detailed comparison of the two alternatives, considering site-specific factors and the five
18 primary balancing criteria specified by the NCP (40 CFR 300.430).

19 On the basis of the detailed comparisons described above, DOE and EPA conclude that the
20 modified Silo 3 treatment process satisfactorily achieves the statutory preference for
21 treatment as a principal element and provides sufficient additional risk reduction in relation
22 to cost. If the treatment step cannot be satisfactorily implemented due to overriding
23 technical or short-term worker risk impediments, then the formal contingency action
24 (additional double packaging of materials in the protective shipping containers) is also
25 deemed to provide an appropriate balance of risk reduction, effectiveness, and cost to
26 satisfy Section 121 requirements and preferences under the site-specific circumstances
27 giving rise to the need for the contingency action.

000038

June 2003

8243

1 **6.6 National Environmental Policy Act**

2 In the original ROD for OU4 DOE chose to complete an integrated CERCLA/NEPA process.
3 This decision was based on the longstanding interest on the part of local stakeholders to
4 prepare an Environmental Impact Statement (EIS) on the restoration activities at the FEMP
5 and on the recognition that the draft document was issued and public comments received.
6 Therefore, the document served as DOE's ROD for OU4 under both CERCLA and NEPA;
7 however, it is not the intent of the DOE to make a statement on the legal applicability of
8 NEPA to CERCLA actions.

9 Four Supplemental Analyses have been prepared evaluating changes to the original OU4
10 FS/PP EIS:

- 11 • January 9, 1996, evaluating shipping material for disposal via truck as opposed to the
12 combination of rail/truck evaluated in the OU4 FS/PP-EIS.
- 13 • August 20, 1996 evaluating the Silo 3 remediation alternatives, including on-site
14 treatment with disposal at the NTS or a PCDF, and transportation of untreated Silo 3
15 material to an off-site facility.
- 16 • March 3, 1998 evaluating Accelerated Waste Retrieval of the Silos 1 and 2 material.
- 17 • March 13, 2000 considering of alternatives for the remediation of the Silos 1 and 2
18 material.

19 No additional impacts were identified as a result of these reevaluations, and in each case,
20 DOE determined that no additional NEPA evaluation or documentation was required.

21 The change documented in the ROD Amendment is bounded by the alternatives evaluated
22 in the original FS/PP/EIS and the subsequent Supplemental Analyses. Therefore, it is DOE's
23 determination that potential NEPA issues associated with the change have been
24 adequately evaluated and that no additional NEPA documentation or evaluation is
25 necessary.

8243

APPENDIX A

**APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS
AND TO BE CONSIDERED REQUIREMENTS
FOR SILO 3 REMEDIAL ACTION**

000041

8243

TABLE A-1
ARARS FOR SILO 3 REMEDIAL ACTION
CHEMICAL-SPECIFIC

Medium	Clean Air Act (CAA)	Requirement	ARAR/TBC	Rationale for Implementation
Air	Radionuclide Emissions (Except Airborne Radon-222), 40 CFR Part 61 Subpart H.	<p>Emissions of radionuclides to the ambient air from DOE facilities shall not exceed those amounts that might cause any member of the public to receive, in any year, an effective dose equivalent (EDE) of 10 mrem or greater per year.</p> <p>Monitoring is required at release points having potential to discharge radionuclides that could cause an EDE in excess of 1% of the standard (0.1 mrem/yr) to any member of the public.</p>	Applicable	Radioactive materials within Silo 3 could contribute to the dose received by members of the public from the air pathway during implementation of Silo 3 remedial actions.
Air	Radon-222 Emissions, 40 CFR Part 61 Subpart Q.	No source at a DOE facility shall emit more than 20 pCi/m ³ s of radon-222 as an average for the entire source during periods of storage and disposal.	Applicable	A 'source' is defined by NESHAP Subpart Q as 'any building, structure, pile, or impoundment used for interim storage or disposal that is or contains waste material containing radium in sufficient concentration to emit radon-222 in excess of this standard prior to remedial action.' Temporary staging of Silo 3 material during the process of packaging and transportation to the disposal facility does not constitute a 'source' for the purposes of this standard. This standard is applicable to the facility used for disposal of the Silo 3 material.

000042

8243

TABLE A-1 (Continued)

Medium	DOE (continued)	Requirement	ARAR/TBC	Rationale for Implementation																																		
Air	Residual Radioactive Material, DOE Order 5400.5 Chap. IV, 6.b (proposed 10 CFR Part 834).	<p><u>Interim Storage</u> The above-background concentration of radon-222 in air above an interim storage facility must not exceed: 100 pCi/L at any point, an annual average of 30 pCi/L over the facility, or an annual average of 0.5 pCi/L above background or above any location outside the site.</p>	To be considered	Management of radium and thorium bearing waste might result in the release of radon gas to the environment.																																		
Water	Radiation Protection of the Public and the Environment, Proposed 10 CFR Part 834.	<p>Residual concentrations of radionuclides in water that may be ingested are listed below. These DCGs for the COCs are based on a committed EDE of 100 mrem/yr, assuming ingestion of 2 liters/day. Note that these DCGs apply only if ingestion is the single pathway of exposure.</p> <p style="text-align: center;">Ingested Water DCGs ($\mu\text{Ci/mL}$)</p> <table border="1"> <thead> <tr> <th>Isotope</th> <th>DCG ($\mu\text{Ci/mL}$)</th> </tr> </thead> <tbody> <tr><td>Actinium-227</td><td>1×10^{-8}</td></tr> <tr><td>Lead-210</td><td>3×10^{-8}</td></tr> <tr><td>Polonium-210</td><td>8×10^{-8}</td></tr> <tr><td>Protactinium-231</td><td>1×10^{-8}</td></tr> <tr><td>Radium-224</td><td>4×10^{-7}</td></tr> <tr><td>Radium-226</td><td>1×10^{-7}</td></tr> <tr><td>Radium-228</td><td>1×10^{-7}</td></tr> <tr><td>Technetium-99</td><td>1×10^{-4}</td></tr> <tr><td>Strontium-90</td><td>1×10^{-6}</td></tr> <tr><td>Thorium-228</td><td>4×10^{-7}</td></tr> <tr><td>Thorium-230</td><td>3×10^{-7}</td></tr> <tr><td>Thorium-232</td><td>5×10^{-8}</td></tr> <tr><td>Uranium-234</td><td>5×10^{-7}</td></tr> <tr><td>Uranium-235</td><td>6×10^{-7}</td></tr> <tr><td>Uranium-236</td><td>5×10^{-7}</td></tr> <tr><td>Uranium-238</td><td>6×10^{-7}</td></tr> </tbody> </table>	Isotope	DCG ($\mu\text{Ci/mL}$)	Actinium-227	1×10^{-8}	Lead-210	3×10^{-8}	Polonium-210	8×10^{-8}	Protactinium-231	1×10^{-8}	Radium-224	4×10^{-7}	Radium-226	1×10^{-7}	Radium-228	1×10^{-7}	Technetium-99	1×10^{-4}	Strontium-90	1×10^{-6}	Thorium-228	4×10^{-7}	Thorium-230	3×10^{-7}	Thorium-232	5×10^{-8}	Uranium-234	5×10^{-7}	Uranium-235	6×10^{-7}	Uranium-236	5×10^{-7}	Uranium-238	6×10^{-7}	To be considered	Remediation of the Silo 3 material has the potential to release radionuclides.
Isotope	DCG ($\mu\text{Ci/mL}$)																																					
Actinium-227	1×10^{-8}																																					
Lead-210	3×10^{-8}																																					
Polonium-210	8×10^{-8}																																					
Protactinium-231	1×10^{-8}																																					
Radium-224	4×10^{-7}																																					
Radium-226	1×10^{-7}																																					
Radium-228	1×10^{-7}																																					
Technetium-99	1×10^{-4}																																					
Strontium-90	1×10^{-6}																																					
Thorium-228	4×10^{-7}																																					
Thorium-230	3×10^{-7}																																					
Thorium-232	5×10^{-8}																																					
Uranium-234	5×10^{-7}																																					
Uranium-235	6×10^{-7}																																					
Uranium-236	5×10^{-7}																																					
Uranium-238	6×10^{-7}																																					

000043

8243

TABLE A-1 (Continued)

Medium	CWA	Requirement	ARAR/TBC	Rationale for Implementation																																										
Water	Ohio Water Quality Standards, Ohio Administrative Code (OAC) 3745-1-04.	<p>"Five Freedoms" for surface water:</p> <p>Surface waters of the state shall be free from:</p> <ul style="list-style-type: none"> • objectionable suspended solids; • floating debris, oil and scum; • materials that create a nuisance; • toxic, harmful or lethal substances; and • nutrients that create nuisance growth. <p><u>Use Designations and Criteria</u></p> <p>All pollutants or combinations of pollutants shall not exceed, outside the mixing zone, the Numerical and Narrative Criteria for Aquatic Life Habitat and Water Supply Use Designations listed in Tables 7-1 through 7-15 of this rule.</p> <p>The following constituents of concern (COCs) for Operable Unit 4 have warm water habitat criteria concentrations outside the mixing zone as follows:</p> <table border="1"> <thead> <tr> <th>30-day Constituent</th> <th>average conc.^a (ug/l)</th> <th>conc. (ug/l)</th> </tr> </thead> <tbody> <tr><td>antimony</td><td>650</td><td>190</td></tr> <tr><td>arsenic</td><td>360</td><td>190</td></tr> <tr><td>beryllium</td><td>Tab. 7-10^b</td><td>Tab. 7-11^c</td></tr> <tr><td>cadmium</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>chromium</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>copper</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>cyanide</td><td>46</td><td>12</td></tr> <tr><td>lead</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>mercury</td><td>1.1</td><td>0.20</td></tr> <tr><td>nickel</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>selenium</td><td>20</td><td>5.0</td></tr> <tr><td>silver</td><td>Tab. 7-10</td><td>1.3</td></tr> <tr><td>thallium</td><td>71</td><td>16</td></tr> </tbody> </table>	30-day Constituent	average conc. ^a (ug/l)	conc. (ug/l)	antimony	650	190	arsenic	360	190	beryllium	Tab. 7-10 ^b	Tab. 7-11 ^c	cadmium	Tab. 7-10	Tab. 7-11	chromium	Tab. 7-10	Tab. 7-11	copper	Tab. 7-10	Tab. 7-11	cyanide	46	12	lead	Tab. 7-10	Tab. 7-11	mercury	1.1	0.20	nickel	Tab. 7-10	Tab. 7-11	selenium	20	5.0	silver	Tab. 7-10	1.3	thallium	71	16	Relevant and Appropriate	Pertains to discharges to surface waters as a result of remediation and to on-site surface waters affected by site conditions.
30-day Constituent	average conc. ^a (ug/l)	conc. (ug/l)																																												
antimony	650	190																																												
arsenic	360	190																																												
beryllium	Tab. 7-10 ^b	Tab. 7-11 ^c																																												
cadmium	Tab. 7-10	Tab. 7-11																																												
chromium	Tab. 7-10	Tab. 7-11																																												
copper	Tab. 7-10	Tab. 7-11																																												
cyanide	46	12																																												
lead	Tab. 7-10	Tab. 7-11																																												
mercury	1.1	0.20																																												
nickel	Tab. 7-10	Tab. 7-11																																												
selenium	20	5.0																																												
silver	Tab. 7-10	1.3																																												
thallium	71	16																																												
Water	Ohio Water Quality Standards, OAC 3745-1-07.	<p><u>Use Designations and Criteria</u></p> <p>All pollutants or combinations of pollutants shall not exceed, outside the mixing zone, the Numerical and Narrative Criteria for Aquatic Life Habitat and Water Supply Use Designations listed in Tables 7-1 through 7-15 of this rule.</p> <p>The following constituents of concern (COCs) for Operable Unit 4 have warm water habitat criteria concentrations outside the mixing zone as follows:</p> <table border="1"> <thead> <tr> <th>30-day Constituent</th> <th>average conc.^a (ug/l)</th> <th>conc. (ug/l)</th> </tr> </thead> <tbody> <tr><td>antimony</td><td>650</td><td>190</td></tr> <tr><td>arsenic</td><td>360</td><td>190</td></tr> <tr><td>beryllium</td><td>Tab. 7-10^b</td><td>Tab. 7-11^c</td></tr> <tr><td>cadmium</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>chromium</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>copper</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>cyanide</td><td>46</td><td>12</td></tr> <tr><td>lead</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>mercury</td><td>1.1</td><td>0.20</td></tr> <tr><td>nickel</td><td>Tab. 7-10</td><td>Tab. 7-11</td></tr> <tr><td>selenium</td><td>20</td><td>5.0</td></tr> <tr><td>silver</td><td>Tab. 7-10</td><td>1.3</td></tr> <tr><td>thallium</td><td>71</td><td>16</td></tr> </tbody> </table>	30-day Constituent	average conc. ^a (ug/l)	conc. (ug/l)	antimony	650	190	arsenic	360	190	beryllium	Tab. 7-10 ^b	Tab. 7-11 ^c	cadmium	Tab. 7-10	Tab. 7-11	chromium	Tab. 7-10	Tab. 7-11	copper	Tab. 7-10	Tab. 7-11	cyanide	46	12	lead	Tab. 7-10	Tab. 7-11	mercury	1.1	0.20	nickel	Tab. 7-10	Tab. 7-11	selenium	20	5.0	silver	Tab. 7-10	1.3	thallium	71	16	Relevant and Appropriate	Pertains to discharges to surface waters as a result of remediation and to on-site surface waters affected by site conditions.
30-day Constituent	average conc. ^a (ug/l)	conc. (ug/l)																																												
antimony	650	190																																												
arsenic	360	190																																												
beryllium	Tab. 7-10 ^b	Tab. 7-11 ^c																																												
cadmium	Tab. 7-10	Tab. 7-11																																												
chromium	Tab. 7-10	Tab. 7-11																																												
copper	Tab. 7-10	Tab. 7-11																																												
cyanide	46	12																																												
lead	Tab. 7-10	Tab. 7-11																																												
mercury	1.1	0.20																																												
nickel	Tab. 7-10	Tab. 7-11																																												
selenium	20	5.0																																												
silver	Tab. 7-10	1.3																																												
thallium	71	16																																												

000044

8243

TABLE A-1 (Continued)

Water	Ohio Water Quality Standards, OAC 3745-1-07 (continued).	30-day Criteria Constituent	average conc. ^a (ug/l)	conc. (ug/l)
		zinc	7100	
		30-day Criteria Constituent	average conc. ^a (ug/l)	conc. (ug/l)
		2-butanone	160000	
		4-nitrophenol	790	35
		acetone	550000	78000
		aldrin	---	0.01
		bis(2-ethylhexyl) phthalate	1100	
		carbon tetrachloride	1800	280
		DDT	---	0.001
		Dieldrin	---	0.005
		di-n-butyl-phthalate	350	
		diethylphthalate	2600	120
		dimethylphthalate	1700	73
		endosulfan ^d	---	0.003
		endrin	---	0.002
		fluoranthene	200	8.9
		methylene chloride	9700	430
		PCBs	---	0.001
		phenol	5300	370
		tetrachloroethene	540	73
		toluene	2400	1700

^a Criteria concentration shall be met outside mixing zone.
^b Criteria concentration based on hardness of water. See Table 7-10 for calculation to determine maximum concentration outside the mixing zone.
^c 30-day average criteria based on hardness of water. See Table 7-11 for calculation to determine allowable 30-day average concentration outside the mixing zone.
^d No designation was made as to whether endosulfan I or endosulfan II or the sum total of each.

The remaining COCs for OU4 will have criteria concentration levels based on calculated acute aquatic criteria or chronic aquatic criteria.

8243

TABLE A-2
ARARS FOR SILO 3
REMEDIAL ACTION, LOCATION-SPECIFIC

NEPA/EPA	Requirement	ARAR/TBC	Rationale for Implementation
Endangered Species Protection, 50 CFR Part 402 (ORC 1518, 1513.25 and OAC 1501-18-1-01).	Federal agencies must not jeopardize the continued existence of any endangered or threatened species, or destroy or adversely modify critical habitat of such species.	Applicable	The FEMP is located within the range of the Indiana bat, a federally listed endangered species, which has been sighted at the FEMP. Therefore, this requirement is applicable. Any potential impacts of the remedial actions on this species must be evaluated and appropriate action taken.
NEPA/DOE	Requirement	ARAR/TBC	Rationale for Implementation
Compliance with Floodplain/Wetlands Environmental Review Requirements, 10 CFR Part 1022 (Executive Order 11990).	DOE actions in a wetland must first evaluate the potential adverse effects that those actions might have on the wetland and consider the natural and beneficial values served by the wetlands.	Applicable	This requirement is applicable because the FEMP is a DOE facility. Several alternatives might result in destruction or modification of wetland areas.

8243

TABLE A-3
ARARS FOR SILO 3
REMEDIAL ACTION, ACTION-SPECIFIC

AEA/DOE	Requirement	ARAR/TBC	Rationale for Implementation
10 CFR Part 1021.2	DOE actions must be subjected to NEPA evaluation as outlined by the Council on Environmental Quality regulations in 40 CFR Part 1500-1508.	Applicable	This requirement is applicable because the FEMP is a DOE facility, and this requirement requires NEPA evaluation for specific actions at DOE facilities.
CWA	Requirement	ARAR/TBC	Rationale for Implementation
Nationwide Permit Program, 33 CFR Part 330.	The U.S. Corps of Engineers can issue a Nationwide Permit (NWP) as a general permit for certain classes of actions that involve dredge or fill activities in wetlands or navigable waters. Discharges of dredged or fill material into wetlands may require a wetland delineation.	Applicable	Remediation activities may require construction of access roads and utility lines resulting in minor wetland disturbances. Dredge and fill activities related to construction of these access roads and utility lines will be conducted in accordance with the substantive terms and conditions of NWP 14 (Road Crossing), and NWP 12 (Utility Line Backfill and Bedding). OEPA has been granted Section 401 State Water Quality Certification for NWPs 12 and 14.
Discharge of Stormwater Runoff, 40 CFR Part 122.26 (OAC 3745-38).	Stormwater runoff from landfills, construction sites, and industrial activities must be monitored and controlled. A Stormwater Pollution Prevention Plan is required for construction activities that result in a total land disturbance of five or more acres.	Applicable	Required of industrial waste sites and construction sites of greater than five acres that discharge stormwater runoff to the waters of the U.S. Some remedial alternatives evaluated might disturb more than five acres of land.

8243

TABLE A-3 (Continued)

CWA (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Discharge of Treatment System Effluent, 40 CFR Part 125.100. 40 CFR Part 125.104.	<p><u>Best Management Practices (BMPs)</u> Development and implementation of a BMP program to prevent the release of toxic or hazardous pollutants to waters of the U.S. Development and implementation of a site-wide BMP Program is also required as a condition of the FEMP National Pollution Discharge Elimination System (NPDES) Permit.</p> <p>The BMP program must:</p> <ul style="list-style-type: none"> • Establish specific objectives for the control of toxic and hazardous pollutants, and • Include a prediction of direction, rate of flow, and total quantity of toxic and hazardous pollutants where experience indicates a reasonable potential for equipment failure. 	Relevant and Appropriate	All of the proposed actions have the potential for releases and runoff from this operable unit (OU).
Safe Drinking Water Act (SDWA)	<p><u>Requirement</u></p>	ARAR/TBC	Rationale for Implementation
Ohio Water Well Standards, OAC 3745-9-10.	<p><u>Abandonment of Test Holes and Wells</u> Upon completion of testing, a test hole or well shall be either completely filled with grout or such material as will prevent contaminants from entering groundwater.</p>	Applicable	Test borings and wells might be installed and/or closed as part of these remedial alternatives.

8243

TABLE A-3 (Continued)

UMTRCA	Requirement	ARAR/TBC	Rationale for Implementation
Implementation of Health and Environmental Protection Standards for Uranium Mill Tailings, 40 CFR Part 192 Subpart C.	This subpart contains guidance, criteria, and supplemental standards for compliance with Subparts A and B of 40 CFR Part 192.	Relevant and Appropriate	Radioactive materials in this OU are primarily by-product residues from uranium processing. Requirements for design of controls should be consistent with design of controls for other residual radioactive materials such as mill tailings.
RCRA Subtitle C	Requirement	ARAR/TBC	Rationale for Implementation
Hazardous Waste Determinations, 40 CFR Part 262.11 (OAC 3745-52-11).	Any generator of waste must determine whether or not the waste is hazardous. The procedures for determination include: <ul style="list-style-type: none"> • Identification of whether a particular material of concern is a "solid waste"; • Identification of whether a particular exclusion applies to the material eliminating it from definition as a "solid waste"; • Identification of whether a particular solid waste might be classified as a hazardous waste; and • Determination of whether a material otherwise classified as a "hazardous waste" might be excluded from RCRA regulation. 	Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes (e.g., secondary waste) that exhibit a hazardous characteristic.)	These procedures are established to determine whether wastes are subject to the requirements of RCRA. The materials in Silo 3 are specifically exempt from the applicability of RCRA requirements. However, certain specific RCRA requirements, as identified in the remainder of this table, have been identified as relevant and appropriate to the onsite management (storage, transportation) of Silo 3 material. Hazardous waste determination requirements of 40CFR 262.11 are relevant and appropriate to determine whether wastes generated during remediation of Silo 3 material, such as debris generated during decontamination (e.g., concrete scabbling) or other secondary waste must be treated, stored, and disposed in accordance with RCRA.
Hazardous Waste Exclusions, 40 CFR Part 261.4(a)(4) and 40 CFR 261 (b)(7) (OAC 3745-51-4)	Materials which are not solid waste include: <ul style="list-style-type: none"> • Source, special nuclear or by-product material as defined by the Atomic Energy Act of 1954 as amended Solid wastes which are not hazardous wastes include: <ul style="list-style-type: none"> • Solid waste from the extraction, beneficiation and processing of ores and minerals. 	Applicable	The materials in Silo 3 were generated from the extraction/beneficiation of uranium from its ore and have been classified as by-product consistent with Section 11(e)2 of the AEA.

8243

TABLE A-3 (Continued)

RCRA Subtitle C	Requirement	ARAR/TBC	Rationale for Implementation
Empty Containers, 40 CFR Part 261.7 (OAC 3745-51-7).	Containers that have held hazardous wastes are "empty" and exempt from further RCRA regulations if one or more of the following are met: <ul style="list-style-type: none"> • No more than 2.5 cm (1 inch) of residue remains on the bottom of their inner liner; • Less than 3% by weight of total capacity remains (less than or equal to 110 gallon container); and • Less than 0.3% by weight of total capacity remains (greater than 110 gallon container). Containers that have held acutely hazardous ("P" listed) wastes are "empty" and exempt from further RCRA regulation if: <ul style="list-style-type: none"> • They or their inner liners have been triple rinsed with an adequate solvent or the inner liner has been removed from the container. 	Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)	Containers used to treat or store secondary waste generated consequential to implementing remedial actions to address the silo 3 residues may exhibit hazardous waste characteristics which must be removed before the containers might be reused or disposed.
Generators Who Transport Hazardous Waste for Off-site Treatment, Storage, or Disposal; 40 CFR Parts 262.20 - 33 and 263.20 - 31 (OAC 3745-52-20 through 33 and OAC 3745-53-20 through 31).	Any generator who transports hazardous waste for off-site treatment, storage or disposal must originate and follow-up the manifest for off-site shipments.	Applicable	Any secondary wastes generated consequential to the implementation of remedial actions to address the silo 3 residues which are determined to be RCRA hazardous waste would be subject to the manifest requirements to facilitate offsite treatment or disposal.

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
<p>Treatment, Storage, or Disposal Facility Standards; 40 CFR Part 264 Subpart B (OAC 3745-54-13 through 16).</p>	<p><u>General Standards</u></p> <ul style="list-style-type: none"> • Waste Analysis - OAC 3745-54-13: Operators of a facility must obtain a detailed chemical and physical analysis of a representative sample of each hazardous waste to be treated, stored, or disposed of at the facility prior to treatment, storage, or disposal. • Security - OAC 3745-54-14: Operators of a facility must prevent the unknowing or unauthorized entry of persons or livestock into the active portions of the facility, maintain a 24-hour surveillance system, or surround the facility with a controlled access barrier and maintain appropriate warning signs at facility approaches. • Inspections - OAC 3745-54-15: Operators of a facility must: (1) develop a schedule and regularly inspect monitoring equipment, safety and emergency equipment, security devices, and operating and structural equipment that are important to preventing, detecting or responding to environmental or human health hazards; (2) promptly or immediately remedy defects; and (3) maintain an inspection log. • Training - OAC 3745-54-16: Operators must train personnel, within six months of their assumption of duties at a facility, in hazardous waste management procedures relevant to their positions, including emergency response training. 	<p>Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)</p>	<p>Secondary wastes generated during the implementation of remedial actions to address the silo 3 residues might be required to be treated, stored, and disposed in accordance with TSD facility standards.</p>

8243

TABLE A-3 (Continued)

RCRA, Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
<p>Treatment, Storage, or Disposal Facility Preparedness and Prevention; 40 CFR Part 264 Subpart C and 40 CFR Part 264.31 (OAC 3745-54-31).</p>	<p>Treatment, storage, and disposal facility (TSD/F) operators must design, construct, maintain and operate facilities to minimize the possibility of a fire, explosion, or any unplanned sudden or nonsudden release of hazardous waste to air, soil, or surface water which might threaten human health or the environment.</p>	<p>Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)</p>	<p>Secondary wastes generated during the implementation of remedial actions to address Silo 3 might be required to be treated, stored, and disposed in accordance with TSD facility standards.</p>
<p>40 CFR Part 264.32 (OAC 3745-54-32).</p>	<p>Facilities must be equipped with an internal communication or alarm system, a telephone, or a two-way radio for calling outside to emergency assistance, fire control, and spill control. Decontamination equipment and water must be at an adequate volume and pressure to supply water hose streams, foam producing equipment, automatic sprinklers, or water spray systems.</p>		
<p>40 CFR Part 264.33 (OAC 3745-54-33).</p>	<p>Fire protection, spill-control and decontamination equipment, and communication and alarm systems must be tested and maintained, as necessary, to ensure proper emergency operation.</p>		
<p>40 CFR Part 264.34 (OAC 3745-54-34).</p>	<p>Personnel must have immediate access to emergency communication or alarm systems whenever hazardous waste is being handled at the facility.</p>		
<p>40 CFR Part 264.35 (OAC 3745-54-35).</p>	<p>Aisle space must be sufficient to allow unobstructed movement of personnel, fire and spill control, and decontamination equipment.</p>		
<p>40 CFR Part 264.37 (OAC 3745-54-37).</p>	<p>Operators must attempt to make arrangements, appropriate to the waste handled, for emergency response by local and state fire, police and medical personnel.</p>		

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
<p>Treatment, Storage, or Disposal Facility Contingency Plan and Emergency Procedures: 40 CFR Part 264 Subpart D and 40 Part CFR 264.51 (OAC 3745-54-51).</p>	<p>Each facility operator must have a contingency plan designed to minimize hazards to human health or the environment due to fires, explosions, or any unplanned releases of hazardous waste constituents to the air, soil, or surface/groundwater.</p>	<p>Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)</p>	<p>Secondary wastes generated during the implementation of remedial actions to address Silo 3 might be required to be treated, stored, and disposed in accordance with TSD facility standards.</p>
<p>40 CFR Part 264.52 (OAC 3745-54-52).</p>	<p>Contingency plans should address procedures to implement a response to incidents involving hazardous waste, and provide for: internal and external communications, arrangements with local emergency authorities, an emergency coordinator list, a facility emergency equipment list indicating equipment descriptions and locations, and a facility personnel evacuation plan.</p>		
<p>40 CFR Part 264.55, .56 (OAC 3745-54-55 through 56).</p>	<p>Each facility must have an emergency coordinator who: (1) has responsibility for coordinating emergency response measures; (2) is on the premises or on call at all times; (3) is thoroughly familiar with all aspects of the contingency plan, facility operations, location and characteristics of waste handled, location of pertinent records, and facility layout; and (4) has the authority to commit the resources necessary to implement the contingency plan in the event of an emergency.</p>		

000053

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Closure, 40 CFR Part 264 Subpart G. 40 CFR Part 264.111 (OAC 3745-55-11). 40 CFR Part 264.114 (OAC 3745-55-14). 40 CFR Part 264.116 (OAC 3745-55-16).	An operator must close facilities in a manner that: <ul style="list-style-type: none"> • Minimizes the need for further maintenance; • Minimizes post-closure escape of hazardous constituents; and • Complies with specific, unit-type closure requirements. Contaminated equipment, structures and soils must be properly disposed or decontaminated. Following closure, a survey plot showing the location of hazardous waste disposal units, with respect to surveyed benchmarks, must be filed with the legal total zoning authority.	Relevant and Appropriate. (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)	Secondary wastes generated during the implementation of remedial actions to address Silo 3 might be required to be treated, stored, and disposed in accordance with TSD facility standards.

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Container Storage, 40 CFR Part 264 Subpart I 40 CFR Part 264.171 - 178 (OAC 3745-55-71 through -78).	<p>Containers of RCRA hazardous waste must be:</p> <ul style="list-style-type: none"> • Maintained in good condition; • Compatible with hazardous waste to be stored; • Closed during storage (except to add or remove waste); and • Managed in a manner that will not cause the container to rupture or leak. <p>Storage areas must be inspected weekly for leaking and deteriorated containers and containment systems.</p> <p>Containers must be placed on a sloped, crack-free base, and protected from contact with accumulated liquid. A containment system with a capacity of 10 percent of the volume of the largest container of free liquids must be provided. Spilled or leaked waste must be removed in a timely manner to prevent overflow of the containment system.</p> <p>Incompatible materials must be separated. Incompatible materials stored near each other must be separated by a dike or other barrier.</p> <p>At closure, hazardous waste and residue from the containment system must be removed, and containers, liners, bases, and soils must be removed or decontaminated.</p>	Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)	Secondary wastes generated during the implementation of remedial actions to address Silo 3 might be required to be treated, stored, and disposed in accordance with TSD facility standards.

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Tank Systems, 40 CFR Part 264 Subpart J (OAC 3745-55-91 through 96).	Design, operating standards, and inspection requirements for tank units within which hazardous waste is stored or treated. Includes the following: <ul style="list-style-type: none"> • Tank design must be compatible with the material being stored. • Tank must be designed and have sufficient strength to store or treat waste in order to ensure that it will not rupture or collapse. • Tank must have secondary containment that is capable of detecting and collecting releases to prevent migration of wastes or accumulated liquids to the environment. 	Relevant and Appropriate (This requirement will be applicable to non-excluded solid hazardous characteristic.)	Design criteria, operating standards, and inspections for tank treatment units might be relevant and appropriate for alternatives utilizing treatment or storage in a tank prior to disposal.
Closure Requirements for Tanks, 40 CFR Part 264.197 (OAC 3745-55-97).	At closure, the facility owner must do the following: <ul style="list-style-type: none"> • Remove waste residues; • Remove or decontaminate tank system components; • Remove or decontaminate contaminated soils and structures; • Manage all of the above as hazardous wastes; and • If all contaminated soils cannot be removed, meet the landfill requirements of 40 CFR Part 264.310. 	Relevant and Appropriate (This requirement will be applicable to non-excluded solid hazardous characteristic.)	These standards will pertain to closure of any tanks and appurtenances used to provide treatment or storage of non-excluded wastes associated with the implementation of remedial actions for silo 3.

000056

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Miscellaneous Units, 40 CFR Part 264 Subpart X (40 CFR 264.601, .602 and OAC 3745-57-91 and 92).	Environmental performance standard, monitoring, inspection, and post-closure care for treatment in miscellaneous units as defined in 40 CFR Part 260.10.	Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)	Miscellaneous units might be utilized under various alternatives to remediate waste that is sufficiently similar to hazardous wastes.
Corrective Action for Solid Waste Management Units (SWMUs), 40 CFR Part 264 Subpart S and 40 CFR Part 264.552,.553.	Corrective action management units (CAMUs) might be designated at the site as areas where remediation wastes (solid, hazardous, or contaminated media and debris) might be placed during the process of remediation. Temporary units consisting of tanks and container storage units might be used to store and treat hazardous waste during the process of corrective action.	Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)	During the process of remediation, waste materials might require temporary management in containment buildings, temporary units, stockpiles, or other land based units for the purpose of staging, treating or disposing the material. Materials generated from remediation of the Silo 3 material are considered remediation wastes. Some of the waste material might exhibit a RCRA characteristic, or otherwise be sufficiently similar to hazardous waste to make this requirement relevant and appropriate.

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
<p>Containment Buildings, 40 CFR Part 264 Subpart DD and 40 CFR Part 264.1101, .1102.</p>	<p>Hazardous waste and debris might be placed into units known as containment buildings for the purpose of interim storage or treatment.</p> <p>Containment buildings must be fully enclosed to prevent exposure to the elements and ensure containment of managed wastes. Floor and containment walls must be designed and constructed of materials of sufficient strength and thickness to support themselves, the waste contents, and any personnel and heavy equipment that operate within the unit. Surfaces coming in contact with hazardous waste must be chemically compatible with waste. Primary barriers must be constructed to prevent migration of hazardous constituents into barrier. Secondary containment systems including secondary barriers and leak detection systems must also be constructed for containment buildings used to manage wastes containing free liquids.</p> <p>Controls must be implemented to ensure: the primary barrier is free of significant cracks, corrosion, or other deterioration that may allow release of hazardous waste; the level of hazardous waste does not exceed height of containment walls and is otherwise maintained within containment walls; tracking of waste out of unit by personnel or equipment used in handling waste is prevented; and fugitive dust emissions are controlled at the level of no visible emissions.</p>	<p>Relevant and Appropriate (This requirement will be applicable to non-excluded solid wastes that exhibit a hazardous characteristic.)</p>	<p>During the process of remediation, waste materials might require temporary management for the purpose of staging or treating the material. Some of the waste material might exhibit a RCRA characteristic, or otherwise be sufficiently similar to hazardous waste to make this requirement relevant and appropriate.</p>

000058

8243

TABLE A-3 (Continued)

RCRA Subtitle C (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Radiation Dose Limit (All Pathways), Proposed 10 CFR Part 834.	The exposure of members of the public to radiation sources as a consequence of all routine DOE activities shall not cause, in a year, an EDE greater than 100 mreem from all exposure pathways.	To be considered	Radiation sources from this OU (i.e., a DOE-owned facility) might contribute to the total dosage to members of the public.
CAA	Requirement	ARAR/TBC	Rationale for Implementation
Control of Fugitive Dust, OAC 3745-17-08.	Visible emissions of fugitive dust generated during grading, loading, or construction operations and other practices that emit fugitive dust shall be minimized or eliminated.	Relevant and Appropriate	The implementation of remedial action alternatives will require the movement of dirt and other material likely to result in fugitive dust emissions. This requirement is relevant and appropriate because the FEMMP is not located in an area subject to this regulation.
Prevention of Air Pollution Nuisance, ORC 3704.01-.05 and OAC 3745-15-07.	Measures shall be taken to adopt and maintain a program for the prevention, control, and abatement of air pollution in order to protect and enhance the quality of the state's air resource so as to promote the public health, welfare, and economic vitality of the people of the state. The emission or escape into open air from any source whatsoever of smoke, ashes, dust, dirt, grime, acids, fumes, gases, vapors, odors, and combinations of the above in such a manner or in such amounts as to endanger the health, safety, or welfare of the public or to cause unreasonable injury or damage to property shall be declared a public nuisance and is prohibited.	Applicable	During the remediation process, some potential exists for emissions of radionuclides and toxic chemicals to the air.

8243

TABLE A-3 (Continued)

CAA (continued)	Requirement	ARAR/TBC	Rationale for Implementation
Control of Visible Particulate Emissions from Stationary Sources, OAC 3745-17-07.	Discharge of particulate emissions of a shade or density greater than 20 percent opacity into ambient air from any stack is prohibited. Transient limits are included in this regulation.	Applicable	Treatment operations for various alternatives might result in the release of particulate material.
Permit to Install, OAC 3745-31-05(A)(3).	The director shall issue a permit to install if he/she determines that the installation or modification and operation of the air contaminant source will employ the best available technology.	Relevant and Appropriate	Although an administrative permit to install is not required for alternatives involving treatment, the substantive requirements of this section must be met by employing Best Available Technology (BAT) for treating particulate and other off-gas emissions.

000060

8243

TABLE A-3 (Continued)

CAA (continued)	Requirement	ARAR/TBC	Rationale for Implementation														
Restrictions on Particulate Emissions from Industrial Processes, OAC 3745-17-11.	<p>This requirement establishes numerical emission release limits for particulate material from industrial sources.</p> <p>Any source (operation, process, or activity) shall be operated so that particulate emissions do not exceed allowable emission rates specified in this regulation [based on processing weights (Table 1) or uncontrolled mass rate of emissions (Figure II) of OAC 3745-17-11].</p> <p>A source complies with Table 1 requirements if its rate of particulate emission is always equal to or less than the allowable rate of particulate emission based on the maximum capacity of the source:</p> <table border="1" data-bbox="690 1134 950 1606"> <thead> <tr> <th>Process Rate at Maximum Capacity (lb/hr)</th> <th>Allowable Rate of Particulate Emission (lb/hr)¹</th> </tr> </thead> <tbody> <tr> <td>100</td> <td>0.551</td> </tr> <tr> <td>200</td> <td>0.877</td> </tr> <tr> <td>400</td> <td>1.40</td> </tr> <tr> <td>600</td> <td>1.83</td> </tr> <tr> <td>800</td> <td>2.22</td> </tr> <tr> <td>1000</td> <td>2.58</td> </tr> </tbody> </table> <p>¹ Excerpted from Table 1 of OAC 3745-17-11.</p>	Process Rate at Maximum Capacity (lb/hr)	Allowable Rate of Particulate Emission (lb/hr) ¹	100	0.551	200	0.877	400	1.40	600	1.83	800	2.22	1000	2.58	Applicable	Treatment operations for various alternatives might result in release of particulate material that might exceed these standards.
Process Rate at Maximum Capacity (lb/hr)	Allowable Rate of Particulate Emission (lb/hr) ¹																
100	0.551																
200	0.877																
400	1.40																
600	1.83																
800	2.22																
1000	2.58																

8243

**TABLE A-4
 OTHER REQUIREMENTS FOR SILO 3
 REMEDIAL ACTION ALTERNATIVES**

Title	Requirement	Rationale for Implementation
OSHA Worker Protection Requirements, 29 CFR Parts 1904 and 1910.	Establishes requirements to protect workers who could be exposed to radiation, noise, hazardous wastes, or other contaminants or hazards at the remediation site.	This OU is a remediation site under CERCLA. Compliance with 29 CFR Part 1910.120 is required for sites undergoing remediation by 40 CFR Part 300.150.
DOT Requirements for Transportation of Hazardous Materials, 49 CFR Parts 171-173, 177, 178.	Hazardous materials may not be transported on public highways except in accordance with these regulations: <ul style="list-style-type: none"> • Part 171, General Requirements. • Part 172, this part establishes shipping papers, marking, labeling, placarding, and emergency response information requirements. • Part 173, this part establishes packaging and other shipping requirements for hazardous materials, including radioactive materials. • Part 177, Requirements of the Transporter. • Part 178, Specifications for Shipping Containers. 	Applicable to those alternatives which involve transportation of the waste materials off-site. Radioactive materials and materials sufficiently similar to hazardous wastes might be shipped off-site.
Highway Improvement Act of 1982, 23 USC 127.	Establishes vehicle weight limits for interstate highways.	Applicable to those alternatives which involve transportation of the waste materials off-site.
Hazardous Materials Transportation Act, 49 USC 1801-1812.	Establishes requirements for minimizing environmental impacts of spills or releases of hazardous materials.	Applicable to those alternatives which involve transportation of the waste materials off-site. Radioactive materials and materials sufficiently similar to hazardous wastes might be shipped off-site.

000062

8243

TABLE A-4 (Continued)

Title	Requirement	Rationale for Implementation
NTS Waste Acceptance Criteria.	Establishes which wastes may be disposed at the Nevada Test Site.	The NTS waste acceptance criteria would be applicable to disposals at the NTS. NTS operates under DOE Order 435.1, "Radioactive Waste Management."
National Historic Preservation Act, 16 USC 470 et seq.	Protects sites listed or eligible for listing in the National Register of Historic Places.	Required by law for the alternatives affected.
Archaeological and Historic Preservation Act, 16 USC 469.	Preserves artifacts and data associated with archaeological finds.	Required by law for the alternatives affected.
American Indian Religious Freedom Act, 42 USC 1996.	Provides for tribal access by native peoples to grave sites and sites of cultural, symbolic, or religious significance.	Required by law for the alternatives affected.
Native American Graves Protection and Repatriation Act, 25 USC 3001.	Provides for return of human remains and cultural objects from Native American graves to affiliated tribes.	Required by law for the alternatives affected.
Protection and Enhancement of Cultural Environment, Executive Order 11593.	Requires inventory of site for potential historic places for eligibility in the National Register of Historic Places.	Required by law for the alternatives affected.
Fish and Wildlife Coordination Act, 16 USC 66 et seq.	Requires consultation with other state agencies on activities that might affect any body of water for the conservation of fish and wildlife resources.	Required by law for the alternatives affected.

8243

TABLE A-4 (Continued)

Title	Requirement	Rationale for Implementation
Archaeological Resources Protection Act, 16 USC 470 (a).	Requires permit for removal of any archaeological resources from federal lands.	Required by law for the alternatives affected.
Antiquities Act and Historic Sites Act, 16 USC 431-433 and 16 USC 461-467.	Requires identification and preservation of cultural resources on federal lands; includes natural landmarks.	Required by law for the alternatives affected.
Farmland Protection Policy Act, 7 USC 4201 et. Seq.	Requires protection and maintenance of farmland for its beneficial use as a national resource.	Required by law for the alternatives affected.
Occupational Radiation Protection, 10 CFR Part 835.	Provides standards for occupational radiation protection of workers at DOE facilities.	Required by law for safety and worker protection at DOE facilities (replaces former DOE Order 5480.11).
DOE Order	Title	Rationale for Implementation
5400.3	Hazardous and Mixed Waste Program	Contractual obligation for activities at DOE facilities.
5400.5	Radiation Protection of the Public and the Environment	Contractual obligation for activities at DOE facilities.
451.1A	NEPA Compliance Program	Contractual obligation for activities at DOE facilities.
5480.1B	Environmental, Safety, and Health Program for DOE Operations	Contractual obligation for activities at DOE facilities.
460.1A	Packaging and Transportation Safety	Contractual obligation for activities at DOE facilities.
460.2	Departmental Materials Transportation and Packaging Management	Contractual obligation for activities at DOE facilities.

8243

TABLE A-4 (Continued)

DOE Order	Title	Rationale for Implementation
5480.4	Environmental Protection, Safety, and Health Protection Standards	Contractual obligation for activities at DOE facilities.
440.1A	Worker Protection for DOE Federal and Contractor Employees	Contractual obligation for activities at DOE facilities.
435.1	Radioactive Waste Management	Contractual obligation for activities at DOE facilities.
414.1	Quality Assurance	Contractual obligation for activities at DOE facilities.
430.1A	Life Cycle Asset Management	Contractual obligation for activities at DOE facilities.

APPENDIX B

RESPONSIVENESS SUMMARY

8243

B Responsiveness Summary

1

2 **B.1 Purpose**

3 As stated in the U. S. Environmental Protection Agency (EPA) Guide to Preparing
4 Superfund Proposed Plans, Records of Decision, and Other Remedy Selection Decision
5 Documents, the responsiveness summary serves three important purposes. First it
6 provides the DOE with information about community preferences regarding both the
7 proposed remedial alternative and general concerns about the site. Second, it
8 demonstrates how public and support agency comments were integrated into the decision-
9 making process. Third, it allows DOE to formally respond to public comments.

10 This Responsiveness Summary has been prepared to meet the requirements of Sections
11 113(k)(2)(B)(iv) and 117(b) of the Comprehensive Environmental Response, Compensation
12 and Liability Act of 1980, as amended (CERCLA). As the lead agency at the FCP, DOE is
13 required to respond "...to each of the significant comments, criticisms, and new data
14 submitted in written or oral presentations" on the Revised Proposed Plan for Remedial
15 Action at Silo3.

16 **B.2 Community Participation For Silo 3**

17 DOE is responsible for conducting the community relations for the FCP. A community
18 relations program was established for the FEMP in 1985 to provide information about the
19 site regarding updates and progress of the clean-up activities.

20 In November 1993, DOE implemented a public participation program at Fernald to involve
21 community members and other interested parties in the decision-making process at the
22 site. This Fernald Community Advisory Board (FCAB), formerly known as the Fernald
23 Citizens Task Force, was chartered to provide DOE, EPA, and Ohio Environmental
24 Protection Agency (OEPA) with recommendations about cleanup solutions and future
25 courses of action at the FEMP. These efforts, along with the community relations

8243

1 activities required by CERCLA, reflect DOE's intent to fully involve the community in the
2 decision-making process.

3 More recently, DOE has encouraged public involvement and informal comment throughout
4 reevaluation of the remedy for Silo 3. Stakeholder input was a key factor in development
5 of the revised remedy formally recommended in the PP issued for formal review. This
6 approach has provided a genuine opportunity for stakeholders to identify issues, voice
7 their concerns, and learn about the proposed clean-up plan. The informal opportunity for
8 the public to provide input enabled DOE to address stakeholder questions and concerns in
9 advance of the formal public comment period.

10 Two Administrative Records, located at the Public Environmental Information Center at the
11 FCP and EPA Region V offices in Chicago, Illinois have been established to provide an
12 information repository on the decision-making process for interested members of the
13 public.

14 B.2.1 Public Comment Period

15 The DOE recently held a public comment period from April 30 through May 30, 2003, for
16 interested parties to comment on the modified selected remedy for the Silo 3 material. The
17 public comment period was held in accordance with Section 117 of CERCLA. A public
18 hearing was held in the vicinity of the FCP on May 13, 2003 to provide the public with a
19 forum to submit oral comments on the proposed revised remedy. No written or oral
20 comments were received by DOE at the Public Hearing. A transcript of the hearing is
21 included in the attachment to this Responsiveness Summary.

22 The availability of the Final PP and supporting documentation, the schedule for the
23 comment period, and the location and schedule for the public hearing, were announced in
24 local newspapers on April 30, 2003. In addition, this information was announced on the
25 Fernald Closure Project web site (www.fernald.gov), and communicated by direct mail to
26 stakeholders on the FCP Public Affairs mailing list.

1 B.2.1.1 Responses to Public Comments

2 Comments were received from only one stakeholder during the public comment period.
3 These comments, and DOE's response to each comment, are documented below.

4 Comment 1: from Robert Vogel

5 "As the initial justification for the use of soft sided shipping containers for Silo 3 material
6 was that it would be in a treated form and therefore resistant to dispersion, the Proposed
7 Plan should explain why untreated Silo 3 material will not disperse. On page 3-6 the
8 airborne release fraction of 0.01 is referenced as the "bounding value" without any
9 attempt to connect this number to the specific characteristics of Silo 3 material. Due to
10 the two different materials which Silo 3 contains (refer to M:SP:2001-0082) the number
11 0.01 can only be correct to use for one of these materials. Anyone familiar with Silo 3
12 material of rotary calciner origin would find it difficult to believe that 0.01 is reflective of
13 this extremely dispersible material. It is probably reasonable to use this number for
14 material produced by the spray calciner, but it is clearly inappropriate to use this number
15 for both materials."

16 **Response:** The primary issue raised in this comment is whether or not the airborne release
17 fraction (ARF) utilized in the transportation risk evaluation adequately represents the
18 behavior of the material, given the known variability in the sources and physical
19 characteristics of the material. The ARF is one of three interdependent parameters
20 affecting potential inhalation exposure, and represents the fraction of any material released
21 from a container that becomes airborne. The other two are the Fraction Released (fraction
22 of material in a container that is released during an accident) and the Respirable Fraction
23 (fraction of the airborne material that becomes respirable). The fraction released is scaled
24 to the various accident severity categories with 100 percent assumed for the most severe
25 accident. For the Silo 3 transportation risk evaluation, the Respirable Fraction was
26 assumed to be 36 percent based on the most conservative empirical data from tests on
27 Silo 3 material.

1 A significant literature search was conducted prior to the conducting the RADTRAN
2 modeling runs for the risk evaluation in order to derive a best and supportable ARF. The
3 American Society of Mechanical Engineers performed an independent peer review of the
4 DOE reference guide on ARFs (DOE-HDBK-3010, *Airborne Release Fraction/Rates And*
5 *Respirable Fractions for Nonreactor Nuclear Facilities*. The ASME recommended a
6 bounding ARF of 0.01 for powders. ASME deemed this to be conservative value and this
7 ARF was adopted for use in the RADTRAN modeling runs performed for the Silo 3 risk
8 analysis. The earlier RADTRAN runs referenced in the comment used an ARF of 0.0001
9 based upon the DOE reference guide (DOE-HDBK-3010). The current ARFs used for the
10 risk analyses supporting the Silo 3 Proposed Plan are more conservative by a factor of
11 100.

12 As discussed in the Proposed Plan, the treatment step included as part of the revised
13 remedy will result in a substantial reduction in ARF compared to the untreated material,
14 However, in order to provide additional conservatism, the transportation risk evaluation
15 took no credit for the any reduction in dispersability resulting from the treatment step.

16 It is recognized, as stated in this comment, the materials within Silo 3 are not
17 homogeneous and likely have a span of ARFs because of the large range of particle sizes.
18 It is recognized that variability in the physical characteristics of Silo 3 material will impact
19 its dispersability and ARF. However, based upon both the conservatism incorporated into
20 the RADTRAN modeling assumptions and independent evaluation of the ARF basis, the
21 evaluation documented in the Proposed Plan adequately characterizes the transportation
22 risk associated with the proposed remedy.

8243

1 Comment 2: from Robert Vogel

2 "Page 3-17, 2nd paragraph, second sentence – "inhalation" is stated to be calculated but
3 there are no data to quantify inhalation so that the reviewer cannot determine if the
4 amount assumed to be inhaled is reasonable. If the purpose of this document is to be
5 informative to the public, it should focus on the elements of this project that are most
6 important; no aspect should be made more clear to the reader than that of inhalation since
7 "cloudshine" and "groundshine" are trivial in comparison. The Proposed Plan does not
8 clarify this issue. This is especially questionable given the inappropriate use of the release
9 fraction mentioned above.

10 Secondly, the amount of material assumed to be inhaled would be helpful to know as the
11 ILCR data stated in the Proposed Plan is not significantly different from RADTRAN data
12 generated in 2002 which was solely based on external dose. As the external dose
13 potential for Silo 3 is minor compared to potential internal exposure, the inclusion of
14 inhalation dose should be reflected in the ILCR data. To be believable, inhalation data
15 should be quantified in the Proposed Plan."

16 **Response:** This comment raises two primary issues: 1) Are the assumptions made in the
17 risk evaluation regarding the amount of silo 3 material assumed to be inhaled in an
18 accident scenario reasonable; and 2) to what extent is the resulting inhalation dose
19 considered in calculating the dose and resulting Incremental Lifetime Cancer Risk (ILCR).

20 First, the amount of airborne material assumed to be inhaled (the Respirable Fraction (RF))
21 utilized in the risk evaluation was a conservative estimate based upon available data on
22 Silo 3 material. It is generally accepted that respirable particles are those less than 10 μm
23 in diameter. The most conservative and supportable test results for Silo 3 material yielded
24 an average fraction of 36 percent of the material that was less than 10 μm in diameter.
25 Other tests suggested as low as 0.99 percent of the particles were less than 10 μm . The
26 current RADTRAN runs assumed 36 percent of the airborne material was respirable.

1 Second, the population dose and risk for routine (non-accident) transport is based solely on
2 external radiation dose. For the accident scenarios the external and internal doses are
3 summed. The doses are reported as the sum of inhalation, ground shine, and cloud shine.
4 Since, as recognized in the comment, dose from "cloudshine" and "groundshine" is trivial
5 (approximately 1%) in comparison to dose from inhalation, the reported accident scenario
6 doses and resulting ILCR attribute 99% of the dose to inhalation following an accident..

7 An important factor in calculating the inhalation dose is the Dose Conversion Factor (DCF)
8 or the dose per quantity of activity inhaled. In preparation for the current RADTRAN runs,
9 the characteristics of the Silo 3 radionuclide forms were evaluated to assure use of the
10 most appropriate solubility class DCF assignment. Processing of the Silo 3 material with
11 the rotary calciner was more likely to have produced insoluble material (termed Class Y
12 material), which in most cases results in DCFs which are considerably higher than more
13 soluble material and deliver more dose per unit activity inhaled. Sometimes this dose is one
14 to two orders of magnitude higher. The less effective spray calciner would have tended to
15 produce insoluble material, but may also have produced some materials with higher
16 solubility (lower DCF) than those yielded from the rotary calciner. The modeling
17 conducted to support the Silo 3 risk evaluation conservatively assumed an insoluble form
18 for the Silo 3 materials and utilized the higher DCF's (Class Y) for dose calculation
19 purposes.

20 One exception to the above discussion should be noted, that being for Thorium-230, one
21 of the predominant radiological constituents present in the Silo 3 materials. Thorium-230
22 has a soluble DCF that is 24 percent higher than its insoluble form. Although thorium
23 compounds, including those associated with Silo 3 material, are considered to be
24 insoluble, the DCF used in the Silo 3 risk analysis was the average between the soluble
25 and insoluble forms as a conservative bounding value.

1 Following estimation of dose for a given routine or accident based transportation scenario,
2 the RADTRAN model is then used to yield an estimate of the risk to an exposed individual
3 or population. The model estimates risk by multiplying the calculated dose by a single
4 fatal cancer risk coefficient of 5×10^{-4} per rem. This includes both internal and external
5 radiation dose equivalents. This risk coefficient is utilized in the Silo 3 risk evaluation and
6 is consistent with the recommendations and methods in *Health Effects of Exposure to Low*
7 *Levels of Ionizing Radiation*, BEIR V, National Academy of Sciences (1990) and ICRP 60,
8 *Recommendations of the International Commission on Radiological Protection*, International
9 Commission of Radiological Protection (1991). The resultant risk totals were quite low
10 and no other specific organ dose assessment was necessary.

11 The information summarized above demonstrates that the assumptions underlying the risk
12 evaluation are reasonable given the known variations in the physical properties of the Silo
13 3 residues and provide an appropriate basis for decision making.

14 Comment 3: from Robert Vogel

15 "Much of the data used in the development of the current plan derives from testing done
16 by Jenike and Johanson on Silo 3 material. Unfortunately, this material was from Small
17 Scale Retrieval origin with its extremely different characteristics from the remaining two
18 thirds of the silo material. For the expertise of Jenike and Johanson to fully benefit the
19 project and provide the basis for design decisions, they should have been provided with
20 Silo 3 material of rotary calciner origin."

21 **Response:** The primary concern raised in this comment is the degree to which the testing
22 done by Jenike & Johanson (J&J) was based upon sufficiently representative
23 characterization of the physical properties of Silo 3 material. Due to their expertise in the
24 field of bulk solids storage, transfer, and flow, J&J was utilized to perform physical
25 property studies to support evaluation of retrieval, material handling, and treatment
26 alternatives for Silo 3 material. As noted in the comment, these studies were performed

1 utilizing actual Silo 3 material as well as on flyash which has similar dusting properties.
2 The Silo 3 material used in these studies was, as indicated in the comment, from the
3 Small-Scale Waste Retrieval Project, obtained in the lower portion of the silo, where it
4 would be expected to be of spray calciner origin.

5 In addition to their evaluation of the actual Silo 3 material, J&J also utilized a significant
6 body of historical data on the characteristics of Silo 3 material, which included copies of
7 historical silo 3 information (reference M:SP:2001-0082) and videos of the vibracore
8 sampling that was performed from the top of the silo. Design decisions were also based on
9 information from past processing facilities, sampling results from several sampling efforts,
10 studies from multiple consultants, and objectives for final disposal.

11 Physical tests performed by Jenike and Johanson were performed at different moisture
12 levels to determine the affect on flowability due to hygroscopic nature of the material, and
13 modeling was done for different scenarios to allow for variability in material properties.

14 Jenike and Johanson studies provided design information consistent with dry, fine
15 powdery material as opposed to free-flowing material such as plastic pellets or coarse
16 sand. The report validates material handling observations made during the various
17 sampling and testing efforts performed on Silo 3, and the original pneumatic conveyance
18 approach used to transfer the material from the old production area to the storage silo.
19 The various reports support the current proposed design approach, which uses: batch
20 process with limited overnight storage in bins; steep sided bins for mass flow; screw
21 conveyors; densification table added to packaging system to de-aerate material after it
22 becomes fluidized; and weigh table for package filling due to density differences and also
23 because packaging will be volume not weight limited; and spray nozzle assembly.
24 Modeling also provides various scenarios for pneumatic retrieval and mechanical retrieval,
25 both methods selected due to anticipated variation in compaction of material.

- 1 The combination of physical testing of actual Silo 3 material, utilization of a variety of
- 2 modeling scenario to account for variability in material characteristics, and the use of
- 3 historical data to support and supplement the studies, provides a sound technical basis for
- 4 the evaluation of retrieval, material handling, and treatment alternatives for Silo 3 material.

ATTACHMENT B-1

TRANSCRIPT OF MAY 13, 2003 PUBLIC HEARING

FERNALD PUBLIC HEARING

SILO 3 PROPOSED PLAN

PUBLIC COMMENTS

Tuesday, May 13, 2003

6:30 p.m.

Crosby Township Senior Center

8910 Willey Road

Harrison, Ohio

- - -

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24

1 MR. STEGNER: At this time we'll
2 open the formal public hearing portion of the
3 meeting. Again, there are comment cards you can
4 use if you do not want to speak tonight. You can
5 hand them to me at the end of the hearing or you
6 can send them via e-mail to me.

7 So with that, does anybody have
8 anything they would like to say during the public
9 comment period this evening?

10 MS. SCHROER: The person that
11 usually does all our talking is sick.

12 MR. STEGNER: Yeah, she called me
13 and said she wasn't going to be able to make it.
14 But, again, you have until May 30th to get your
15 comments in to me.


16 With that, going once, twice. Thank
17 you all very much for coming tonight.

18 - - -
19 PUBLIC HEARING CONCLUDED
20 - - -

C E R T I F I C A T E

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24

I, LOIS A. ROELL, RMR, the undersigned, a notary public-court reporter, do hereby certify that at the time and place stated herein, I recorded in stenotypy and thereafter had transcribed with computer-aided transcription the within (2) two pages, and that the foregoing transcript of proceedings is a complete and accurate report of my said stenotypy notes.



MY COMMISSION EXPIRES: LOIS A. ROELL, RMR
SEPTEMBER 7, 2003. NOTARY PUBLIC-STATE OF
KENTUCKY