

**CERTIFICATION DESIGN LETTER
FOR AREA 5 ADMINISTRATION AREA
AND WEST PARKING LOT**

**FERNALD CLOSURE PROJECT
FERNALD, OHIO**



OCTOBER 2006

U.S. DEPARTMENT OF ENERGY

**20810-PL-0008
REVISION 0
FINAL**

**CERTIFICATION DESIGN LETTER
FOR AREA 5 ADMINISTRATION AREA
AND WEST PARKING LOT**


**Document Number 20810-PL-0008
Final Revision 0**

October 2006


APPROVAL:



Jyh-Dong Chiou, Project Manager
Environmental Closure Project
Date 10/25/06



Rich Abitz, Characterization Manager
Environmental Closure Project
Date 25 Oct 06



Tom Buhrlage, Sampling Manager
Environmental Closure Project
Date 10-25-06



Reinhard Friske, Quality Assurance/Quality Control
Safety, Health and Quality
Date 10-25-06

FERNALD CLOSURE PROJECT

**Fluor Fernald, Inc.
P.O. Box 538704
Cincinnati, Ohio 45253-8704**

TABLE OF CONTENTS

	<u>Page</u>
List of Acronyms and Abbreviations	iii
List of Appendices	i
List of Figures	ii
List of Tables	ii
 Executive Summary	 ES-1
1.0 Introduction	1-1
1.1 Objectives	1-1
1.2 Scope and Area Description	1-2
2.0 Historical and Precertification Data	2-1
2.1 Area 5 Administration Area and West Parking Lot	2-1
2.1.1 Historical, Predesign and Excavation Control	2-1
2.1.2 Precertification Data	2-1
3.0 Area-Specific Constituents of Concern	3-1
3.1 Selection Criteria	3-1
3.1.1 Area 5 Administration Area and WPL ASCOC Selection	3-2
4.0 Certification Approach	4-1
4.1 Certification Design	4-1
4.1.1 Area 5 Administration Area, Haul Road, and WPL Certification Unit Design	4-2
4.1.2 Sample Location Design	4-2
4.2 Analytical Methodology and Statistical Analysis	4-2
5.0 Schedule	5-1
References	R-1

LIST OF APPENDICES

Appendix A	Precertification Real-Time Scan Data for Area 5 Administration Area, West Parking Lot, Haul Road, and the 60-inch Storm Sewer Line Excavation Footprint
Appendix B	Variance/Field Change Notices for Precertification Sampling in Area 5 Administration Area, Haul Road, and West Parking Lot
Appendix C	Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

LIST OF TABLES

Table 3-1	ASCOC List for Remediation Area 5
Table 3-2	ASCOC Retention Process for Area 5 Administration Area and WPL
Table 3-3	Final ASCOC List for Area 5 Administration Area and WPL
Table A-1	Area 5 Administration Area and West Parking Lot – HPGe Results Detector Height 31 cm
Table A-2	Area 5 Administration Area and West Parking Lot – HPGe Results Detector Height 15 cm
Table C-1	Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

LIST OF FIGURES

Figure 1-1	Area 5 Administration Area, West Parking Lot, Haul Road, and 60-Inch Line Areas
Figure 4-1	Area 5 CU Location Map
Figure 4-2	Area 5 West Parking Lot Certification Sample Locations
Figure 4-3	Area 5 Administration Area Certification Sample Locations
Figure 4-4	Area 5 Administration Area Haul Road Certification Sample Locations
Figure 4-5	Area 5 60-Inch Line Certification Sample Locations
Figure 4-6	Area 5 60-Inch Line Certification Sample Locations
Figure A-1	Area 5 Administration Area and West Parking Lot Phase 1 Total Gross Counts per Second
Figure A-2	Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Radium-226
Figure A-3	Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Thorium-232
Figure A-4	Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Total Uranium
Figure A-5	Area 5 Administration Area and West Parking Lot Phase 2 Moisture Corrected Radium-226
Figure A-6	Area 5 Administration Area and West Parking Lot Phase 2 Moisture Corrected Thorium-232
Figure A-7	Area 5 Administration Area and West Parking Lot Phase 2 Moisture Corrected Total Uranium
Figure A-8	Area 5 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Radium-226
Figure A-9	Area 5 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Thorium-232
Figure A-10	Area 5 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Total Uranium
Figure A-11	Administration Area and West Parking Lot Confirmation of Precertification Phase 1 - Moisture Corrected Total Uranium

LIST OF ACRONYMS AND ABBREVIATIONS

ASCOC	area-specific constituent of concern
ASL	analytical support level
CDL	Certification Design Letter
COC	constituent of concern
CRDL	contract required detection limit
CU	certification unit
DOE	U.S. Department of Energy
EPA	U.S. Environmental Protection Agency
FCP	Fernald Closure Project
FRL	final remediation level
FS	Feasibility Study
mg/kg	milligrams per kilogram
mg/L	milligrams per liter
OEPA	Ohio Environmental Protection Agency
OU	Operable Unit
pCi/g	picoCuries per gram
pCi/L	picoCuries per liter
PSP	Project Specific Plan
RI/FS	Remedial Investigation/Feasibility Study
ROD	Record of Decision
SED	Sitewide Environmental Database
SEP	Sitewide Excavation Plan
SWRB	Storm Water Retention Basin
UCL	Upper Confidence Limit
V/FCN	Variance/Field Change Notice
VSL	validation support level
WAC	waste acceptance criteria
WPL	West Parking Lot

EXECUTIVE SUMMARY

This Certification Design Letter (CDL) describes the certification approach for Area 5 Administration Area and West Parking Lot (WPL). The following information is included:

- The boundary of Area 5 (Figure 1-1) and a description of the area to be certified under the guidance of this CDL;
- A discussion of historical data from the area proposed for certification;
- A discussion of the area-specific constituent of concern (ASCOC) selection process and list of ASCOCs assigned to Area 5;
- A presentation of the certification unit (CU) boundaries and proposed sampling strategy;
- Details of certification sampling, analysis, and validation that took place;
- The analytical requirements and the statistical methodology that will be employed; and
- The analytical results of the precertification sampling in the Area 5 Administration Area, WPL, Haul Road, and 60-inch Line footprint.
- The proposed schedule for the certification activities.

The scope of this CDL is limited to the certification of the Area 5 Administration Area, a section of the haul road running through Area 5, the WPL, and the footprint of the 60-inch storm water line excavation that extends the length of Area 5 as shown on Figure 1-1.

The 5-acre West Parking Lot was first sampled in November 2005 and partially re-scanned and re-sampled in the summer 2006 following haul road operation and excavation of the 60" main storm water sewer. The southern portion of the West Parking Lot is located at a well-controlled area right by the front entrance of the Fernald site and did not have any "dirty" operation before or after November 2005. In August of 2006 Oak Ridge Institute for Science and Education (ORISE) conducted an independent verification of the Fluor Fernald certification process for United States Department of Energy. The Administration Area and portion of the West Parking Lot (i.e., the northern two thirds of the area covered by this CDL) were among the areas specifically evaluated by ORISE. Document review, field observation, radiological field scan, physical sampling, and cross-laboratory comparisons were applied to confirm that these areas meet the established FRLs. No above FRL conditions were found in the Administration Area or West Parking Lot.

Remediation was complete in the Administration Area in 2006 and the WPL in 2005, thus initiating the certification process described in this plan.

1 The certification design presented in this CDL follows the general approach outlined in Section 3.4 of the
2 Sitewide Excavation Plan (SEP, DOE 1998) and SEP Addendum (DOE 2001). The selection of Area 5
3 Administration Area and WPL ASCOCs was accomplished using constituent of concern (COC) lists in the
4 Operable Unit 5 Record of Decision (DOE 1996), previous investigation data, and process knowledge.
5 Thirteen CUs have been defined for this CDL. Total uranium, thorium-228, thorium-232, radium-226, and
6 radium-228 (the sitewide primary radiological COCs) are considered ASCOCs in each CU. Secondary
7 COCs are identified for specific CUs within the certification area.

1.0 INTRODUCTION

This Certification Design Letter (CDL) describes the certification approach for demonstrating that soil in the Area 5 Administration Area, a section of the haul road running through Area 5, the West Parking Lot (WPL), and the footprint of the 60-inch storm water line excavation that extends the length of Area 5 meet the final remediation levels (FRLs) for all area-specific constituents of concern (ASCOCs). The format of this document follows guidelines presented in the Sitewide Excavation Plan (SEP, DOE 1998) and SEP Addendum (2001). Accordingly, this document consists of the following sections:

- 1.0 Introduction - Presentation of the purpose, objectives, and scope of this CDL
 - 2.0 Historical and Precertification Data - Discussion of historical soil data and presentation of precertification data from the Area 5 Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line excavation.
 - 3.0 Area-Specific Constituents of Concern - Discussion of selection criteria and ASCOCs for Area 5 Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line excavation.
 - 4.0 Certification Approach - Presentation of design, surveying, sampling and analytical methodologies.
 - 5.0 Schedule
- References

1.1 OBJECTIVES

The primary objectives of this document are to:

- Define the boundaries of the areas to be certified under the guidance of this CDL;
- Present maps for newly acquired real-time data;
- Define the ASCOC selection process and list the selected COCs for the Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line excavation;
- Present the certification unit (CU) boundaries and proposed certification sampling strategy;
- Summarize the analytical requirements and the statistical methodology that will be employed; and
- Present the proposed schedule for the certification activities.

1 1.2 SCOPE AND AREA DESCRIPTION


2 The scope of this CDL includes details of certification sampling, analysis, and validation that will take
3 place in Area 5 Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line
4 excavation. Figure 1-1 depicts the layout of Area 5 and the portion of Area 5 (Administration Area, haul
5 road, WPL and the 60-inch line excavation) that is to be certified under this plan.

6
7 Remediation Area 5 lies in the southern portion of the Former Production Area and the Administration
8 Area including all but the southern end of the main parking lot. The area is bound by the Main Drainage
9 Corridor 1st Street to the north; Area 7 to the west and south; and Area 6 and Area 5 East Parking Lot to
10 the east. The section of the haul road that that is under this certification effort extends from the western
11 side of the WPL to the northeastern corner of the Administration Area. Once the area has been certified,
12 the haul road will be blended into the surrounding soil during restoration of the area.

V:\22\fm\2\ed\9\mcs_admin\wp1_13.dgn

STATE PLANNING COORDINATE SYSTEM 1983

18-OCT-2006




LEGEND:




ADMIN AREA



WPL AREA



60-INCH LINE AREA



HAUL ROAD AREA

FIGURE 1-1. AREA 5 ADMINISTRATION, WPL, HAUL ROAD, AND 60-INCH LINE AREAS

2.0 HISTORICAL AND PRECERTIFICATION DATA

In accordance with the SEP, prior to conducting precertification and certification activities, all soil demonstrated to contain contamination above the associated FRLs or other applicable action levels must be evaluated for remedial actions.

The Project Specific Plan (PSP) for Predesign Investigation in Area 5 (DOE 2002), the Remedial Investigation Reports (RI, DOE 1995a and 1995b), and Feasibility Study Reports (FS, DOE 1995c and 1995d) for Operable Units (OU) 3 and 5 were used for remedial design of Area 5. Final grade excavation monitoring/sampling and real-time scanning/sampling data have been collected pursuant to the RI/FS and remedial activities.

Before initiating the certification process, all historical soil data within the Area 5 Administration Area and WPL certification area were pulled from the Sitewide Environmental Database (SED). The data are summarized in Section 2.1. Based on the results of sampling and scanning activities summarized in Section 2.1, it has been determined that no additional remedial actions are necessary to remove above-FRL or above-waste acceptance criteria (WAC) soil.

The concrete pads and footers of the former Services, Administration, and Industrial Relations Buildings were removed as well as all sidewalks. All of the asphalt in the West Parking Lot has been removed, and all utilities have been removed from the area. The 60-inch storm water line that ran the entire length of Area 5 has been excavated. This excavation remains open.

2.1 Area 5 Administration Area and West Parking Lot

2.1.1 Historical, Predesign and Excavation Control

All historical data for Area 5 Administration Area and WPL are presented in the Implementation Plan for Area 3B/4B/5 (DOE 2004a). This includes data collected during the RI/FS and Area 5 Predesign Investigation PSP. No above-WAC areas have been identified in Area 5 Administration Area and WPL. Three above-FRL borings were identified during the Predesign Investigation, two in the Administration Area (beryllium and radium-226) and one in the West Parking Lot (arsenic). These three locations were excavated.

2.1.2 Precertification Data

During excavation of Area 5 Administration Area and WPL, various utilities were removed from the area. These utilities consisted of storm sewer, sanitary, effluent, drinking water, fire, electrical, communication lines, etc. Of these utilities, only those that contained a waste stream that could have leaked and potentially impacted the surrounding soil (i.e., effluent, storm sewer, and sanitary lines), and were going to be back

1 filled prior to certification of the area, were a concern for precertification. Therefore, following the
2 excavation and removal of these types of utilities and their associated bedding material, precertification
3 real-time scans were performed and physical precertification samples were collected from the top 6 inches
4 of the soil beneath the bedding. Physical precertification samples from utility excavations were collected
5 under Variance/Field Change Notices (V/FCNs) 20810-PSP-0006-114, 20810-PSP-0006-126, and
6 20810-PSP-0006-137 (see Appendix A).

7
8 Additionally, real-time precertification scans were performed on the surface of the overburden prior to
9 excavation of all utilities. After the potentially impacted material [i.e. utility lines and bedding (where
10 applicable)] was removed, the utility excavations were backfilled with the precertified overburden.

11
12 Following completion of all excavations in the Area 5 Administration Area, haul road, WPL, and the
13 footprint of the 60-inch storm water line excavation, precertification scans were performed according to
14 guidelines established in Section 3.3.3 of the SEP. These precertification activities were conducted to
15 evaluate residual radiological contamination patterns as specified in the PSP Guidelines for General
16 Characterization for Site-wide Soil Remediation (DOE 2005a). The results of all precertification scans in
17 the area are presented in Appendix B.

18
19 Following precertification real-time scans in the WPL, Administration Area, haul road, and prior to the
20 excavation of the 60-inch line, physical precertification samples were collected following certification
21 guidelines under V/FCNs 20810-PSP-0006-129, 151, and 165 (respectively). The last precertification
22 samples collected in Area 5 Administration Area and WPL were from the footprint of the 60-inch storm
23 water line excavation. The precertification data are presented in Appendix C. A statistical analysis of
24 these data will be presented in the Certification Report for this area.

3.0 AREA-SPECIFIC CONSTITUENTS OF CONCERN

In the OU5 Record of Decision (ROD), there are 80 soil COCs with established FRLs. These COCs were retained for further investigation based on a screening process that considered the presence of the constituent in site soil and the potential risk to a receptor exposed to soil containing this contaminant. In spite of the conservative nature of this COC retention process, many of the COCs with established FRLs have a limited distribution in site soil or the presence of the COC is based on high contract required detection limits (CRDLs). When FRLs were established for these COCs in the OU5 ROD, the FRLs were initially screened against site data presented on spatial maps to establish a picture of potential remediation areas.

By reviewing existing RI/FS data presented on spatial distribution maps, the sitewide list of soil COCs in the OU5 ROD was reduced from 80 to 30. This reduction was possible because the majority of the COCs with FRLs listed in the OU5 ROD have no detections above their corresponding FRL, thus eliminating them from further consideration. The 30 remaining sitewide COCs account for over 99 percent of the combined risk to a site receptor model, and they comprise the list from which all of the remediation ASCOCs are drawn. When planning certification for a remediation area, additional selection criteria are used to derive a subset of these 30 COCs. This subset of COCs is passed along to the certification process.

3.1 SELECTION CRITERIA

The selection process for retaining ASCOCs for a remediation area is driven by applying a set of decision criteria. A soil contaminant will be retained as an ASCOC if:

- It is listed as a soil COC in the OU5 ROD, and it is listed as an ASCOC in Table 2-7 of the SEP for the Remediation Area of interest;
- It can be traced to site use in the remediation area of interest, either through process knowledge or known release of the constituent to the environment;
- Analytical results indicate that a contaminant is present above its FRL, and the above-FRL concentrations are not attributable to false positives or elevated CRDLs;
- Physical characteristics of the contaminant, such as degradation rate and volatility, indicate it is likely to persist in the soil between time of release and remediation; or
- The contaminant is one of the sitewide primary COCs (total uranium, radium-226, radium-228, thorium-238, and thorium-232).

Using the above process, the ASCOCs were refined to those listed in Tables 2-7 of the SEP. The list of ASCOCs is also presented in Table 3-1 with their respective FRLs.

1 3.1.1 Area 5 Administration Area and WPL ASCOC Selection

2 Table 3-1 lists the ASCOCs for Remediation Area 5. Table 3-2 shows how each COC listed in Table 3-1
3 was evaluated for its relevance to Area 5 Administration Area and WPL. Additional COCs have been
4 added to Table 3-2 for sampling of the haul road and the 60-inch line excavation. These additional
5 constituents were based on the source areas of the soil and debris that were transported on the haul road
6 (i.e., Silos and Waste Pits areas), and the list of potential contaminants from 60-inch storm sewer line
7 excavation. Table 3-3 presents the final list of ASCOCs for Area 5 Administration Area and WPL
8 including the haul road and the 60-inch storm sewer line excavation.

1
2
3

TABLE 3-1
ASCOC LIST FOR REMEDIATION AREA 5

ASCOC	FRL
Radionuclides	
Total Uranium	82/20 ^a mg/kg
Radium-226	1.7 pCi/g
Radium-228	1.8 pCi/g
Thorium-228	1.7 pCi/g
Thorium-232	1.5 pCi/g
Organic	
Aroclor-1254	0.13 mg/kg
Aroclor-1260	0.13 mg/kg
Dieldrin	0.015 mg/kg
Metals	
Arsenic	12.0 mg/kg
Beryllium	1.5 mg/kg

4
5
6
7
8
9

^aThe total uranium FRL is lower in the defined high leachability zones (i.e., 20 mg/kg).

mg/kg - milligrams per kilogram

pCi/g - picoCuries per gram

TABLE 3-2
ASCOC RETENTION PROCESS FOR AREA 5 ADMINISTRATION AREA AND WPL

ASCOC	Retained as ASCOC?	Justification	CU(s)
Total Uranium	Yes	Primary Radionuclide	All
Radium-226	Yes	Primary Radionuclide	All
Radium-228	Yes	Primary Radionuclide	All
Thorium-228	Yes	Primary Radionuclide	All
Thorium-232	Yes	Primary Radionuclide	All
Cesium-137	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Lead-210	Yes	Potential contaminant from Waste Pits and Silos material hauling operations.	A5A-PC08
Technetium-99	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Thorium-230	Yes	Potential contaminant from Waste Pits and Silos material hauling operations.	A5A-PC08
Organic			
1,1-dichloroethene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
1,1,1-trichloroethane	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
1,2-dichloroethene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
4-Methyl-2-pentone	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Acetone	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Aroclor-1254	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Aroclor-1260	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Benzene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Benzo(a)pyrene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Benzo(a)anthracene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Benzo(b)fluoranthene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05

TABLE 3-2
(Continued)

ASCOC	Retained as ASCOC?	Justification	CU(s)
Organic (Continued)			
Benzo(g,h,i)perylene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Benzo(k)fluoranthene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Bromodichloromethane	Yes	Potential contaminant from Waste Pits and Silos material hauling operations.	A5A-PC08
Carbon tetrachloride	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Chrysene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Dieldrin	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Dibenzo(a,h)anthracene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Ethylbenzene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Fluoranthene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Indeno(1,2,3-cd)pyrene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Methyl Chloride	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Phenanthrene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Pyrene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Tetrachloroethene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Toluene	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Trichloroethene	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Xylenes, Total	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Metals			
Antimony	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Arsenic	Yes	Detected at concentrations above the FRL. Potential contaminant from Waste Pits and Silos material hauling operations.	All
Barium	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05

**TABLE 3-2
 (Continued)**

ASCOC	Retained as ASCOC?	Justification	CU(s)
Metals (Continued)			
Beryllium	Yes	Detected at concentrations above the FRL. Potential contaminant from Waste Pits and Silos material hauling operations.	All
Cadmium	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Chromium	Yes	Potential contaminant from Waste Pits and Silos material hauling operations. Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC08 A5A-PC09 A5WPL-PC05
Lead	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Mercury	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Molybdenum	Yes	Potential contaminant from 60-inch storm sewer line excavation.	A5A-PC09 A5WPL-PC05
Selenium	Yes	Potential contaminant from 60-inch storm sewer line excavation	A5A-PC09 A5WPL-PC05
Silver	Yes	Potential contaminant from 60-inch storm sewer line excavation	A5A-PC09 A5WPL-PC05
General chemistry			
Fluoride	Yes	Potential contaminant from Waste Pits and Silos material hauling operations.	A5A-PC08

TABLE 3-3
FINAL ASCOC LIST FOR AREA 5 ADMINISTRATION AREA AND WPL

ASCOC	FRL/(BTV)
Radionuclides	
Total Uranium	82/20 ^a mg/kg
Radium-226	1.7 pCi/g
Radium-228	1.8 pCi/g
Thorium-228	1.7 pCi/g
Thorium-232	1.5 pCi/g
Cesium-137	1.4 pCi/g
Lead-210	38 pCi/g
Technetium-99	30 pCi/g
Thorium-230	280 pCi/g
Organic	
1,1-dichloroethene	0.41 mg/kg
1,1,1-trichloroethane ^b	4.3 mg/kg
1,2-dichloroethene	0.16 mg/kg
4-Methyl-2-pentanone (MIK)	2500 mg/kg
Acetone	43,000 mg/kg
Aroclor-1254	0.13 mg/kg
Aroclor-1260	0.13 mg/kg
Benzene	850 mg/kg
Benzo(a)pyrene	2.0 mg/kg
Benzo(a)anthracene	20 mg/kg /(1.0 mg/kg)
Benzo(b)fluoranthene	20 mg/kg
Benzo(g,h,i)perylene	(1.0 mg/kg)
Benzo(k)fluoranthene	200 mg/kg /(1.0 mg/kg)
Bromodichloromethane	4.0 mg/kg
Carbon tetrachloride	2.1 mg/kg
Chrysene	2000 mg/kg /(1.0 mg/kg)
Dibenzo(a,h)anthracene	2.0 mg/kg
Dieldrin	0.015 mg/kg
Ethylbenzene	5,100 mg/kg
Fluoranthene	(10 mg/kg)
Indeno(1,2,3-cd)pyrene	20 mg/kg
Methyl Chloride	37 mg/kg /(85 mg/kg)
Phenanthrene	(5 mg/kg)
Pyrene	(10 mg/kg)
Tetrachloroethene	3.6 mg/kg
Toluene	100,000 mg/kg
Trichloroethene	25 mg/kg
Total Xylenes	920,000 mg/kg

**TABLE 3-3
 (Continued)**

ASCOC	FRL/(BTV)
General chemistry	
Fluoride	78,000 mg/kg
Metals	
Antimony	96 mg/kg / (10 mg/kg)
Arsenic	12.0 mg/kg
Barium	68,000 mg/kg
Beryllium	1.5 mg/kg
Cadmium	82 mg/kg / (5.0 mg/kg)
Chromium ^c	300 mg/kg
Lead	400 mg/kg
Mercury	7.5 mg/kg
Molybdenum	2900 mg/kg / (10 mg/kg)
Selenium	5,400 mg/kg
Silver	29,000 mg/kg / (10 mg/kg)

^a The total uranium FRL is lower in the defined high leachability zones (i.e., 20 mg/kg).

^b The FRL is actually for 1,1,2-trichloroethane because 1,1,1-trichloroethane does not have a FRL. This value will be used for statistical comparison for certification criteria.

^c The FRL is actually for hexavalent chromium because total chromium does not have a FRL.

4.0 CERTIFICATION APPROACH

The certification design for Area 5 Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line excavation differs from the typical certification effort. As discussed in Section 2.1.2, utility trenches below design grade were done with physical precertification samples throughout the Administration Area and WPL per variances 20810-PSP-0006-114, 20810-PSP-0006-126, and 20810-PSP-0006-137. Additionally, precertification surface samples have been collected in the WPL, Administration Area, haul road, and 60-inch storm water line per variances 20810-PSP-0006-129, 20810-PSP-0006-151, 20810-PSP-0006-165, and 20810-PSP-0006-168, respectively. The precertification sampling variances are in Appendix B. These sampling approaches were consistent with the certification criteria established in the SEP including CU size, minimum distance between points, analytical support levels as well as validation of all data.

Based on the above practices being consistent with all SEP protocols, the precertification physical samples that have been collected will be used for final certification. This approach is consistent with other approved certification efforts such as the former Impacted Material Haul Road in Area 2, Phase II - Subarea 3.

All physical precertification data are presented in Appendix C. A statistical analysis of the data shall be summarized in tables presented in the Certification Report.

4.1 CERTIFICATION DESIGN

The certification design for Area 5 Administration Area, WPL, the haul road, and the footprint of the 60-inch storm water line excavation follows the general approach outlined in Section 3.4 of the SEP. The certification design for the trench CUs follows the approach described in the CDL for Area 9, Phase III - Part One (DOE 2004b). This approach ensures that the excavation activities to remove utilities have no effect on the soil in Area 5 Administration Area and WPL.

The layout for Area 5 Administration Area, WPL, haul road, and the footprint of the 60-inch storm water line excavation is depicted on Figure 4-1 and the sample locations for Area 5 Administration Area, haul road, WPL, and the footprint of the 60-inch storm water line excavation are depicted in Figures 4-2, 4-3, 4-4, 4-5, and 4-6.

As discussed in Section 2.1.2, precertification samples were collected from the bottom of utility excavations in Area 5 Administration Area and the WPL. The precertification data and statistical analysis will be presented in the certification report for this area.

As discussed in Section 3.0 of this document, the five primary ASCOCs (total uranium, radium-226, radium-228, thorium-228, and thorium-232) will be retained in each CU. Additional secondary COCs are identified for specific CUs within the certification area.

1 The certification area boundary encompasses the Area 5 Administration Area, the haul road, the WPL, and
2 the footprint of the 60-inch storm water line excavation. Because a portion of these areas are in the former
3 production area, which is an impacted area, they were comprised of Group 1 CUs to allow for more
4 concentrated sampling to ensure excavation activities had no effect on the soil.
5

6 4.1.1 Area 5 Administration Area, Haul Road, and WPL Certification Unit Design

7 The first CUs to be designed were A5WPL-PC01 through A5WPL-PC04. These CUs were designed
8 around the portions of the WPL that were available for sampling. The notch on the western side of CU
9 A5WPL-PC01 represents the turn around area where trucks hauling impacted material from the Storm
10 Water Retention Basin (SWRB) maneuvered while backing up to dump the SWRB material across the
11 contamination boundary of Area 7.
12

13 Once excavation activities were completed in Area 5 Administration Area, CUs A5A-PC01 through A5A-
14 PC06, were designed within the boundaries of the area that was available for sampling. At the time of CU
15 design the Administration Area was bound by the haul road to the north and west of the area.
16

17 The haul road was reconstructed by blading and compacting existing precertified soils following
18 remediation of Area 4B – Part Two, Main Drainage Corridor – 1st Street Area, and the Lime Sludge Pond.
19 It was built with proper run on/run-off controls and to enable impacted material to be transported from the
20 Silos Area to Area 6E stockpiles. Once hauling activities were completed, A5A-PC08 was designed around
21 the section of the haul road that ran through the Administration Area.
22

23 In addition to the precertification scans and samples collected during the excavation and removal of the 60-
24 inch line and its associated bedding material, CUs A5A-PC09 and A5A-PC05 were designed around the
25 final grade excavation footprint of the 60-inch line.
26

27 4.1.2 Sample Location Design

28 The selection of certification sampling locations in the Group 1 CUs was conducted according to
29 Section 3.4.2 of the SEP. Each CU was first divided into 16 approximately equal sub-CUs. Sample
30 locations were then generated by randomly selecting an easting and northing coordinates within the
31 boundaries of each sub-CU, then testing those locations against the minimum distance criteria for the CU.
32 If the minimum distance criteria were not met, an alternative random location was selected for that sub-CU,
33 and all the locations were re-tested. This process continued, until all 16 random locations met the minimum
34 distance criteria.

1 As discussed in Section 2.1.1, the precertification samples that were collected from the bottom of the trenches will be
2 used for certification of the trenches. These sampling locations were placed every 50 feet in the applicable trenches:
3

4 All CUs, sub-CUs, and planned certification sampling locations are shown on Figures 4-2 through 4-5. Four of the
5 16 sample locations (one location from each quadrant of the CU) are designated with a "V," indicating archive
6 sample locations. One sample location in the CU is designated with a "D," indicating a field duplicate sample
7 collection location. Neither archive samples nor duplicate samples were collected during trench sampling.
8


9 4.2 ANALYTICAL METHODOLOGY AND STATISTICAL ANALYSIS

10 Laboratory analysis of certification samples was conducted using an approved analytical method, as discussed
11 in Appendix H of the SEP. Analyses were conducted to Analytical Support Level (ASL) D or E, where all
12 requirements for ASL E are the same as ASL D except the minimum detection level for the selected
13 analytical method must be at least 10 percent of the FRL where practical. A minimum of 10 percent of the
14 laboratory data was validated to Validation Support Level (VSL) D with the remainder validated to VSL B.
15 The validated results were entered into the SED and a statistical analysis will be performed to evaluate the
16 pass/fail criteria for each CU. The statistical approach is discussed in Section 3.4.3 and Appendix G of the
17 SEP, and will be the same for Area 5.
18

19 Two criteria must be met for the CU to pass certification. If the data distribution is normal or lognormal, the
0 first criterion compares the 95 percent Upper Confidence Limit (UCL) on the mean of each primary ASCOC
21 to its FRL. On an individual CU basis, any ASCOC with the 95 percent or 90% UCL above the FRL results in
22 that CU failing certification. If the data distribution is not normal or lognormal, the appropriate nonparametric
23 approach discussed in Appendix G of the SEP will be used to evaluate the first criterion. The second criterion
24 is related to individual samples. An individual sample cannot be greater than two times the FRL (the hotspot
25 criterion). When the given UCL on the mean for each ASCOC is less than its FRL, and the hot spot criterion
26 is met, the CU has met both criteria and will be considered certified.
27

28 There are three conditions that could result in a CU failing certification: 1) high variability in the data set,
29 2) localized contamination, and 3) widespread contamination. Details on the evaluation and responses to these
30 possible outcomes are provided in Section 3.4.5 of the SEP. When all CUs within the scope of this CDL have
31 passed certification, a certification report will be issued. The certification report will be submitted to the U.S.
32 Environmental Protection Agency (EPA) and Ohio Environmental Protection Agency (OEPA) to receive
33 acknowledgement that the pertinent OU remedial actions were completed and the individual CUs are certified
34 to be released for interim or final land use. Section 7.4 of the SEP provides additional details and describes the
35 required content of the certification report.
36

37 The precertification analytical data are presented in Appendix C. A statistical analysis of the data will be
38 presented in the certification report.
39



LEGEND:




FIGURE 4-1. AREA 5 CU LOCATION MAP




FIGURE 4-2. AREA 5 WEST PARKING LOT CERTIFICATION SAMPLE LOCATIONS





FIGURE 4-3. AREA 5 ADMINISTRATION AREA CERTIFICATION SAMPLE LOCATIONS

V = ARCHIVE SAMPLE
D = DUPLICATE SAMPLE



STATE PLANAR COORDINATE SYSTEM 1983
v:\2fm12\dgn\05_haul_101.dgn

LEGEND:

● SAMPLE LOCATION




FIGURE 4-4. AREA 5 ADMINISTRATION AREA HAUL ROAD CERTIFICATION SAMPLE LOCATIONS


13-OCT-2006

006314

V:\2006\11\24\05_157.dgn

STATE PLANNER COORDINATE SYSTEM 1983

13-OCT-2006



LEGEND:

• SAMPLE LOCATION




FIGURE 4-6. AREA 5 60-INCH LINE CERTIFICATION SAMPLE LOCATIONS

1
2
3 **5.0 SCHEDULE**

4 The following draft schedule shows key activities for the completion of the work within the scope of this
5 CDL. Implementation of this schedule is pending funding availability. If necessary, an extension will be
6 requested.

<u>Activity</u>	<u>Target Date</u>
Submittal of Certification Design Letter	September 29, 2006
Start of Certification Sampling	Completed
Complete Field Work	Completed
Complete Analytical Work	Completed
Complete Data Validation and Statistical Analysis	Completed
Submit Certification Report	October 24, 2006 ^a

7
8 ^a The date for submittal of the CDL and Certification Report are commitments to EPA and OEPA. Other
9 dates are internal target completion dates.

REFERENCES

- 1
2
3 U.S. Department of Energy, 1995a "Remedial Investigation Report Operable Unit 3," Final, Fernald
4 Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
5
6 U.S. Department of Energy, 1995b "Remedial Investigation Report Operable Unit 5," Final, Fernald
7 Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
8
9 U.S. Department of Energy, 1995c "Feasibility Study Report Operable Unit 3," Final, Fernald
10 Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
11
12 U.S. Department of Energy, 1995d "Feasibility Study Report Operable Unit 5," Final, Fernald
13 Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
14
15 U.S. Department of Energy, 1996, "Record of Decision for Remedial Action at Operable Unit 5," Final,
16 Fernald Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
17
18 U.S. Department of Energy, 1998, "Sitewide Excavation Plan," Final, Fernald Environmental Management
19 Project, DOE, Fernald Area Office, Cincinnati, Ohio.
20
21 U.S. Department of Energy, 2001, "Addendum to the Sitewide Excavation Plan," Final, Fernald
22 Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
23
24 U.S. Department of Energy, 2002, "Project Specific Plan for Predesign Investigation in Area 5,"
25 Revision 0, Fernald Environmental Management Project, DOE, Fernald Area Office, Cincinnati, Ohio.
26
27 U.S. Department of Energy, 2004a, "Implementation Plan for Area 3B/4B/5," Final, Fernald Closure
28 Project, DOE, Fernald Area Office, Cincinnati, Ohio
29
30 U.S. Department of Energy, 2004b, "Certification Design Letter for Area 9, Phase III Abandoned Outfall
31 Line - Part One," Final, Fernald Closure Project, DOE, Fernald Area Office, Cincinnati, Ohio.
32
33 U.S. Department of Energy, 2005a, "Project Specific Plan Guidelines for General Characterization for
34 Sitewide Soil Remediation," Revision 2, PCN 1, Fernald Closure Project, DOE, Fernald Area Office,
35 Cincinnati, Ohio.
36
37 U.S. Department of Energy, 2005b, "Access to and Management of a Certified Area (CA)," FCP
38 Procedure EP-0008, Revision 5, Fernald Closure Project, DOE, Fernald Area Office, Cincinnati, Ohio.

APPENDIX A
PRECERTIFICATION REAL-TIME SCAN DATA FOR AREA 5
ADMINISTRATION AREA, WEST PARKING LOT, HAUL ROAD, AND
THE 60-INCH STORM SEWER LINE EXCAVATION FOOTPRINT

TABLE A-1
AREA 5 ADMINISTRATION AREA AND WEST PARKING LOT -
HPGe RESULTS DETECTOR HEIGHT 31 cm

Location ID	Measurement Date	Northing	Easting	Detector Height (cm)	Ra-226 (pCi/g)	Th-232 (pCi/g)	Total U (ppm)
A5-WPL-P2-638	05Aug051	479271	1349306	31	2.996	0.834	18.7
A5-WPL-P2-637	05Aug051	479422	1349456	31	2.353	0.635	20.4
A5-WPL-P2-742	10Oct051	479164	1349254	31	1.361	0.898	0
A5-WPL-P2-742-D	10Oct051	479164	1349254	31	1.297	0.916	0
A5-WPL-P2-743	10Oct051	479103	1349266	31	1.701	1.02	16
A5-WPL-P2-791	19Oct051	479197	1349224	31	1.24	0.694	0
ADMIN&WPL-P2-2243	16Jan061	479555	1349556	31	1.82	0.867	0.105
ADMIN&WPL-P2-2243-D	16Jan061	479554	1349556	31	1.648	1.02	17.3
ADMIN&WPL-P2-2246	16Jan061	479601	1349632	31	1.768	1.04	0.101
ADMIN&WPL-P2-2247	16Jan061	479918	1349287	31	1.782	1.04	28.3
ADMIN&WPL-P2-2509	16Feb061	479742	1349783	31	1.634	1.12	0.103
ADMIN&WPL-P2-2509-D	16Feb061	479742	1349783	31	1.807	1.15	11.8
ADMIN&WPL-P2-2511	16Feb061	479707	1349689	31	1.521	0.895	14.6
ADMIN&WPL-P2-2513	16Feb061	479711	1349666	31	1.521	0.896	9.18E-02
ADMIN&WPL-P2-2510	16Feb061	479735	1349771	31	1.75	1.1	0.104
ADMIN&WPL-P2-2512	16Feb061	479737	1349706	31	1.65	0.944	19
ADMIN&WPL-P2-2512-D	16Feb061	479737	1349706	31	1.71	0.953	19.1
ADMIN&WPL-P2-2514	16Feb061	479714	1349646	31	1.74	0.946	14.2
ADMIN&WPL-P2-2516	16Feb061	479674	1349567	31	1.75	1.03	16.4
ADMIN&WPL-P2-2518	16Feb061	479793	1349416	31	1.49	1.14	11.9
ADMIN&WPL-P2-2520	16Feb061	479897	1349296	31	1.28	0.822	16.2
ADMIN&WPL-P2-2522	16Feb061	479728	1349756	31	1.65	1.04	14.5
ADMIN&WPL-P2-2524	16Feb061	479725	1349773	31	1.76	1.03	11.9
ADMIN&WPL-P2-2532	17Feb061	479470	1349419	31	1.042	0.932	35.3
ADMIN&WPL-P2-2532-D	17Feb061	479470	1349419	31	1.055	0.971	31.7
ADMIN&WPL-P2-2533	17Feb061	479516.1	1349391.3	31	0.935	0.895	130
ADMIN&WPL-P2-4512	28Jul061	479467	1349888	31	1.935	0.733	17.5
ADMIN&WPL-P2-4512-D	28Jul061	479467	1349888	31	2.025	0.737	18.9
A4BPT2-CONF-P2-4830	17Aug061	479398	1349364	31	1.374	0.811	14.1
ADMIN&WPL-P2-5030	30Aug061	479320	1349262	31	1.37	1.15	0
ADMIN&WPL-P2-5030-D	30Aug061	479320	1349262	31	1.51	1.12	7.94E-02
ADMIN&WPL-P2-5031	30Aug061	479504	1349229	31	1.21	0.702	17.5
ADMIN&WPL-P2-5034	30Aug061	479755	1349613	31	1.35	0.972	0
ADMIN&WPL-P2-5051	31Aug061	479495	1349192	31	1.56	0.947	5.62E-02
ADMIN&WPL-P2-5417	27Sep061	479589	1349776	31	1.254	0.828	0
ADMIN&WPL-P2-5417-D	27Sep061	479589	1349776	31	1.283	0.793	16.1

TABLE A-1
AREA 5 ADMINISTRATION AREA AND WEST PARKING LOT -
HPGe RESULTS DETECTOR HEIGHT 31 cm

Location ID	Measurement Date	Northing	Easting	Detector Height (cm)	Ra-226 (pCi/g)	Th-232 (pCi/g)	Total U (ppm)
ADMIN&WPL-P2-5416	27Sep061	479652	1349914	31	2.163	0.733	25.6
ADMIN&WPL-P2-5416-D	27Sep061	479652	1349914	31	2.201	0.796	27.7
ADMIN&WPL-PHYS-31-P3-4783	14Aug061	479272	1349141	31	1.24	0.731	0
ADMIN&WPL-CONF-P1-5006	25Aug061	479976	1349591	31	1.56	0.937	12.4
ADMIN&WPL-CONF-P1-5007	25Aug061	479986	1349529	31	1.67	1.01	12
ADMIN&WPL-CONF-P1-5008	25Aug061	479893	1349521	31	1.612	0.74	7.57
ADMIN&WPL-CONF-P1-5009	25Aug061	479893	1349503	31	1.754	0.735	13.1
ADMIN&WPL-CONF-P1-5010	25Aug061	479906	1349421	31	1.475	0.863	17.1
ADMIN&WPL-CONF-P1-5011	25Aug061	479916	1349390	31	1.719	0.755	11.5
ADMIN&WPL-CONF-P1-5012	25Aug061	479940	1349450	31	1.578	0.816	46.3

TABLE A-2
AREA 5 ADMINISTRATION AREA AND WEST PARKING LOT -
HPGe RESULTS DETECTOR HEIGHT 15 cm

Location ID	Measurement Date	Northing	Easting	Detector Height (cm)	Ra-226 (pCi/g)	Th-232 (pCi/g)	Total U (ppm)
ADMIN&WPL-PHYS-15-P3-4766	14Aug062	479272	1349141	15	1.16	0.874	8.55E-02

Figure A-1 Area 5 Administration Area and West Parking Lot Phase 1 Total Gross Counts per Second



Data Groups: GATOR_0638_08-02-2005, 0643_08-03-2005, 0779_01-10-2006, 0782_01-16-2006, 1035_08-03-2006
 RSS1_2144_09-06-2005, 2212_10-05-2005, 2237_10-18-2005, 2375_01-10-2006, 2381_01-16-2006, 2388_01-27-2006
 2406_02-09-2006, 2412_02-10-2006, 2420_02-15-2006, 2714_07-25-2006, 2733_08-01-2006, 2888_09-27-2006
 RSS2_1204_10-05-2005, 1402_07-25-2006
 RSS3_1190_01-26-2006, 1193_01-27-2006, 1255_02-15-2006, 1591_08-01-2006
 RSS4_0799_01-26-2006, 0824_02-08-2006, 0852_02-15-2006, 0854_02-15-2006, 1451_07-25-2006, 1459_07-28-2006
 Measurement Period: 08-02-2005 thru 09-27-2006

Areas not showing coverage are due to standing water and staged soil stockpiles.



Nal Tcps	
	0 to 3000
	3000 to 5000
	5000 to 15000
	15000 to 18000
	18000 to 99999


RTIMP DWG ID: ADMIN_P1_TC.srf
 Project ID: Gen Char for Site Soil Rem 20300-PSP-0011
 Prepared: D. Seiller 09-28-2006
 Support Data: ADMIN_P1.xls



Figure A-2 Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Radium-226

Data Groups: GATOR_0638_08-02-2005, 0643_08-03-2005, 0779_01-10-2006, 0782_01-16-2006, 1035_08-03-2006
 RSS1_2144_09-06-2005, 2212_10-05-2005, 2237_10-18-2005, 2375_01-10-2006, 2381_01-16-2006, 2388_01-27-2006
 2406_02-09-2006, 2412_02-10-2006, 2420_02-15-2006, 2714_07-25-2006, 2733_08-01-2006, 2888_09-27-2006
 RSS2_1204_10-05-2005, 1402_07-25-2006
 RSS3_1190_01-26-2006, 1193_01-27-2006, 1255_02-15-2006, 1591_08-01-2006
 RSS4_0799_01-26-2006, 0824_02-08-2006, 0852_02-15-2006, 0854_02-15-2006, 1451_07-25-2006, 1459_07-28-2006
 Measurement Period: 08-02-2005 thru 09-27-2006

Areas not showing coverage are due to standing water and staged soil stockpiles.



— High Leachability boundary
 — CDL Boundary
 — Sub Area Boundary

NaI Ra-226 pCi/g	
	-9999 to 5.1
	5.1 to 9999


RTIMP DWG ID: ADMIN_P1_RA.srf
 Project ID: Gen Char for Site Soil Rem 20300-PSP-0011
 Prepared: D. Seiller 09-28-2006
 Support Data: ADMIN_P1.xls

Figure A-3 Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Thorium-232



Data Groups: GATOR_0638_08-02-2005, 0643_08-03-2005, 0779_01-10-2006, 0782_01-16-2006, 1035_08-03-2006
 RSS1_2144_09-06-2005, 2212_10-05-2005, 2237_10-18-2005, 2375_01-10-2006, 2381_01-16-2006, 2388_01-27-2006
 2406_02-09-2006, 2412_02-10-2006, 2420_02-15-2006, 2714_07-25-2006, 2733_08-01-2006, 2888_09-27-2006
 RSS2_1204_10-05-2005, 1402_07-25-2006
 RSS3_1190_01-26-2006, 1193_01-27-2006, 1255_02-15-2006, 1591_08-01-2006
 RSS4_0799_01-26-2006, 0824_02-08-2006, 0852_02-15-2006, 0854_02-15-2006, 1451_07-25-2006, 1459_07-28-2006
 Measurement Period: 08-02-2005 thru 09-27-2006

Areas not showing coverage are due to standing water and staged soil stockpiles.



High Leachability boundary CDL Boundary Sub Area Boundary

Nal Th-232 pCi/g
 □ -9999 to 4.5
 □ 4.5 to 9999


RTIMP DWG ID: ADMIN_P1_TH.srf
 Project ID: Gen Char for Site Soil Rem 20300-PSP-0011
 Prepared: D. Seiller 09-28-2006
 Support Data: ADMIN_P1.xls



Figure A-4 Area 5 Administration Area and West Parking Lot Phase 1 Moisture Corrected Total Uranium

Data Groups: GATOR_0638_08-02-2005, 0643_08-03-2005, 0779_01-10-2006, 0782_01-16-2006, 1035_08-03-2006
 RSS1_2144_09-06-2005, 2212_10-05-2005, 2237_10-18-2005, 2375_01-10-2006, 2381_01-16-2006, 2388_01-27-2006
 2406_02-09-2006, 2412_02-10-2006, 2420_02-15-2006, 2714_07-25-2006, 2733_08-01-2006, 2888_09-27-2006
 RSS2_1204_10-05-2005, 1402_07-25-2006
 RSS3_1190_01-26-2006, 1193_01-27-2006, 1255_02-15-2006, 1591_08-01-2006
 RSS4_0799_01-26-2006, 0824_02-08-2006, 0852_02-15-2006, 0854_02-15-2006, 1451_07-25-2006, 1459_07-28-2006
 Measurement Period: 08-02-2005 thru 09-27-2006

Areas not showing coverage are due to standing water and staged soil stockpiles.



 High Leachability boundary	 CDL Boundary	 Sub Area Boundary
---	--	---


NaITU ppm	
Non-High Leachability Area	High Leachability Area
 -9999 to 246	 -9999 to 60
 246 to 875	 60 to 875
 875 to 9999	 875 to 9999

RTIMP DWG ID: ADMIN_P1_TU.srf
 Project ID: Gen Char for Site Soil Rem 20300-PSP-0011
 Prepared: D. Seiller 09-28-2006
 Support Data: ADMIN_P1.xls

Figure A-5 Administration Area and West Parking Lot Phase 2 Moisture Corrected Radium-226


Includes all Phase 2 measurements

Phase 2 Data Groups: 31204_08-05-2005,02-16-2006,02-17-2006
31265_10-10-2005,08-30-2006
30687_10-19-2005,01-16-2006,02-16-2006,07-28-2006
40293_08-17-2006,09-27-2006
30699_08-31-2006,09-01-2006,09-27-2006



Confirmation Phase 2 Data Groups: 40293_08-21-2006

Measurement Period: 08-05-2005 thru 09-27-2006



HPGe Ra-226 pCi/g	
○	0 to 5.1
○	5.1 to 999

RTIMP DWG ID: ADMIN&WPL_P2_RA.srf
 Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
 Prepared: D.Seiller 09-28-2006
 Support Data: ADMIN&WPL_P2.xls

Figure A-6 Administration Area and West Parking Lot Phase 2 Moisture Corrected Thorium-232


Includes all Phase 2 measurements

Phase 2 Data Groups: 31204_08-05-2005,02-16-2006,02-17-2006
31265_10-10-2005,08-30-2006
30687_10-19-2005,01-16-2006,02-16-2006,07-28-2006
40293_08-17-2006,09-27-2006
30699_08-31-2006,09-01-2006,09-27-2006



Confirmation Phase 2 Data Groups: 40293_08-21-2006

Measurement Period: 08-05-2005 thru 09-27-2006



HPGe Th-232 pCi/g


- 0 to 4.5
- 4.5 to 999

RTIMP DWG ID: ADMIN&WPL_P2_TH.srf
 Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
 Prepared: D.Seiller 09-28-2006
 Support Data: ADMIN&WPL_P2.xls

Figure A-7 Administration Area and West Parking Lot Phase 2 Moisture Corrected Total Uranium


Includes all Phase 2 measurements

Phase 2 Data Groups: 31204_08-05-2005,02-16-2006,02-17-2006
 31265_10-10-2005,08-30-2006
 30687_10-19-2005,01-16-2006,02-16-2006,07-28-2006
 40293_08-17-2006,09-27-2006
 30699_08-31-2006,09-01-2006,09-27-2006



Confirmation Phase 2 Data Groups: 40293_08-21-2006

Measurement Period: 08-05-2005 thru 09-27-2006



<p>HPGe TU ppm Non-High leachability Area</p> <p>● 0 to 246 ○ 246 to 999</p>	<p>HPGe TU ppm High Leachability Area</p> <p>● 0 to 60 ○ 60 to 999</p>
--	--

RTIMP DWG ID: ADMIN&WPL_P2_TU.srf
 Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
 Prepared: D.Seiller 09-28-2006
 Support Data: ADMIN&WPL_P2.xls

Figure A-8 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Radium-226



Data Group: 40293_08-14-2006

Measurement Period: 08-14-2006 thru 08-14-2006




High Leachability boundary CDL Boundary Sub Area Boundary

HPGe Ra-226

- -999 to 5.1
- 5.1 to 9999

RTIMP DWG ID: ADMIN&WPL_PHYS_P3_RA.srf
Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
Prepared: D.Seiller 09-28-2006
Support Data: ADMIN&WPL_PHYS_P3.xls

Figure A-9 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Thorium-232



Data Group: 40293_08-14-2006

Measurement Period: 08-14-2006 thru 08-14-2006




High Leachability boundary CDL Boundary Sub Area Boundary

HPGe Th-232

- -999 to 4.5
- 4.5 to 9999


RTIMP DWG ID: ADMIN&WPL_PHYS_P3_TH.srf
Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
Prepared: D.Seiller 09-28-2006
Support Data: ADMIN&WPL_PHYS_P3.xls

Figure A-10 Administration Area and West Parking Lot Phase 3 (Physical Sample) Moisture Corrected Total Uranium



Data Group: 40293_08-14-2006

Measurement Period: 08-14-2006 thru 08-14-2006



High Leachability boundary CDL Boundary Sub Area Boundary

HPGe TU ppm	
○	-999 to 246
○	246 to 9999


RTIMP DWG ID: ADMIN&WPL_PHYS_P3_TU.srf
Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
Prepared: D.Seiller 09-28-2006
Support Data: ADMIN&WPL_PHYS_P3.xls

Figure A-11 Administration Area and West Parking Lot Confirmation of Precertification Phase 1- Moisture Corrected Total Uranium



Data Groups: RSS3_1632_08-16-2006,40227_08-25-2006

Measurement Period: 08-16-2006 thru 08-25-2006



——— High Leachability boundary
 ——— CDL Boundary
 ——— Sub Area Boundary

Nal TU ppm	
■	-9999 to 246
■	246 to 875
■	875 to 9999

HPGe TU ppm	
○	-999 to 246
○	246 to 928
○	928 to 9999

RTIMP DWG ID: ADMIN&WPL_CONF_P1_TU.srf
 Project ID: Gen. Char. for Site. Soil Rem 20300-PSP-0011
 Prepared: D.Seiller 09-28-2006
 Support Data: ADMIN&WPL_CONF_P1.xls

APPENDIX B
VARIANCE/FIELD CHANGE NOTICES FOR
PRECERTIFICATION SAMPLING IN AREA 5
ADMINISTRATION AREA, HAUL ROAD, AND WEST PARKING LOT

VARIANCE / FIELD CHANGE NOTICE	Significant? (Yes or No): NO	V/F: 20810-PSP-0006-114
WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1		Page: 1 of 3
PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5		Date: 8/02/05

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples for Precertification of the West Parking Lot of Area 5 (Area 5 WPL) following the removal of utilities in the former West Parking Lot (Figure 1). Construction will be excavating known utilities; however, the possibility exists that unknown utilities will be uncovered during excavation. All sampling locations will be field located approximately every ~~forty~~ ^{FIFTY} feet along the bottom of the excavation. All samples will be collected from the bottom of the excavation from the bucket of an excavator (if necessary) after the piping and bedding material has been removed. The goal will be to collect samples from the top six inches of soil from the bottom of the excavation.

Additionally, if there is evidence of leakage from the piping (e.g. broken, cracked, or disjointed piping), then a biased sample location will be flagged, and samples will be collected from the floor and both sidewalls approximately one foot from the floor of the excavation.

The area specific constituents of concern (ASCOCs) for this precertification effort will be primary radionuclides (total uranium, radium-226, radium-228, thorium-228, and thorium-232) [TAL F]. The sampling and analytical requirements and TAL are listed on Attachment 1.

The first sample ID shall be ASEC-WPL-T-1^R and each additional sample ID will be sequentially numbered (e.g. second sample ID is ASEC-WPL-T-2^R).

Where:

- ASEC = Area 5 Excavation Control
- WPL = West Parking Lot
- T = trench
- 1, 2, 3, etc. = Consecutive Sample Numbers (Locations)
- R = Radiological analysis

- Field sketch required: Yes
- Surveying required: Yes. Surveying will survey these locations.
- QC samples required: No
- Field data validation: Yes
- Analytical data validation: Yes 10%D, 90%B
- Off-site data package requirements (if applicable): ASL D(E)
- The highest total uranium result from this area is 35.4 ppm at location A5A-45.

Justification:

Because the utilities in this area are so deep, it is necessary to backfill the trenches after the utilities have been removed in order to ensure the area is left in a safe condition. Therefore, samples will be collected from the bottom of the excavation prior to backfilling the trenches similarly to the sampling performed during the excavation of the Abandoned Outfall Line.

REQUESTED BY: Greg Lupton Date: 8/02/05

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE <i>[Signature]</i>	8-3-05	X	PROJECT MANAGER: J.F. Chang <i>[Signature]</i>	8/3/05
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: Frank Miller <i>[Signature]</i>	8/3/05
X	ANALYTICAL CUSTOMER SUPPORT: WAD <i>[Signature]</i>	8-4-05		RTIMP Manager	
*			X	SAMPLING MANAGER: <i>[Signature]</i>	8/3/05

VARIANCE/FCN APPROVED YES NO REVISION REQUIRED: YES NO

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

Analyte ^a	Method ^a	Matrix	Preserve	TAT	Hold Time	Container ^b	Minimum Mass/Volume
Radiological (TAL F)	Gamma Spec	Solid	none	30 days	12 months	Plastic core liner or glass or polyethylene sample container	300 g (900 g) ^c

^a Samples will be analyzed according to Analytical Support Level (ASL) D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^c At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in the CU in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

**TAL F
(Radiological - ASL D/E*)**


Analyte	On-Property FRL	MDL
Total Uranium	82 mg/kg	8.2 mg/kg
Radium-226	1.7 pCi/g	0.17 pCi/g
Radium-228	1.8 pCi/g	0.18 pCi/g
Thorium-228	1.7 pCi/g	0.17 pCi/g
Thorium-232	1.5 pCi/g	0.15 pCi/g

*Analytical requirements will meet ASL D but the MDL may cause some analyses to be considered ASL E.

MDL – minimum detection level

mg/kg – milligrams per kilogram

pCi/g – picoCuries per gram




LEGEND:



A5 WEST PARKING LOT

SCALE



DRAFT

v:\02\frt12\dwg\05_1346.dgn
STATE PLANAR COORDINATE SYSTEM 1983

FIGURE 1. AREA 5 WEST PARKING LOT PRECERTIFICATION AREA

02-AUG-2005

006314

VARIANCE / FIELD CHANGE NOTICE	Significant? (Yes or No): NO	V/F: 20810-PSP-0006-126
WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1		Page: 1 of 2
PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5		Date: 10/04/05

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples and real-time scanning for precertification of the Area 5 Admin Area (V/FCN 20810-PSP-0006-80) following the removal of utilities in the Precertification Units A5A-PC05, A5A-PC06, and A5A-PC-07. Construction will be excavating known utilities and will have to back fill some of the areas to maintain the open roadway. All sampling locations will be field located approximately every fifty feet along the bottom of the excavation. Upon completion of the removal of subsurface utilities and bedding material, the excavator will excavate a bucket-load of soil from the bottom of the trench every 50 feet. All samples will be collected from this excavated material.

The area specific constituents of concern (ASCOCs) for this precertification/certification effort will be primary radionuclides (total uranium, radium-226, radium-228, thorium-228, and thorium-232) [TAL F]. The sampling and analytical requirements and TAL are listed on Attachment 1.

The first sample ID shall be A5A-PC2-T-1^R and each additional sample ID will be sequentially numbered (e.g. second sample ID is A5A-PC2-T-2^R).

- Where:
- A5A = Area 5 Admin
 - PC2 = Precertification Number 2
 - T = trench
 - 1, 2, 3, etc. = Consecutive Sample Numbers (Locations)
 - R = Radiological analysis

Field sketch required: Yes
 Surveying required: Yes. Surveying will survey these locations.
 Field QC samples required: No
 Field data validation: Yes
 Analytical data validation: Yes, VSL D
 Off-site data package requirements (if applicable): ASL D(E)
 The highest total uranium result from this area is 368 ppm at RI/FS location ZONE 1-82.

Justification:
 Because the utilities in this area are so deep, it is necessary to backfill the trenches after the utilities have been removed in order to maintain the roadway and to ensure the area is left in a safe condition. Therefore, samples will be collected from the bottom of the excavation prior to backfilling the trenches similarly to the sampling performed during the excavation of the utilities in the West Parking Lot.

REQUESTED BY: Krista Flaugh Date: 10/05/05

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE <i>[Signature]</i>	10-4-05	X	PROJECT MANAGER: I.D. <i>[Signature]</i>	10/6/05
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: F. Miller <i>[Signature]</i>	10/4/05
X	ANALYTICAL CUSTOMER SUPPORT: <i>Paul S. McWhigan</i>	10/4/05		RTIMP Manager	
X	WAD <i>Scott Osborn</i>	10/5/05	X	SAMPLING MANAGER: <i>Tom Buhays</i>	10/4/05

VARIANCE/FCN APPROVED YES NO REVISION REQUIRED: YES NO

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

Analyte ^a	Method ^a	Matrix	Preserve	Hold Time	Container ^b	Minimum Mass/Volume
Radiological (TAL F)	Gamma Spec	Solid	none	12 months	Plastic core liner or glass or polyethylene sample container	400 g (1200 g ^c)

^a Samples will be analyzed according to Analytical Support Level (ASL) D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^c At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

ICP/MS - inductively coupled plasma/mass spectroscopy

LSC - liquid scintillation counting

**TAL F
(Radiological - ASL D/E*)**

Analyte	On-Property FRL	MDL
Total Uranium	82 mg/kg	8.2 mg/kg
Radium-226	1.7 pCi/g	0.17 pCi/g
Radium-228	1.8 pCi/g	0.18 pCi/g
Thorium-228	1.7 pCi/g	0.17 pCi/g
Thorium-232	1.5 pCi/g	0.15 pCi/g

*Analytical requirements will meet ASL D but the MDL may cause some analyses to be considered ASL E.

MDL - minimum detection level

mg/kg - milligrams per kilogram

pCi/g - picoCuries per gram

VARIANCE / FIELD CHANGE NOTICE

Significant?
(Yes or No): **YES**

V/F: 20810-PSP-0006-129

WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1

Page: 1 of 8

PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5

Date: 10/31/05

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples for Precertification of the West Parking Lot of Area 5 (Area SWPL) following the removal of the asphalt, underlying gravel, and utilities in the area (see Figure 1).

To ensure ample coverage for precertification, this area was gridded into areas not greater than 250' by 250' similar to a Group 1 certification unit. With this gridding process, four areas were defined (see Figure 2). Each of the defined areas has been sub-divided into 16 approximately equal sub-areas. Sample locations within each of the defined areas have been generated by randomly selecting an easting and northing coordinate within the boundaries of each sub-area, then each location was tested against the minimum distance criteria for each defined area to ensure that all 16 random locations have sufficient spacing. One sample location in each of the defined areas has been designated with a "D", indicating a field duplicate sample collection location. All samples within each defined area will be collected for analysis from 0 to 6 inches. The planned precertification sampling locations are shown on Figure 3.

The area specific constituents of concern (ASCOCs) for this entire precertification effort will be the primary radionuclides (total uranium, radium-226, radium-228, thorium-228, and thorium-232) TAL F. Additionally, arsenic (TAL H) is an ASCOC in PC04 only. These sampling and analytical requirements and the TAL are listed on Attachment 1. The sample locations and identifiers are listed in Attachment 2.

If "push tubes" are used for sample collection, two container blanks will be collected – one before sample collection begins and one at the conclusion of sample collection. The container blank samples will be analyzed for the primary radiological COCs that are identified in TAL F. If an alternate sample collection method is used, one rinsate will be collected at a minimum frequency of one per 20 pieces of equipment reused in the field.

Analyses will be conducted to Analytical Support Level (ASL) D or E, where all requirements for ASL E are the same as ASL D except the minimum detection level for the selected analytical method must be at least 10 percent of the FRL. A minimum of 10 percent of the laboratory data will be validated to Validation Support Level (VSL) D with the remainder validated to VSL B.

Historical data will be used for shipment of the samples collected under this V/FCN. The highest total uranium result from this area is 35.4 ppm at location A5A-45.

Justification:

This area is to be used as a temporary parking lot for Silos clean truck staging, which will require importing clean gravel to be used as a base similar to the East Parking Lot. Samples need to be collected before the clean gravel is brought to the area.

REQUESTED BY: Greg Lupton

Date: 10/31/05

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE: <i>[Signature]</i>	11/1/05	X	PROJECT MANAGER: J.D. [Signature]	10/31/05
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: Frank Miller	10/31/05
X	ANALYTICAL CUSTOMER SUPPORT: <i>[Signature]</i>	11/1/05		RTIMP Manager	
X	WAO: <i>[Signature]</i>		X	SAMPLING MANAGER: <i>[Signature]</i>	10/31/05
VARIANCE/FCN APPROVED [X] YES [] NO			REVISION REQUIRED: [] YES [x] NO		

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

Analyte ^a	Method ^a	Matrix	Preserve	TAT	Hold Time	Container ^b	Minimum Mass/Volume
Rads/Metals (TAL F and/or H)	Gamma Spec	Solid	Cool to 4 degrees	30 days	12 months	Plastic core liner or glass or polyethylene sample container	500 g (1500 g) ^c
	ICP or ICP/MS				6 months		
Metals (TAL H)	ICP or ICP/MS	Liquid (rinsate ^d)	HNO ₃ pH<2	30 days	6 months	Polyethylene	500 ml
Radiological (TAL F)	Gamma Spec	Liquid (rinsate ^d)	HNO ₃ pH<2	30 days	6 months	Polyethylene	4 liters

^a Samples will be analyzed according to Analytical Support Level (ASL) D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^c At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in the CU in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

^d If "push tubes" are used for sampling, the off-site laboratories will be sent container blanks. If an alternative sample method is used, a rinsate will be collected by the Field Technicians.

**TAL F
(Radiological - ASL D/E*)**

Analyte	On-Property FRL	MDL
Total Uranium	82 mg/kg	8.2 mg/kg
Radium-226	1.7 pCi/g	0.17 pCi/g
Radium-228	1.8 pCi/g	0.18 pCi/g
Thorium-228	1.7 pCi/g	0.17 pCi/g
Thorium-232	1.5 pCi/g	0.15 pCi/g

**TAL H
(Metals - ASL D/E*)**

Analyte	On-Property FRL	MDL
Arsenic	12 mg/kg	1.2 mg/kg

*Analytical requirements will meet ASL D but the MDL may cause some analyses to be considered ASL E.

MDL – minimum detection level

pCi/g – picoCuries per gram

ATTACHMENT 2
AREA 5WPL SAMPLE LOCATIONS AND IDENTIFIERS

Defined Area	Defined sub-Area Location	Depth	Sample ID	Analysis (TAL)	Northing	Easting
A5WPL-PC01	1-1	0"-6"	A5WPL-PC01-1^R	F	479479.2	1349378.51
	1-2	0"-6"	A5WPL-PC01-2^R	F	479450.71	1349406.31
	1-3	0"-6"	A5WPL-PC01-3^R	F	479379.12	1349345.68
	1-4	0"-6"	A5WPL-PC01-4^R	F	479410.4	1349415.2
	1-5	0"-6"	A5WPL-PC01-5^R	F	479437.43	1349477.64
	1-6	0"-6"	A5WPL-PC01-6^R	F	479456.15	1349556.05
	1-7D	0"-6"	A5WPL-PC01-7^R-D	F	479393.06	1349478.6
	1-8	0"-6"	A5WPL-PC01-8^R	F	479393.01	1349523.37
	1-9	0"-6"	A5WPL-PC01-9^R	F	479346.77	1349358.99
	1-10	0"-6"	A5WPL-PC01-10^R	F	479350.69	1349441.46
	1-11	0"-6"	A5WPL-PC01-11^R	F	479281.19	1349267.64
	1-12	0"-6"	A5WPL-PC01-12^R	F	479300.59	1349333.85
	1-13	0"-6"	A5WPL-PC01-13^R	F	479356.7	1349488.31
	1-14	0"-6"	A5WPL-PC01-14^R	F	479354.26	1349552.48
	1-15	0"-6"	A5WPL-PC01-15^R	F	479304.51	1349440.7
	1-16	0"-6"	A5WPL-PC01-16^R	F	479274.95	1349546.74
A5WPL-PC02	2-1	0"-6"	A5WPL-PC02-1^R	F	479434.5	1349598.06
	2-2D	0"-6"	A5WPL-PC02-2^R-D	F	479431.04	1349716.08
	2-3	0"-6"	A5WPL-PC02-3^R	F	479364.72	1349594.83
	2-4	0"-6"	A5WPL-PC02-4^R	F	479373.13	1349679.13
	2-5	0"-6"	A5WPL-PC02-5^R	F	479414.63	1349760.05
	2-6	0"-6"	A5WPL-PC02-6^R	F	479422.02	1349903.42
	2-7	0"-6"	A5WPL-PC02-7^R	F	479388.73	1349777.15
	2-8	0"-6"	A5WPL-PC02-8^R	F	479383.7	1349858.37
	2-9	0"-6"	A5WPL-PC02-9^R	F	479334.92	1349616.49
	2-10	0"-6"	A5WPL-PC02-10^R	F	479331.84	1349699.4
	2-11	0"-6"	A5WPL-PC02-11^R	F	479280.38	1349637.47
	2-12	0"-6"	A5WPL-PC02-12^R	F	479296.03	1349735.34
	2-13	0"-6"	A5WPL-PC02-13^R	F	479337.57	1349791.03
	2-14	0"-6"	A5WPL-PC02-14^R	F	479336.47	1349878.57
	2-15	0"-6"	A5WPL-PC02-15^R	F	479304.68	1349802.51
	2-16	0"-6"	A5WPL-PC02-16^R	F	479277.22	1349871.13

ATTACHMENT 2
AREA 5WPL SAMPLE LOCATIONS AND IDENTIFIERS

Defined Area	Defined sub-Area Location	Depth	Sample ID	Analysis (TAL)	Northing	Easting
A5WPL-PC03	3-1	0"-6"	A5WPL-PC03-1^R	F	479229.4	1349300.43
	3-2	0"-6"	A5WPL-PC03-2^R	F	479255.1	1349350.53
	3-3	0"-6"	A5WPL-PC03-3^R	F	479186.25	1349283.99
	3-4	0"-6"	A5WPL-PC03-4^R	F	479206.77	1349342.02
	3-5	0"-6"	A5WPL-PC03-5^R	F	479247.53	1349406.94
	3-6	0"-6"	A5WPL-PC03-6^R	F	479230.78	1349531.19
	3-7	0"-6"	A5WPL-PC03-7^R	F	479198.13	1349481.82
	3-8	0"-6"	A5WPL-PC03-8^R	F	479186.01	1349550.17
	3-9	0"-6"	A5WPL-PC03-9^R	F	479143.34	1349257.09
	3-10	0"-6"	A5WPL-PC03-10^R	F	479144.91	1349350.64
	3-11	0"-6"	A5WPL-PC03-11^R	F	479115.29	1349270.46
	3-12	0"-6"	A5WPL-PC03-12^R	F	479115.69	1349407.64
	3-13D	0"-6"	A5WPL-PC03-13^R-D	F	479160.47	1349435.21
	3-14	0"-6"	A5WPL-PC03-14^R	F	479141.4	1349527.51
	3-15	0"-6"	A5WPL-PC03-15^R	F	479089.46	1349482.99
	3-16	0"-6"	A5WPL-PC03-16^R	F	479097.08	1349529.85
A5WPL-PC04	4-1	0"-6"	A5WPL-PC04-1^RM	FH	479221.11	1349600.13
	4-2	0"-6"	A5WPL-PC04-2^RM	FH	479245.11	1349666.69
	4-3	0"-6"	A5WPL-PC04-3^RM	FH	479179.38	1349635.49
	4-4	0"-6"	A5WPL-PC04-4^RM	FH	479200.44	1349699.59
	4-5	0"-6"	A5WPL-PC04-5^RM	FH	479227.91	1349768.62
	4-6	0"-6"	A5WPL-PC04-6^RM	FH	479256.21	1349822.57
	4-7	0"-6"	A5WPL-PC04-7^RM	FH	479190.24	1349773.4
	4-8	0"-6"	A5WPL-PC04-8^RM	FH	479190.49	1349844.42
	4-9D	0"-6"	A5WPL-PC04-9^RM-D	FH	479150.25	1349620.54
	4-10	0"-6"	A5WPL-PC04-10^RM	FH	479139.02	1349679.77
	4-11	0"-6"	A5WPL-PC04-11^RM	FH	479116.44	1349582.65
	4-12	0"-6"	A5WPL-PC04-12^RM	FH	479082.24	1349689.19
	4-13	0"-6"	A5WPL-PC04-13^RM	FH	479138.69	1349802.62
	4-14	0"-6"	A5WPL-PC04-14^RM	FH	479161.26	1349854
	4-15	0"-6"	A5WPL-PC04-15^RM	FH	479103.01	1349779.6
	4-16	0"-6"	A5WPL-PC04-16^RM	FH	479112.15	1349853.8

ATTACHMENT 3
AREA 5WPL SAMPLE LOCATIONS AND IDENTIFIERS

Each soil precertification sample will be assigned a unique sample identification number where:

A5WPL = Sample collected from Remediation Area 5 West Parking Lot

PC = Precertification


= Specific area from which sample was collected

Location = Sample location number within the specific area

^ = The ^ is placed between the location number for the specific area and the analysis type identifier. When used, the information to the left of this symbol identifies the location number and allows the automatic assignment of the location identification number to be transferred to the appropriate field/table in the Sitewide Environmental Database.

Analysis = "R" indicates radiological analysis; "M" indicates metals

QC = Quality control sample. A "D" indicates a field-duplicated sample; "Y" indicates a container blank sample; "X" indicates a rinsate




LEGEND:




A5 WEST PARKING LOT

SCALE



DRAFT

FIGURE 1. AREA 5 WEST PARKING LOT PRECERTIFICATION AREA



DRAFT

LEGEND:

----- FEMP BOUNDARY

SCALE




FIGURE 2. AREA 5 WEST PARKING LOT PRECERTIFICATION SUBAREAS




FIGURE 3. AREA 5 WEST PARKING LOT PRECERTIFICATION SAMPLE LOCATIONS

VARIANCE / FIELD CHANGE NOTICE

Significant?
(Yes or No): **NO**

V/F: 20810-PSP-0006-137

WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1

Page: 1 of 3

PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5

Date: 11/30/05

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples for Precertification of the Administration Area of Area 5 (Area 5A) following the removal of utilities (Figure 1). Construction will be excavating known utilities; however, the possibility exists that unknown utilities will be uncovered during excavation. All sampling locations will be field located approximately every fifty feet along the bottom of the excavation. All samples will be collected from the bottom of the excavation from the bucket of an excavator (if necessary) after the piping and bedding material has been removed. The goal will be to collect samples from the top six inches of soil from the bottom of the excavation.

Additionally, if there is evidence of leakage from the piping (e.g. broken, cracked, or disjointed piping), then a biased sample location will be flagged, and samples will be collected from the floor and both sidewalls approximately one foot from the floor of the excavation.

The area specific constituents of concern (ASCOCs) for this precertification effort will be primary radionuclides (total uranium, radium-226, radium-228, thorium-228, and thorium-232) [TAL F] and beryllium (TAL G). The sampling and analytical requirements and TALs are listed on Attachment 1.

The first sample ID shall be A5A-T-1^R and each additional sample ID will be sequentially numbered (e.g. second sample ID is A5A-T-2^R).

Where:

A5A = Area 5 Administration

T = trench

1, 2, 3, etc. = Consecutive Sample Numbers (Locations)

R = Radiological analysis

Field sketch required: No

Surveying required: Yes. Samplers shall contact Surveying when locations are ready to be surveyed.

Field QC samples required: No

Field data validation: Yes

Analytical data validation: Yes 10%D, 90%B

Off-site data package requirements (if applicable): ASL D(E)

The highest total uranium result from this area is 368 ppm at RI/FS location ZONE 1-82.

Justification:

Because the utilities in this area are so deep, it is necessary to backfill the trenches after the utilities have been removed in order to ensure the area is left in a safe condition. Therefore, samples will be collected from the bottom of the excavation prior to backfilling the trenches similarly to the sampling performed during the excavation of the West Parking Lot.

REQUESTED BY: Greg Lupton

Date: 11/30/05

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE: <i>Dave Wassel</i> DATA QUALITY MANAGEMENT	12-01-05	X	PROJECT MANAGER: J.D. Chiou <i>J.D. Chiou</i>	12/1/05
X	ANALYTICAL CUSTOMER SUPPORT: <i>Arny Meyer</i>	12/6/05	X	CHARACTERIZATION MANAGER: Frank Miller <i>Frank Miller</i> RTIMP Manager	11/30/05
X	<i>Chris Fall</i>	11-30-05	X	SAMPLING MANAGER: <i>Tom Schiller</i>	12/6/05
VARIANCE/FCN APPROVED [X]YES []NO			REVISION REQUIRED: []YES [x]NO		

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:-	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

Analyte ^a	Method ^a	Matrix	Preserve	Hold Time	Container ^b	Minimum Mass/Volume
Rads and Metals (TALs F and G)	Gamma Spec	Solid	Cool, 4° C	12 months	Plastic core liner or glass or polyethylene sample container	400 g (1200 g) ^c
	ICP/MS			6 months		

^a Samples will be analyzed according to Analytical Support Level (ASL) D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^c At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location per release in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

ICP/MS – inductively coupled plasma/mass spectroscopy

LSC – liquid scintillation counting

**TAL F
(Radiological - ASL D/E*)**

Analyte	On-Property FRL	MDL
Total Uranium	82 mg/kg	8.2 mg/kg
Radium-226	1.7 pCi/g	0.17 pCi/g
Radium-228	1.8 pCi/g	0.18 pCi/g
Thorium-228	1.7 pCi/g	0.17 pCi/g
Thorium-232	1.5 pCi/g	0.15 pCi/g

**TAL G
(Metals - ASL D/E*)**

Analyte	On-Property FRL	MDL
Beryllium	1.5 mg/kg	0.15 mg/kg

*Analytical requirements will meet ASL D but the MDL may cause some analyses to be considered ASL E.

MDL – minimum detection level


mg/kg – milligrams per kilogram

pCi/g – picoCuries per gram

V:\92\m12\adgnms-115.dgn

STATE PLANNING COORDINATE SYSTEM 1983

30-NOV-2005




LEGEND:



AREA 5 ADMINISTRATION AREA

SCALE



500 250 0 500 FEET

FIGURE 1.

VARIANCE / FIELD CHANGE NOTICE

Significant?
(Yes or No): **YES**

V/F: 20810-PSP-0006-151

WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1

Page: 1 of 9

PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5

Date: 1/11/06

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples for Precertification of the Area 5 Administration Area following the removal of concrete, underlying gravel, and utilities in the area (see Figure 1).

To ensure ample coverage for precertification, this area was gridded into areas not greater than 250' by 250' similar to a Group 1 certification unit. With this gridding process, six areas were defined (see Figure 2). Each of the defined areas has been sub-divided into 16 approximately equal sub-areas. Sample locations within each of the defined areas have been generated by randomly selecting an easting and northing coordinate within the boundaries of each sub-area, then each location was tested against the minimum distance criteria for each defined area to ensure that all 16 random locations have sufficient spacing. One sample location in each of the defined areas has been designated with a "D", indicating a field duplicate sample collection location. Additionally, four archive sample locations have been identified in each of the six defined areas. All samples within each defined area will be collected for analysis from 0 to 6 inches with the exception of the archive sample locations. However, all of the sampling locations including the archives will be surveyed. The planned precertification sampling locations are shown on Figure 3.

The area specific constituents of concern (ASCOCs) for this entire precertification effort will be the primary radionuclides (total uranium, radium-226, radium-228, thorium-228, and thorium-232) TAL F, arsenic (TAL H), and beryllium (TAL G). These sampling and analytical requirements and the TALs are listed on Attachment 1. The sample locations and identifiers are listed in Attachment 2. The sample identifier description is in Attachment 3.

If "push tubes" are used for sample collection, two container blanks will be collected – one before sample collection begins and one at the conclusion of sample collection. The container blank samples will be analyzed for TALs F, G, and H. If an alternate sample collection method is used, one rinsate will be collected at a minimum frequency of one per 20 pieces of equipment reused in the field.

Analyses will be conducted to Analytical Support Level (ASL) D or E, where all requirements for ASL E are the same as ASL D except the minimum detection level for the selected analytical method must be at least 10 percent of the FRL. A minimum of 10 percent of the laboratory data will be validated to Validation Support Level (VSL) D with the remainder validated to VSL B.

Historical data will be used for shipment of the samples collected under this V/FCN. The highest total uranium result from this area is 76.2 mg/kg at location A5A-10.

Justification:

The 60-inch main drainage line that passes under the western section of Area 5 Administration Area is being excavated. Precertification samples are necessary to determine where the excavated overburden can be temporarily stockpiled and if it can be used as backfill once the 60-inch line has been removed. Precertification samples are necessary in the remainder of the Area 5 Administration Area before the overburden is stockpiled in the area.

REQUESTED BY: Greg Lupton

Date: 1/11/06

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE: <i>[Signature]</i>	1/12/06	X	PROJECT MANAGER: J.D. Chou <i>[Signature]</i>	1/11/06
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: Frank Miller <i>[Signature]</i>	1/11/06
X	ANALYTICAL CUSTOMER SUPPORT: <i>Paul S. McSwigan</i>	1/12/06		RTIMP Manager	
X	WAO <i>[Signature]</i>		X	SAMPLING MANAGER: <i>[Signature]</i>	1/12/06

VARIANCE/FCN APPROVED YES NO

REVISION REQUIRED: YES NO

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

20F9

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

Analyte ^a	Method ^a	Matrix	Preserve	Hold Time	TAT	Container ^b	Minimum Mass/Volume
Rads/Metals (TAL F, G, and H)	Gamma Spec	Solid	Cool, 4° C	12 months	Prelim 10 days Final 30 days	Glass with Teflon-lined lid	500 g (1500 g) ^c
	ICP or ICP/MS			6 months	10 days		
Radiological (TAL F)	Gamma Spec	Liquid (rinsate ^d)	HNO ₃ pH<2	6 months	30 days	Polyethylene	4 liters
Metals (TAL G, H)	ICP or ICP/MS	Liquid (rinsate ^d)	HNO ₃ pH<2	6 months	10 days	Polyethylene	500 ml

^a Samples will be analyzed according to Analytical Support Level (ASL) D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^c At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in the CU in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

^d If "push tubes" are used for sampling, the off-site laboratories will be sent container blanks. If an alternative sample method is used, a rinsate will be collected by the Field Technicians.

**TAL F
(Radiological - ASL D/E*)**

Analyte	On-Property FRL	MDL
Total Uranium	82 mg/kg	8.2 mg/kg
Radium-226	1.7 pCi/g	0.17 pCi/g
Radium-228	1.8 pCi/g	0.18 pCi/g
Thorium-228	1.7 pCi/g	0.17 pCi/g
Thorium-232	1.5 pCi/g	0.15 pCi/g

**TAL G
(Metals - ASL D/E*)**

Analyte	On-Property FRL/(BTV)	MDL (soil)
Beryllium	1.5 mg/kg	0.15 mg/kg

**TAL H
(Metals - ASL D/E*)**

Analyte	On-Property FRL	MDL
Arsenic	12 mg/kg	1.2 mg/kg

*Analytical requirements will meet ASL D but the MDL may cause some analyses to be considered ASL E.

MDL – minimum detection level

pCi/g – picoCuries per gram

**ATTACHMENT 3
AREA 5 ADMINISTRATION SAMPLE LOCATIONS AND IDENTIFIERS**

Each soil precertification sample will be assigned a unique sample identification number where:

- A5A = Sample collected from Area 5 Administration
- PC = Precertification
- # = Specific area from which sample was collected
- Location = Sample location number within the specific area
- ^ = The ^ is placed between the location number for the specific area and the analysis type identifier. When used, the information to the left of this symbol identifies the location number and allows the automatic assignment of the location identification number to be transferred to the appropriate field/table in the Sitewide Environmental Database.
- Analysis = "R" indicates radiological analysis; "M" indicates metals
- QC = Quality control sample. A "D" indicates a field-duplicated sample; "Y" indicates a container blank sample; "X" indicates a rinsate

ATTACHMENT 2
AREA 5 ADMINISTRATION AREA SAMPLE LOCATIONS AND IDENTIFIERS

CU	Location	Depth	Sample ID	TAL	North-83	East-83
1	1-1	0"-6"	A5A-PC01-1^RM	FGH	479920.74	1349196.94
	1-2V	0"-6"	A5A-PC01-2^V	Archive	479943.09	1349249.55
	1-3	0"-6"	A5A-PC01-3^RM	FGH	479852.72	1349170.64
	1-4	0"-6"	A5A-PC01-4^RM	FGH	479859.67	1349260.97
	1-5	0"-6"	A5A-PC01-5^RM	FGH	479941.1	1349312.59
	1-6V	0"-6"	A5A-PC01-6^V	Archive	479906.84	1349357.75
	1-7	0"-6"	A5A-PC01-7^RM	FGH	479872.08	1349311.1
	1-8D	0"-6"	A5A-PC01-8^RM	FGH	479836.83	1349352.3
			A5A-PC01-8^RM-D			
	1-9	0"-6"	A5A-PC01-9^RM	FGH	479777.99	1349160.21
	1-10	0"-6"	A5A-PC01-10^RM	FGH	479789.41	1349243.1
	1-11V	0"-6"	A5A-PC01-11^V	Archive	479711.95	1349178.58
	1-12	0"-6"	A5A-PC01-12^RM	FGH	479728.33	1349245.58
	1-13	0"-6"	A5A-PC01-13^RM	FGH	479771.53	1349302.17
	1-14V	0"-6"	A5A-PC01-14^V	Archive	479800.33	1349365.7
	1-15	0"-6"	A5A-PC01-15^RM	FGH	479704.5	1349317.55
1-16	0"-6"	A5A-PC01-16^RM	FGH	479736.77	1349369.67	
2	2-1	0"-6"	A5A-PC02-1^RM	FGH	479914.78	1349405.15
	2-2	0"-6"	A5A-PC02-2^RM	FGH	479950.04	1349480.6
	2-3	0"-6"	A5A-PC02-3^RM	FGH	479840.8	1349405.15
	2-4V	0"-6"	A5A-PC02-4^V	Archive	479872.08	1349492.51
	2-5D	0"-6"	A5A-PC02-5^RM	FGH	479916.27	1349534.2
			A5A-PC02-5^RM-D			
	2-6	0"-6"	A5A-PC02-6^RM	FGH	479905.85	1349607.16
	2-7	0"-6"	A5A-PC02-7^RM	FGH	479835.34	1349528.24
	2-8V	0"-6"	A5A-PC02-8^V	Archive	479863.14	1349593.26
	2-9	0"-6"	A5A-PC02-9^RM	FGH	479776	1349416.07
	2-10	0"-6"	A5A-PC02-10^RM	FGH	479790.4	1349469.18
	2-11V	0"-6"	A5A-PC02-11^V	Archive	479720.88	1349428.98
	2-12	0"-6"	A5A-PC02-12^RM	FGH	479710.46	1349489.03
	2-13	0"-6"	A5A-PC02-13^RM	FGH	479772.52	1349520.8
	2-14	0"-6"	A5A-PC02-14^RM	FGH	479803.81	1349608.53
	2-15V	0"-6"	A5A-PC02-15^V	Archive	479735.28	1349537.55
2-16	0"-6"	A5A-PC02-16^RM	FGH	479705.99	1349608.03	

ATTACHMENT 2
AREA 5 ADMINISTRATION AREA SAMPLE LOCATIONS AND IDENTIFIERS

CU	Location	Depth	Sample ID	TAL	North-83	East-83
3	3-1D	0"-6"	A5A-PC03-1^RM	FGH	479928.49	1349626.41
			A5A-PC03-1^RM-D			
	3-2	0"-6"	A5A-PC03-2^RM	FGH	479919.1	1349726.22
	3-3	0"-6"	A5A-PC03-3^RM	FGH	479938.17	1349775.59
	3-4V	0"-6"	A5A-PC03-4^V	Archive	479880.58	1349769.21
	3-5	0"-6"	A5A-PC03-5^RM	FGH	479866.74	1349654.59
	3-6	0"-6"	A5A-PC03-6^RM	FGH	479857.96	1349721.57
	3-7V	0"-6"	A5A-PC03-7^V	Archive	479764.92	1349636.15
	3-8	0"-6"	A5A-PC03-8^RM	FGH	479779.42	1349691.19
	3-9	0"-6"	A5A-PC03-9^RM	FGH	479806.68	1349752.93
	3-10	0"-6"	A5A-PC03-10^RM	FGH	479782.6	1349810.04
	3-11	0"-6"	A5A-PC03-11^RM	FGH	479810.92	1349874.22
	3-12V	0"-6"	A5A-PC03-12^V	Archive	479737.89	1349856.46
	3-13	0"-6"	A5A-PC03-13^RM	FGH	479722.3	1349649.48
	3-14	0"-6"	A5A-PC03-14^RM	FGH	479712.24	1349714.83
	3-15V	0"-6"	A5A-PC03-15^V	Archive	479740.59	1349765.9
3-16	0"-6"	A5A-PC03-16^RM	FGH	479712.57	1349820.16	
4	4-1	0"-6"	A5A-PC04-1^RM	FGH	479649.63	1349159.1
	4-2V	0"-6"	A5A-PC04-2^V	Archive	479666.01	1349232.06
	4-3D	0"-6"	A5A-PC04-3^RM	FGH	479583.59	1349181.93
			A5A-PC04-3^RM-D			
	4-4	0"-6"	A5A-PC04-4^RM	FGH	479573.16	1349243.47
	4-5	0"-6"	A5A-PC04-5^RM	FGH	479659.56	1349314.45
	4-6	0"-6"	A5A-PC04-6^RM	FGH	479680.41	1349376.99
	4-7V	0"-6"	A5A-PC04-7^V	Archive	479618.35	1349300.06
	4-8	0"-6"	A5A-PC04-8^RM	FGH	479577.63	1349348.7
	4-9	0"-6"	A5A-PC04-9^RM	FGH	479538.9	1349159.1
	4-10	0"-6"	A5A-PC04-10^RM	FGH	479526.49	1349261.84
	4-11V	0"-6"	A5A-PC04-11^V	Archive	479483.91	1349191.86
	4-12	0"-6"	A5A-PC04-12^RM	FGH	479445.67	1349251.42
	4-13	0"-6"	A5A-PC04-13^RM	FGH	479512.71	1349320.41
	4-14V	0"-6"	A5A-PC04-14^V	Archive	479550.44	1349375.5
	4-15	0"-6"	A5A-PC04-15^RM	FGH	479466.03	1349307
4-16	0"-6"	A5A-PC04-16^RM	FGH	479392.67	1349302.54	


ATTACHMENT 2
AREA 5 ADMINISTRATION AREA SAMPLE LOCATIONS AND IDENTIFIERS

CU	Location	Depth	Sample ID	TAL	North-83	East-83
5	5-1	0"-6"	A5A-PC05-1^RM	FGH	479666.5	1349421.54
	5-2	0"-6"	A5A-PC05-2^RM	FGH	479656.24	1349467.54
	5-3V	0"-6"	A5A-PC05-3^V	Archive	479574.01	1349393.09
	5-4	0"-6"	A5A-PC05-4^RM	FGH	479571.6	1349447.76
	5-5	0"-6"	A5A-PC05-5^RM	FGH	479636.18	1349507.4
	5-6V	0"-6"	A5A-PC05-6^V	Archive	479664.37	1349547.83
	5-7	0"-6"	A5A-PC05-7^RM	FGH	479550.66	1349485.5
	5-8	0"-6"	A5A-PC05-8^RM	FGH	479545.23	1349541.16
	5-9	0"-6"	A5A-PC05-9^RM	FGH	479663.23	1349602.27
	5-10V	0"-6"	A5A-PC05-10^V	Archive	479645.78	1349652.47
	5-11D	0"-6"	A5A-PC05-11^RM	FGH	479562.82	1349601.06
			A5A-PC05-11^RM-D			
	5-12	0"-6"	A5A-PC05-12^RM	FGH	479589.42	1349643.94
	5-13	0"-6"	A5A-PC05-13^RM	FGH	479513.99	1349428.45
	5-14	0"-6"	A5A-PC05-14^RM	FGH	479508.9	1349527.29
	5-15	0"-6"	A5A-PC05-15^RM	FGH	479492.88	1349598.81
5-16V	0"-6"	A5A-PC05-16^V	Archive	479507.45	1349658.34	
6	6-1	0"-6"	A5A-PC06-1^RM	FGH	479666.33	1349677.04
	6-2V	0"-6"	A5A-PC06-2^V	Archive	479666.87	1349754.58
	6-3	0"-6"	A5A-PC06-3^RM	FGH	479625.05	1349708.01
	6-4	0"-6"	A5A-PC06-4^RM	FGH	479585.32	1349745.44
	6-5	0"-6"	A5A-PC06-5^RM	FGH	479662.11	1349817.21
	6-6	0"-6"	A5A-PC06-6^RM	FGH	479670.01	1349883.15
	6-7	0"-6"	A5A-PC06-7^RM	FGH	479581.3	1349820.41
	6-8V	0"-6"	A5A-PC06-8^V	Archive	479613.12	1349863.45
	6-9	0"-6"	A5A-PC06-9^RM	FGH	479528.13	1349674.08
	6-10	0"-6"	A5A-PC06-10^RM	FGH	479540.45	1349758.72
	6-11	0"-6"	A5A-PC06-11^RM	FGH	479492.69	1349697.28
	6-12V	0"-6"	A5A-PC06-12^V	Archive	479476.18	1349758.17
	6-13V	0"-6"	A5A-PC06-13^V	Archive	479543.71	1349808.72
	6-14	0"-6"	A5A-PC06-14^RM	FGH	479519.95	1349865.78
	6-15D	0"-6"	A5A-PC06-15^RM	FGH	479465.45	1349818.4
			A5A-PC06-15^RM-D			
6-16	0"-6"	A5A-PC06-16^RM	FGH	479485.45	1349865.03	

V:\22\m12\edg\m25_admin\1_002.dgn

STATE PLANNING COORDINATE SYSTEM 1983

11-JAN-2006




LEGEND:



PRECERTIFICATION AREA


SCALE



DRAFT

FIGURE 1. AREA 5 ADMINISTRATION AREA


70F9



V = ARCHIVE SAMPLE
 D = DUPLICATE SAMPLE

LEGEND:


• SAMPLE LOCATION



DRAFT

FIGURE 3. AREA 5 ADMINISTRATION AREA PRECERTIFICATION SAMPLE LOCATIONS

8 of 9




DRAFT

v:\2\fm\2\dgn\ca5_admin_003.dgn
STATE PLANAR COORDINATE SYSTEM 1983

FIGURE 2. PRECERTIFICATION AREA 5 ADMINISTRATION SUB AREAS

9 of 9



12-JAN-2006

006314



State of Ohio Environmental Protection Agency

Southwest District

401 East Fifth Street
Dayton, Ohio 45402-2911

TELE: (937)285-6357 FAX: (937)285-6249
www.epa.state.oh.us

Bob Taft, Governor
Bruce Johnson, Lt. Governor
Joseph P. Koncelik, Director

MEMO

TO: J.D. Chiou, Fluor Fernald

FROM: Donna Bohannon, Ohio EPA/OFFO

DATE: January 13, 2006

SUBJECT: *V/FCN 20810-PSP-0006-151 Project Specific Plan For Excavation Control of Areas 3B, 4B, And 5*

This V/FCN documents the soil sampling to be performed for precertification of Area 5 Administration Area after concrete, gravel and utilities have been removed. The precertification samples are to determine where excavated overburden soil is to be temporarily stockpiled, once the 60-in main drainage line, located under the western section of the Administration Area, is excavated. Ohio EPA approves of this precertification sampling.

Q:\ou5\3B4BA5\3B4B5(5)ExcCtrl.VFCN4.wpd

VARIANCE / FIELD CHANGE NOTICE

Significant?
(Yes or No) **YES**

V/F: 20810-PSP-0006-165

WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1

Page: 1 of 6

PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5

Date: 7/21/06

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples for Precertification of the Area 5 Administration Area Haul Road (see Figure 1).

To ensure ample coverage for precertification, this area was gridded into areas not greater than 250' by 250' similar to a Group 1 certification unit. With this gridding process, one area was defined. The defined area has been sub-divided into 16 approximately equal sub-areas. Sample locations within each of the defined areas have been generated by randomly selecting an easting and northing coordinate within the boundaries of each sub-area, then each location was tested against the minimum distance criteria for each defined area to ensure that all 16 random locations have sufficient spacing. One sample location in each of the defined areas has been designated with a "D", indicating a field duplicate sample collection location. Additionally, four archive sample locations have been identified in each of the six defined areas. All samples within each defined area will be collected for analysis from 0 to 6 inches with the exception of the archive sample locations. However, all of the sampling locations including the archives will be surveyed. The planned precertification sampling locations are shown on Figure 2.

The Sampling and Analytical Requirements are provided on Attachment 1. The Target Analyte Lists are in Attachment 2. The sample locations and identifiers are listed in Attachment 3.

Sampling will be completed using the Geoprobe® Model 5400 and Model 6600 per EQT-06, or an alternate method identified in SMPL-01, as long as sufficient volume is collected to perform the prescribed analyses. Ultimately, the method of sample collection will be left to the discretion of the Field Sampling Lead. One rinsate will be collected for TALs P and Q at a minimum frequency of one per 20 pieces of equipment reused in the field.

Analyses will be conducted to Analytical Support Level (ASL) D or E, where all requirements for ASL E are the same as ASL D except the minimum detection level for the selected analytical method must be at least 10 percent of the FRL. A minimum of 10 percent of the laboratory data will be validated to Validation Support Level (VSL) D with the remainder validated to VSL B.

Historical data will be used for shipment of the samples collected under this V/FCN. The highest total uranium result from this area is 76.2 mg/kg at location A5A-10.

Justification:

The soils in the Area 5 Administration and West Parking Lot areas have been precertified. Following precertification of these areas, a haul road was created with clean material on top of the precertified soil. Precertification samples in conjunction with real-time scans are necessary to confirm that the road can pass certification or determine whether any sections of the road require excavation.

REQUESTED BY: Greg Lupton

Date: 7/21/06

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE: R. Friske <i>R. Friske</i>	7/21/06	X	PROJECT MANAGER: J.D. Chiou <i>J.D. Chiou</i>	7/21/06
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: R. Abitz <i>Greg Lupton FOR R. Abitz</i>	7/21/06
X	ANALYTICAL CUSTOMER SUPPORT: WAO <i>Greg Lupton</i>	7/21/06	X	SAMPLING MANAGER: T. Dabrlage <i>T. Dabrlage</i>	7/31/06
VARIANCE/FCN APPROVED [X]YES []NO			REVISION REQUIRED: []YES [x]NO		

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

TAL(s)	Method ^a	Matrix	Preserve	Hold Time	TAT	Container ^c	Minimum Mass/Volume
Rads/Metals/ PCBs/SVOCs (TALs P, Q, R)	Gamma Spec, Alpha Spec, and LSC or GPC ----- ICP or ICP/MS and IC ----- GC ----- GC	Solid	Cool, 4° C	12 months	EDD 10 days	Glass with Teflon- lined lid	500 g (1500 g) ^d
					Final 14 days 10 days		
				6 months	10 days		
					14 days		
14 days	10 days						
	14 days	10 days					
VOCs (TAL S)	GC/MS	Solid	Cool, 4° C	48 hours	10 days	3 x 1-Encore Sampler ^d plus 1 x 2-oz jar for % moisture	Each full Encore Sampler ^d will hold approx. 5 g
Rads (TALs P)	Gamma Spec, Alpha Spec, and LSC	Liquid (rinsate)	HNO ₃ pH<2	6 months	14 days	Polyethylene	4 liters
Metals (TAL Q)	ICP or ICP/MS and ISE	Liquid (rinsate)	HNO ₃ pH<2	6 months	10 days	Polyethylene	500 ml
VOCs (TAL S)	GC/MS	Liquid (trip blank only)	H ₂ SO ₄ pH<2 Cool, 4o C	14 days	10 days	3 x 40-ml glass with teflon-lined septa	120 ml (no headspace)

^a Samples will be analyzed according to ASL D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b One sample per CU will be selected for analysis utilizing a 21-day in-growth with a 30-day TAT for Ra-226 only. Samples with a 7-day in-growth will be denoted by a "7DAY" suffix while the sample chosen as a 21-day in-growth will be denoted by a "21DAY" suffix attached to the laboratory data.

^c Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^d At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in the CU in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

ATTACHMENT 2
TARGET ANALYTE LISTS

V/FCN 20810-PSP-0006-165

Page 3 of 6

TAL 20810-PSP-0006-P - 13 Samples

Analyte	On-Property FRL	MDL (soil)	MDL (water)
Total Uranium	82 mg/kg	8.2 mg/kg	650 µg/L
Radium-226	1.7 pCi/g	0.17 pCi/g	30 pCi/L
Radium-228	1.8 pCi/g	0.18 pCi/g	30 pCi/L
Thorium-228	1.7 pCi/g	0.17 pCi/g	30 pCi/L
Thorium-232	1.5 pCi/g	0.15 pCi/g	30 pCi/L
Cesium-137	1.4 pCi/g	0.14 pCi/g	15 pCi/L
Lead-210	38 pCi/g	3.8 pCi/g	700 pCi/L
Technetium-99	30.0 pCi/g (29.1 pCi/g)	2.91 pCi/g ^a	10 pCi/L
Thorium-230	280 pCi/g	28 pCi/g	1 pCi/L

TAL 20810-PSP-0006-Q - 13 Samples

Analyte	On-Property FRL	MDL (soil)	MDL (water)
Arsenic	12 mg/kg	1.2 mg/kg	1.8 mg/L
Beryllium	1.5 mg/kg	0.15 mg/kg	0.22 mg/L
Chromium	300 mg/kg	30 mg/kg	45 mg/L
Fluoride	78,000 mg/kg	7800 mg/kg	11,700 mg/L

TAL 20810-PSP-0006-R - 13 Samples

Analyte	On-Property FRL	MDL (soil)
Aroclor-1254	0.13 mg/kg	0.013 mg/kg
Aroclor-1260	0.13 mg/kg	0.013 mg/kg
Dieldrin	0.015 mg/kg	0.0015 mg/kg
Benzo(a)pyrene	2.0 mg/kg	0.2 mg/kg
Benzo(b)fluoranthene	20 mg/kg	2.0 mg/kg
Dibenzo(a,h)anthracene	2.0 mg/kg	0.2 mg/kg
Indeno(1,2,3-cd)pyrene	20 mg/kg	2.0 mg/kg

TAL 20810-PSP-0006-S - 13 Samples

Analyte	On-Property FRL	MDL (soil)	MDL (water)
1,1-Dichloroethene	0.41 mg/kg	0.041 mg/kg	10 µg/L
1,2-Dichloroethene	0.16 mg/kg	0.016 mg/kg	10 µg/L
1,1,1-Trichloroethane	4.3 mg/kg ^b	0.43 mg/kg	10 µg/L
Bromodichloromethane	4.0 mg/kg	0.4 mg/kg	10 µg/L
Tetrachloroethene	3.6 mg/kg	0.36 mg/kg	10 µg/L
Trichloroethene	25 mg/kg	2.5 mg/kg	10 µg/L

^aThe MDL for technetium-99 is 10 percent of the WAC limit, which is lower than the FRL.

^bThe FRL is actually for 1,1,2-trichloroethane because 1,1,1-trichloroethane does not have a FRL. This value will be used for statistical comparison for certification criteria.

ATTACHMENT 3


AREA 5 ADMINISTRATION AREA HAUL ROAD SAMPLE LOCATIONS AND IDENTIFIERS

CU	Location	Depth	Sample ID	TAL	North-83	East-83
8	8-1	0"-6"	A5A-PC08-1^RMPS	PQR	479412.62	1349254.70
			A5A-PC08-1^L	S		
	8-2	0"-6"	A5A-PC08-2^RMPS	PQR	479429.00	1349348.04
			A5A-PC08-2^L	S		
	8-3V	0"-6"	A5A-PC08-3^V	Archive	479413.15	1349392.42
	8-4	0"-6"	A5A-PC08-4^RMPS	PQR	479401.17	1349445.43
			A5A-PC08-4^L	S		
	8-5	0"-6"	A5A-PC08-5^RMPS	PQR	479428.65	1349507.07
			A5A-PC08-5^L	S		
	8-6V	0"-6"	A5A-PC08-6^V	Archive	479401.87	1349631.58
	8-7	0"-6"	A5A-PC08-7^RMPS	PQR	479415.97	1349669.97
			A5A-PC08-7^L	S		
	8-8	0"-6"	A5A-PC08-8^RMPS	PQR	479400.81	1349761.38
			A5A-PC08-8^L	S		
	8-9D	0"-6"	A5A-PC08-9^RMPS	PQR	479411.03	1349810.69
			A5A-PC08-9^L	S		
			A5A-PC08-9^RMPS-D	PQR		
			A5A-PC08-9^L-D	S		
	8-10V	0"-6"	A5A-PC08-10^V	Archive	479451.20	1349807.17
	8-11	0"-6"	A5A-PC08-11^RMPS	PQR	479501.59	1349851.90
			A5A-PC08-11^L	S		
	8-12	0"-6"	A5A-PC08-12^RMPS	PQR	479566.53	1349824.78
			A5A-PC08-12^L	S		
	8-13	0"-6"	A5A-PC08-13^RMPS	PQR	479635.59	1349831.82
			A5A-PC08-13^L	S		
	8-14V	0"-6"	A5A-PC08-14^V	Archive	479670.48	1349858.95
	8-15	0"-6"	A5A-PC08-15^RMPS	PQR	479739.37	1349851.55
			A5A-PC08-15^L	S		
	8-16	0"-6"	A5A-PC08-16^RMPS	PQR	479790.82	1349864.58
			A5A-PC08-16^L	S		

v:\22\fm\2\edg\mcds\mou1_001.dgn

STATE PLANNING COORDINATE SYSTEM 1983

20-JUL-2006



LEGEND:



HAUL ROAD
 PRECERTIFICATION
 AREA

SCALE




500 250 0 500 FEET

DRAFT

FIGURE 1. AREA 5 ADMINISTRATION AREA HAUL ROAD


V = ARCHIVE SAMPLE
D = DUPLICATE SAMPLE



STATE PLANAR COORDINATE SYSTEM 1983
v:\2\mt2\dgn\5_haul_101.dgn

LEGEND:

● SAMPLE LOCATION



DRAFT

FIGURE 2. AREA 5 ADMINISTRATION AREA HAUL ROAD PRECERTIFICATION SAMPLE LOCATIONS

20-JUL-2006



State of Ohio Environmental Protection Agency

Southwest District

401 East Fifth Street
Columbus, Ohio 45402-2911TELE: (937)285-6357 FAX: (937)285-6249
www.epa.state.oh.usBob Taft, Governor
Bruce Johnson, Lt. Governor
Joseph P. Koncelik, Director**MEMO**

TO: J.D. Chiou, Fluor Fernald

FROM: Donna Bohannon, Ohio EPA/OFFO

DATE: July 26, 2006

SUBJECT: *V/FCN 20810-PSP-0006-165 Project Specific Plan For Excavation Control of Areas 3B, 4B, And 5*

This V/FCN documents the collection of 16 soil samples from Area 5 Administration Area Haul Road for precertification. The area is equalvalent in size to a Group 1 Certification Unit and has been divided into 16 sub areas. The existing soils in Area 5 and the West Parking Lot were previously precertified and due to the creation of a Haul Road in this area, the precertification samples will help determine whether the road will pass certification. In addition, the status of Area 5 and the Haul Road will be clarified in the Certification Design Letter and Project Specific Plan. Ohio EPA approves of this variance.

Q:\ou5\3B4BA5\3B4B5(5)ExcvcCtrl.VFCN4approval.wpd

VARIANCE / FIELD CHANGE NOTICE

Significant?
(Yes or No) **YES**

V/F: 20810-PSP-0006-168

WBS NO.: PROJECT/DOCUMENT/ECDC # 20810-PSP-0006 Rev.1

Page: 1 of 9

PROJECT TITLE: Project Specific Plan For Excavation Control Of Areas 3B, 4B, And 5

Date: 8/21/06

VARIANCE / FIELD CHANGE NOTICE (Include justification):

This Variance/Field Change Notice (V/FCN) documents the collection of physical soil samples from the footprint of the 60-inch storm sewer line excavation (see Figure 1). Samples are being collected to complete the Precertification of the Area 5 Administration Area and West Parking Lot.

To ensure ample coverage for precertification, this area was gridded into areas not greater than 250' by 250' similar to a Group 1 certification unit. With this gridding process, two areas were defined (see Figure 2). Each of the defined areas has been sub-divided into 16 approximately equal sub-areas. Sample locations within each of the defined areas have been generated by randomly selecting an easting and northing coordinate within the boundaries of each sub-area, then each location was tested against the minimum distance criteria for each defined area to ensure that all 16 random locations have sufficient spacing. One sample location in each of the defined areas has been designated with a "D", indicating a field duplicate sample collection location. Additionally, four archive sample locations have been identified in each of the two defined areas. All samples within each defined area will be collected for analysis from 0 to 6 inches with the exception of the archive sample locations. The planned precertification sampling locations are shown on Figure 3.

The area specific constituents of concern (ASCOCs) for this precertification effort are the same as those collected during the certification of the 60-inch excavated footprint in the Area Main Drainage Corridor and Former Production Area, which is certified. The sampling and analytical requirements and the TALs are listed on Attachment 1. The sample locations and identifiers are listed in Attachment 2. The sample identifier description is in Attachment 3.

Analyses will be conducted to Analytical Support Level (ASL) D or E, where all requirements for ASL E are the same as ASL D except the minimum detection level for the selected analytical method must be at least 10 percent of the FRL. A minimum of 10 percent of the laboratory data will be validated to Validation Support Level (VSL) D with the remainder validated to VSL B.

Justification:

The 60-inch main drainage line and the 18-inch storm drainage line that passed under the western section of Area 5 Administration Area and the West Parking Lot was excavated and removed. Precertification samples are necessary to determine if the soil can pass certification.

REQUESTED BY: Greg Lupton

Date: 8/21/06

X IF REQD	VARIANCE/FCN APPROVAL	DATE	X IF REQD	VARIANCE/FCN APPROVAL	DATE
X	QUALITY ASSURANCE: <i>[Signature]</i>	8-22-06	X	PROJECT MANAGER: J.D. Chiu <i>[Signature]</i>	9/15/06
	DATA QUALITY MANAGEMENT		X	CHARACTERIZATION MANAGER: F. Miller <i>[Signature]</i>	22/06
X	ANALYTICAL CUSTOMER SUPPORT: <i>[Signature]</i>	9/15/06		RAMP Manager	
* 9/2	WAO 9/15/06		X	SAMPLING MANAGER: <i>[Signature]</i>	9/14/06
VARIANCE/FCN APPROVED [X] YES [] NO			REVISION REQUIRED: [] YES [x] NO		

DISTRIBUTION

PROJECT MANAGER:	DOCUMENT CONTROL: Jeannie Rosser	OTHER:
QUALITY ASSURANCE:	CHARACTERIZATION MANAGER: Frank Miller	OTHER:
FIELD MANAGER:	OTHER:	OTHER:

**ATTACHMENT 1
SAMPLING AND ANALYTICAL REQUIREMENTS**

TAL(s)	Method ^a	Matrix	Preserve	Hold Time	TAT	Container ^c	Minimum Mass/Volume
Rads/Metals/ PCBs/SVOCs (TALs A3/T/A2)	Gamma Spec and LSC or GPC	Solid	Cool, 4° C	12 months	EDD 10 days	Glass with Teflon- lined lid	500 g (1500 g) ^d
					Final 14 days ^b		
	10 days						
	6 months			10 days			
	14 days			10 days			
ICP or ICP/MS and IC	14 days	10 days					
GC							
GC							
VOCs (TAL Z)	GC/MS	Solid	Cool, 4° C	48 hours	10 days	3 x 1-Encore Sampler ^d plus 1 x 2-oz jar for % moisture	Each full Encore Sampler ^d will hold approx. 5 g
Metals ^e (TAL T)	ICP or ICP/MS and ISE	Liquid ^e	HNO ₃ pH<2	6 months	10 days	Polyethylene	500 ml
VOCs (TAL Z)	GC/MS	Liquid (trip blank only)	H ₂ SO ₄ pH<2 Cool, 4° C	14 days	10 days	3 x 40-ml glass with teflon-lined septa	120 ml (no headspace)

^a Samples will be analyzed according to ASL D requirements but the minimum detection level may cause some analyses to be considered ASL E.

^b One sample per CU will be selected for analysis utilizing a 21-day in-growth with a 30-day TAT for Ra-226 only. Samples with a 7-day in-growth will be denoted by a "7DAY" suffix while the sample chosen as a 21-day in-growth will be denoted by a "21DAY" suffix attached to the laboratory data.

^c Sample container types may be changed at the direction of the Field Sampling Lead, as long as the volume requirements, container compatibility requirements, and SCQ requirements are met.

^d At the direction of the Field Sampling Lead, triple the specified volume must be collected for all samples at one location in the CU in order for the contract laboratory to perform the required quality control analysis. The samples shall be identified on the Chain of Custody/Request for Analysis forms as "designated for laboratory QC".

^e The container blank and/or rinsate samples will be analyzed for TAL T only.

The highest total uranium result from this area is 76.2 mg/kg at location A5A-10.

**ATTACHMENT 2
TARGET ANALYTE LISTS**

V/FCN 20810-PSP-0006-168

Page 3 of 9

TAL 20810-PSP-0006-A3 - 26 Samples

Analyte	On-Property FRL/WAC	MDL (soil)
Total Uranium	20 mg/kg	2.0 mg/kg
Radium-226	1.7 pCi/g	0.3 pCi/g
Radium-228	1.8 pCi/g	0.3 pCi/g
Thorium-228	1.7 pCi/g	0.3 pCi/g
Thorium-232	1.5 pCi/g	0.3 pCi/g
Cesium-137	1.4 pCi/g	0.2 pCi/g
Technetium-99	30.0 pCi/g (29.1 pCi/g)	2.91 pCi/g

TAL 20810-PSP-0006-T - 26 Samples

Analyte	On-Property FRL/(BTV)	MDL (soil)	MDL (water)
Antimony	96 mg/kg /(10 mg/kg)	1.0 mg/kg	1.5 mg/L
Arsenic	12 mg/kg	1.2 mg/kg	1.8 mg/L
Barium	68,000 mg/kg /(500 mg/kg)	50 mg/kg	10,200 mg/L
Beryllium	1.5 mg/kg	0.15 mg/kg	0.22 mg/L
Cadmium	82 mg/kg /(5.0 mg/kg)	0.5 mg/kg	0.75 mg/L
Chromium	300 mg/kg	30 mg/kg	45 mg/L
Lead	400 mg/kg /(200 mg/kg)	20 mg/kg	30 mg/L
Mercury	7.5 mg/kg /(5 mg/kg)	0.5 mg/kg	0.75 mg/L
Molybdenum	2900 mg/kg /(10 mg/kg)	1.0 mg/kg	1.5 mg/L
Selenium	5400 mg/kg	540 mg/kg	810 mg/L
Silver	29,000 /(10 mg/kg)	1.0 mg/kg	1.5 mg/L

TAL 20810-PSP-0006-Z - 26 Samples

Analyte	On-Property FRL	MDL (soil)	MDL (water)
1,1-dichloroethene	0.16 mg/kg	0.016 mg/kg	10 µg/L
1,2-dichloroethane	0.015 mg/kg	0.0015 mg/kg	10 µg/L
1,1,1-Trichloroethane ^c	4.3 mg/kg ^c	0.43 mg/kg ^c	10 µg/L
4-Methyl-2-pentanone	2500 mg/kg	250 mg/kg	10 µg/L
Acetone	43,000 mg/kg	4,300 mg/kg	10 µg/L
Benzene	850 mg/kg	85 mg/kg	10 µg/L
Carbon tetrachloride	2.1 mg/kg	0.21 mg/kg	10 µg/L
Ethylbenzene	5,100 mg/kg	510 mg/kg	10 µg/L
Methyl Chloride	37 mg/kg	3.7 mg/kg	10 µg/L
Tetrachloroethene	3.6 mg/kg	0.36 mg/kg	10 µg/L
Toluene	100,000 mg/kg	10,000 mg/kg	10 µg/L
Trichloroethene	25 mg/kg	2.5 mg/kg	10 µg/L
Xylene	920,000 mg/kg	92,000 mg/kg	10 µg/L

**ATTACHMENT 2
TARGET ANALYTE LISTS**

V/FCN 20810-PSP-0006-168

Page 4 of 9

TAL 20810-PSP-0006-A2 - 26 Samples

Analyte	On-Property FRL/(BTV)	MDL (soil)
Aroclor-1254	0.13 mg/kg	0.013 mg/kg
Aroclor-1260	0.13 mg/kg	0.013 mg/kg
Benzo(a)pyrene	2.0 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Benzo(a)anthracene	20 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Benzo(b)fluoranthene	20 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Benzo(g,h,i)perylene	(1.0 mg/kg)	0.1 mg/kg
Benzo(k)fluoranthene	200 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Chrysene	2000 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Dibenzo(a,h)anthracene	2.0 mg/kg /(0.088 mg/kg)	0.0088 mg/kg
Dieldrin	0.015 mg/kg	0.0015 mg/kg
Fluoranthene	(10 mg/kg)	1.0 mg/kg
Indeno(1,2,3-cd)pyrene	20 mg/kg /(1.0 mg/kg)	0.1 mg/kg
Phenanthrene	(5 mg/kg)	0.5 mg/kg
Pyrene	(10 mg/kg)	1.0 mg/kg


ATTACHMENT 3

AREA 5 ADMINISTRATION AREA AND WEST PARKING LOT SAMPLE LOCATIONS AND IDENTIFIERS


CU	Location	Depth	Sample ID	TAL	North-83	East-83
A5A-PC09	9-1	0"-6"	A5A-PC09-1^RMPS	T,A2,A3	479901.96	1349192.37
			A5A-PC09-1^L	Z		
	9-2V	0"-6"	A5A-PC09-2^V	Archive	479936.99	1349272.81
	9-3	0"-6"	A5A-PC09-3^RMPS	T,A2,A3	479843.82	1349157.73
			A5A-PC09-3^L	Z		
	9-4D	0"-6"	A5A-PC09-4^RMPS	T,A2,A3	479870.38	1349257.41
			A5A-PC09-4^L	Z		
			A5A-PC09-4^RMPS-D	T,A2,A4		
			A5A-PC09-4^L-D	Z		
	9-5	0"-6"	A5A-PC09-5^RMPS	T,A2,A3	479795.69	1349183.51
			A5A-PC09-5^L	Z		
	9-6V	0"-6"	A5A-PC09-6^V	Archive	479815.33	1349280.51
	9-7	0"-6"	A5A-PC09-7^RMPS	T,A2,A3	479744.48	1349141.17
			A5A-PC09-7^L	Z		
	9-8	0"-6"	A5A-PC09-8^RMPS	T,A2,A3	479766.04	1349265.49
			A5A-PC09-8^L	Z		
	9-9	0"-6"	A5A-PC09-9^RMPS	T,A2,A3	479698.08	1349168.50
			A5A-PC09-9^L	Z		
	9-10	0"-6"	A5A-PC09-10^RMPS	T,A2,A3	479730.42	1349242.40
			A5A-PC09-10^L	Z		
	9-11V	0"-6"	A5A-PC09-11^V	Archive	479637.25	1349165.04
	9-12	0"-6"	A5A-PC09-12^RMPS	T,A2,A3	479669.97	1349225.47
			A5A-PC09-12^L	Z		
	9-13	0"-6"	A5A-PC09-13^RMPS	T,A2,A3	479608.56	1349231.24
			A5A-PC09-13^L	Z		
	9-14V	0"-6"	A5A-PC09-14^V	Archive	479568.13	1349188.90
	9-15	0"-6"	A5A-PC09-15^RMPS	T,A2,A3	479523.85	1349167.73
			A5A-PC09-15^L	Z		
9-16	0"-6"	A5A-PC09-16^RMPS	T,A2,A3	479494.78	1349227.78	
		A5A-PC09-16^L	Z			

ATTACHMENT 3
AREA 5 ADMINISTRATION AREA AND WEST PARKING LOT SAMPLE LOCATIONS AND IDENTIFIERS

CU	Location	Depth	Sample ID	TAL	North-83	East-83
A5WPL-PC05	5-1	0"-6"	A5WPL-PC05-1^RMPS	T,A2,A3	479379.46	1349145.41
			A5WPL-PC05-1^L	Z		
	5-2	0"-6"	A5WPL-PC05-2^RMPS	T,A2,A3	479356.36	1349201.99
			A5WPL-PC05-2^L	Z		
	5-3	0"-6"	A5WPL-PC05-3^RMPS	T,A2,A3	479282.05	1349141.94
			A5WPL-PC05-3^L	Z		
	5-4V	0"-6"	A5WPL-PC05-4^V	Archive	479224.77	1349200.83
	5-5	0"-6"	A5WPL-PC05-5^RMPS	T,A2,A3	479392.64	1349243.56
			A5WPL-PC05-5^L	Z		
	5-6	0"-6"	A5WPL-PC05-6^RMPS	T,A2,A3	479319.10	1349278.20
			A5WPL-PC05-6^L	Z		
	5-7	0"-6"	A5WPL-PC05-7^RMPS	T,A2,A3	479285.22	1349234.70
			A5WPL-PC05-7^L	Z		
	5-8V	0"-6"	A5WPL-PC05-8^V	Archive	479244.02	1349259.72
	5-9	0"-6"	A5WPL-PC05-9^RMPS	T,A2,A3	479182.22	1349162.34
			A5WPL-PC05-9^L	Z		
	5-10	0"-6"	A5WPL-PC05-10^RMPS	T,A2,A3	479119.85	1349199.29
			A5WPL-PC05-10^L	Z		
	5-11V	0"-6"	A5WPL-PC05-11^V	Archive	479070.75	1349144.64
	5-12D	0"-6"	A5WPL-PC05-12^RMPS	T,A2,A3	479003.76	1349203.91
			A5WPL-PC05-12^L	Z		
			A5WPL-PC05-12^RMPS-D	T,A2,A4		
			A5WPL-PC05-12^L-D	Z		
	5-13	0"-6"	A5WPL-PC05-13^RMPS	T,A2,A3	479158.92	1349233.93
			A5WPL-PC05-13^L	Z		
	5-14	0"-6"	A5WPL-PC05-14^RMPS	T,A2,A3	479150.07	1349277.81
			A5WPL-PC05-14^L	Z		
	5-15V	0"-6"	A5WPL-PC05-15^V	Archive	479054.58	1349243.17
5-16	0"-6"	A5WPL-PC05-16^RMPS	T,A2,A3	479027.63	1349280.51	
		A5WPL-PC05-16^L	Z			



LEGEND:




PREVIOUSLY SAMPLED AREA - ADMIN & WPL




PRECERTIFICATION AREA

SCALE



DRAFT

FIGURE 1. 60-INCH LINE EXCAVATED AREA




V = ARCHIVE SAMPLE
 D = DUPLICATE SAMPLE

LEGEND:

• SAMPLE LOCATION

SCALE




DRAFT

FIGURE 2. PC09 SAMPLE LOCATIONS

v:\eg\fm\2\eg\p05_153.dgn

STATE PLANNING COORDINATE SYSTEM 1983

14-SEP-2006



DRAFT

LEGEND:

• SAMPLE LOCATION




FIGURE 3. PC05 SAMPLE LOCATIONS

APPENDIX C

**AREA 5 ADMINISTRATION AREA, WPL, HAUL ROAD, AND 60-INCH
LINE PRECERTIFICATION DATA**

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Arsenic	4.06	-		mg/kg
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Beryllium	0.454	-		mg/kg
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Radium-226	1.18	J		pCi/g
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Radium-228	0.878	-		pCi/g
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Thorium-228	0.877	-		pCi/g
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Thorium-232	0.878	-		pCi/g
A5A-PC01	A5A-PC01A-1	A5A-PC01A-1^RM	Uranium, Total	11.2	-		mg/kg
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Arsenic	4.71	-		mg/kg
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Beryllium	0.577	-		mg/kg
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Radium-226	1.64	J		pCi/g
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Radium-228	1.28	-		pCi/g
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Thorium-228	1.3	-		pCi/g
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Thorium-232	1.28	-		pCi/g
A5A-PC01	A5A-PC01A-3	A5A-PC01A-3^RM	Uranium, Total	51.9	-		mg/kg
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Arsenic	7.1	-		mg/kg
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Beryllium	0.653	-		mg/kg
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Radium-226	1.29	J		pCi/g
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Radium-228	0.998	-		pCi/g
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Thorium-228	0.993	-		pCi/g
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Thorium-232	0.998	-		pCi/g
A5A-PC01	A5A-PC01A-4	A5A-PC01A-4^RM	Uranium, Total	10	-		mg/kg
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Arsenic	8.43	-		mg/kg
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Beryllium	0.662	-		mg/kg
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Radium-226	1.41	J		pCi/g
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Radium-228	1.1	-		pCi/g
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Thorium-228	1.11	-		pCi/g
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Thorium-232	1.1	-		pCi/g
A5A-PC01	A5A-PC01A-5	A5A-PC01A-5^RM	Uranium, Total	6.22	J		mg/kg
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Arsenic	8.98	-		mg/kg
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Beryllium	0.666	-		mg/kg
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Radium-226	1.29	J		pCi/g
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Radium-228	1.01	-		pCi/g
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Thorium-228	1.06	-		pCi/g
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Thorium-232	1.01	-		pCi/g
A5A-PC01	A5A-PC01A-7	A5A-PC01A-7^RM	Uranium, Total	10.5	-		mg/kg
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Arsenic	7.12	-		mg/kg
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Arsenic	7.07	-		mg/kg
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Beryllium	0.689	-		mg/kg
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Beryllium	0.698	-		mg/kg
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Radium-226	1.23	J		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Radium-226	1.22	J		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Radium-228	0.945	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Radium-228	0.878	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Thorium-228	0.933	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Thorium-228	0.898	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Thorium-232	0.945	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Thorium-232	0.878	-		pCi/g
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM	Uranium, Total	3.95	J		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC01	A5A-PC01A-8	A5A-PC01A-8^RM-D	Uranium, Total	6.19	-		mg/kg
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Arsenic	8.37	-		mg/kg
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Beryllium	0.477	-		mg/kg
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Radium-226	1.28	J		pCi/g
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Radium-228	1.07	-		pCi/g
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Thorium-228	1.09	-		pCi/g
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Thorium-232	1.07	-		pCi/g
A5A-PC01	A5A-PC01A-9	A5A-PC01A-9^RM	Uranium, Total	9.03	-		mg/kg
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Arsenic	8.31	-		mg/kg
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Beryllium	0.683	-		mg/kg
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Radium-226	1.13	J		pCi/g
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Radium-228	0.935	-		pCi/g
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Thorium-228	0.914	-		pCi/g
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Thorium-232	0.935	-		pCi/g
A5A-PC01	A5A-PC01A-10	A5A-PC01A-10^RM	Uranium, Total	4.7	J		mg/kg
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Arsenic	5.63	-		mg/kg
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Beryllium	0.604	-		mg/kg
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Radium-226	1.15	J		pCi/g
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Radium-228	0.901	-		pCi/g
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Thorium-228	0.901	-		pCi/g
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Thorium-232	0.901	-		pCi/g
A5A-PC01	A5A-PC01A-12	A5A-PC01A-12^RM	Uranium, Total	6.6	-		mg/kg
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Arsenic	6.71	-		mg/kg
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Beryllium	0.684	-		mg/kg
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Radium-226	1.27	J		pCi/g
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Radium-228	1.17	-		pCi/g
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Thorium-228	1.22	-		pCi/g
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Thorium-232	1.17	-		pCi/g
A5A-PC01	A5A-PC01A-13	A5A-PC01A-13^RM	Uranium, Total	8.05	-		mg/kg
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Arsenic	6.74	-		mg/kg
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Beryllium	0.694	-		mg/kg
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Radium-226	1.15	J		pCi/g
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Radium-228	0.899	-		pCi/g
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Thorium-228	0.902	-		pCi/g
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Thorium-232	0.899	-		pCi/g
A5A-PC01	A5A-PC01A-15	A5A-PC01A-15^RM	Uranium, Total	6.66	-		mg/kg
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Arsenic	6.84	-		mg/kg
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Beryllium	0.641	-		mg/kg
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Radium-226	1.03	J		pCi/g
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Radium-228	0.806	-		pCi/g
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Thorium-228	0.832	-		pCi/g
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Thorium-232	0.806	-		pCi/g
A5A-PC01	A5A-PC01A-16	A5A-PC01A-16^RM	Uranium, Total	2.85	J		mg/kg
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Arsenic	8.48	J		mg/kg
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Beryllium	0.776	-		mg/kg
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Radium-226	1.08	-		pCi/g
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Radium-228	0.859	J		pCi/g
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Thorium-228	0.844	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Thorium-232	0.859	J		pCi/g
A5A-PC02	A5A-PC02A-1	A5A-PC02A-1^RM	Uranium, Total	8.4	-		mg/kg
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Arsenic	7.74	J		mg/kg
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Beryllium	0.672	-		mg/kg
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Radium-226	1.42	-		pCi/g
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Radium-228	0.984	J		pCi/g
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Thorium-228	0.959	J		pCi/g
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Thorium-232	0.984	J		pCi/g
A5A-PC02	A5A-PC02A-2	A5A-PC02A-2^RM	Uranium, Total	4.9	J		mg/kg
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Arsenic	9.52	J		mg/kg
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Beryllium	0.856	-		mg/kg
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Radium-226	1.68	-		pCi/g
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Radium-228	1.37	J		pCi/g
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Thorium-228	1.39	J		pCi/g
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Thorium-232	1.37	J		pCi/g
A5A-PC02	A5A-PC02A-3	A5A-PC02A-3^RM	Uranium, Total	3.85	U		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Arsenic	7.41	J		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Arsenic	10.2	J		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Beryllium	0.775	-		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Beryllium	0.938	-		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Radium-226	1.39	-		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Radium-226	1.3	-		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Radium-228	1.06	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Radium-228	0.856	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Thorium-228	1.01	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Thorium-228	0.814	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Thorium-232	1.06	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Thorium-232	0.856	J		pCi/g
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM	Uranium, Total	9.89	-		mg/kg
A5A-PC02	A5A-PC02A-5	A5A-PC02A-5^RM-D	Uranium, Total	6.71	-		mg/kg
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Arsenic	6.19	J		mg/kg
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Beryllium	0.531	-		mg/kg
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Radium-226	1.1	-		pCi/g
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Radium-228	0.688	J		pCi/g
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Thorium-228	0.7	J		pCi/g
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Thorium-232	0.688	J		pCi/g
A5A-PC02	A5A-PC02A-6	A5A-PC02A-6^RM	Uranium, Total	14.6	-		mg/kg
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Arsenic	5.62	J		mg/kg
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Beryllium	0.698	-		mg/kg
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Radium-226	1.01	-		pCi/g
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Radium-228	0.687	J		pCi/g
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Thorium-228	0.677	J		pCi/g
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Thorium-232	0.687	J		pCi/g
A5A-PC02	A5A-PC02A-7	A5A-PC02A-7^RM	Uranium, Total	7.92	-		mg/kg
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Arsenic	6.73	J		mg/kg
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Beryllium	0.744	-		mg/kg
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Radium-226	1.5	-		pCi/g
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Radium-228	1.1	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Thorium-228	1.07	J		pCi/g
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Thorium-232	1.1	J		pCi/g
A5A-PC02	A5A-PC02A-9	A5A-PC02A-9^RM	Uranium, Total	6.18	-		mg/kg
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Arsenic	7.96	J		mg/kg
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Beryllium	0.734	-		mg/kg
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Radium-226	1.43	-		pCi/g
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Radium-228	1.04	J		pCi/g
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Thorium-228	1.03	J		pCi/g
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Thorium-232	1.04	J		pCi/g
A5A-PC02	A5A-PC02A-10	A5A-PC02A-10^RM	Uranium, Total	12.5	-		mg/kg
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Arsenic	7.04	J		mg/kg
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Beryllium	0.747	-		mg/kg
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Radium-226	1.06	-		pCi/g
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Radium-228	0.873	J		pCi/g
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Thorium-228	0.877	J		pCi/g
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Thorium-232	0.873	J		pCi/g
A5A-PC02	A5A-PC02A-12	A5A-PC02A-12^RM	Uranium, Total	9.46	-		mg/kg
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Arsenic	7.27	J		mg/kg
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Beryllium	0.696	-		mg/kg
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Radium-226	1.29	-		pCi/g
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Radium-228	0.969	J		pCi/g
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Thorium-228	0.971	J		pCi/g
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Thorium-232	0.969	J		pCi/g
A5A-PC02	A5A-PC02A-13	A5A-PC02A-13^RM	Uranium, Total	6.81	-		mg/kg
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Arsenic	6.6	J		mg/kg
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Beryllium	0.738	-		mg/kg
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Radium-226	1.53	-		pCi/g
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Radium-228	1.06	J		pCi/g
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Thorium-228	1.09	J		pCi/g
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Thorium-232	1.06	J		pCi/g
A5A-PC02	A5A-PC02A-14	A5A-PC02A-14^RM	Uranium, Total	7.22	-		mg/kg
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Arsenic	16.9	J		mg/kg
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Beryllium	0.97	-		mg/kg
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Radium-226	1.57	-		pCi/g
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Radium-228	1.17	J		pCi/g
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Thorium-228	1.18	J		pCi/g
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Thorium-232	1.17	J		pCi/g
A5A-PC02	A5A-PC02A-16	A5A-PC02A-16^RM	Uranium, Total	6.35	-		mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Arsenic	2.5	J		mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Arsenic	6.2	J		mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Beryllium	0.75	J		mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Beryllium	0.59	J		mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Radium-226	1.34	J		pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Radium-226	1.09	J		pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Radium-228	1.07	J		pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Radium-228	0.798	J		pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Thorium-228	1.12	J		pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Thorium-228	0.808	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	VQ	Units
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Thorium-232	1.07	J	pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Thorium-232	0.798	J	pCi/g
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM	Uranium, Total	4.47	J	mg/kg
A5A-PC03	A5A-PC03A-1	A5A-PC03A-1^RM-D	Uranium, Total	8.15	J	mg/kg
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Arsenic	8.5	J	mg/kg
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Beryllium	0.84	J	mg/kg
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Radium-226	1.15	J	pCi/g
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Radium-228	0.985	J	pCi/g
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Thorium-228	0.999	J	pCi/g
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Thorium-232	0.985	J	pCi/g
A5A-PC03	A5A-PC03A-2	A5A-PC03A-2^RM	Uranium, Total	14.5	J	mg/kg
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Arsenic	6.5	J	mg/kg
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Beryllium	0.66	J	mg/kg
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Radium-226	1.07	J	pCi/g
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Radium-228	0.858	J	pCi/g
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Thorium-228	0.858	J	pCi/g
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Thorium-232	0.858	J	pCi/g
A5A-PC03	A5A-PC03A-3	A5A-PC03A-3^RM	Uranium, Total	19.7	J	mg/kg
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Arsenic	6	J	mg/kg
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Beryllium	0.79	J	mg/kg
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Radium-226	1.08	J	pCi/g
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Radium-228	0.836	J	pCi/g
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Thorium-228	0.831	J	pCi/g
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Thorium-232	0.836	J	pCi/g
A5A-PC03	A5A-PC03A-5	A5A-PC03A-5^RM	Uranium, Total	6.43	J	mg/kg
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Arsenic	6.3	J	mg/kg
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Beryllium	0.61	J	mg/kg
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Radium-226	1.1	J	pCi/g
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Radium-228	0.969	J	pCi/g
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Thorium-228	0.971	J	pCi/g
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Thorium-232	0.969	J	pCi/g
A5A-PC03	A5A-PC03A-6	A5A-PC03A-6^RM	Uranium, Total	11.2	J	mg/kg
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Arsenic	5.2	J	mg/kg
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Beryllium	0.6	J	mg/kg
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Radium-226	1.49	J	pCi/g
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Radium-228	1.09	J	pCi/g
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Thorium-228	1.07	J	pCi/g
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Thorium-232	1.09	J	pCi/g
A5A-PC03	A5A-PC03A-8	A5A-PC03A-8^RM	Uranium, Total	5.06	J	mg/kg
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Arsenic	8.5	J	mg/kg
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Beryllium	0.84	J	mg/kg
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Radium-226	1.1	J	pCi/g
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Radium-228	0.865	J	pCi/g
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Thorium-228	0.857	J	pCi/g
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Thorium-232	0.865	J	pCi/g
A5A-PC03	A5A-PC03A-9	A5A-PC03A-9^RM	Uranium, Total	8.02	J	mg/kg
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Arsenic	7	J	mg/kg
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Beryllium	0.69	J	mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Radium-226	1.64	J		pCi/g
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Radium-228	0.965	J		pCi/g
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Thorium-228	1.3	J		pCi/g
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Thorium-232	0.965	J		pCi/g
A5A-PC03	A5A-PC03A-10	A5A-PC03A-10^RM	Uranium, Total	9.93	J		mg/kg
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Arsenic	5.6	J		mg/kg
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Beryllium	1	J		mg/kg
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Radium-226	1.44	J		pCi/g
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Radium-228	1.11	J		pCi/g
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Thorium-228	1.12	J		pCi/g
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Thorium-232	1.11	J		pCi/g
A5A-PC03	A5A-PC03A-11	A5A-PC03A-11^RM	Uranium, Total	7.06	J		mg/kg
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Arsenic	12.1	J		mg/kg
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Beryllium	0.85	J		mg/kg
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Radium-226	1.29	J		pCi/g
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Radium-228	1.13	J		pCi/g
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Thorium-228	1.17	J		pCi/g
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Thorium-232	1.13	J		pCi/g
A5A-PC03	A5A-PC03A-13	A5A-PC03A-13^RM	Uranium, Total	8.26	J		mg/kg
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Arsenic	7.1	J		mg/kg
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Beryllium	0.76	J		mg/kg
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Radium-226	1.12	J		pCi/g
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Radium-228	0.894	J		pCi/g
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Thorium-228	0.873	J		pCi/g
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Thorium-232	0.894	J		pCi/g
A5A-PC03	A5A-PC03A-14	A5A-PC03A-14^RM	Uranium, Total	11.2	J		mg/kg
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Arsenic	6.3	J		mg/kg
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Beryllium	0.73	J		mg/kg
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Radium-226	1.29	J		pCi/g
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Radium-228	1.03	J		pCi/g
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Thorium-228	1.05	J		pCi/g
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Thorium-232	1.03	J		pCi/g
A5A-PC03	A5A-PC03A-16	A5A-PC03A-16^RM	Uranium, Total	9.3	J		mg/kg
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Arsenic	6.4	-		mg/kg
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Beryllium	0.59	-		mg/kg
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Radium-226	0.841	J		pCi/g
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Radium-228	0.644	-		pCi/g
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Thorium-228	0.607	-		pCi/g
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Thorium-232	0.644	-		pCi/g
A5A-PC04	A5A-PC04A-1	A5A-PC04A-1^RM	Uranium, Total	8.59	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Arsenic	6.9	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Arsenic	7.6	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Beryllium	0.56	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Beryllium	0.65	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Radium-226	1.27	J		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Radium-226	1.08	J		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Radium-228	1.28	-		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Radium-228	1.16	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Thorium-228	1.34	-		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Thorium-228	1.18	-		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Thorium-232	1.28	-		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Thorium-232	1.16	-		pCi/g
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM	Uranium, Total	32.2	-		mg/kg
A5A-PC04	A5A-PC04A-3	A5A-PC04A-3^RM-D	Uranium, Total	35.3	-		mg/kg
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Arsenic	6.5	-		mg/kg
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Beryllium	0.8	-		mg/kg
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Radium-226	2.17	J		pCi/g
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Radium-228	1.03	-		pCi/g
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Thorium-228	1.01	-		pCi/g
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Thorium-232	1.03	-		pCi/g
A5A-PC04	A5A-PC04A-4	A5A-PC04A-4^RM	Uranium, Total	30.1	-		mg/kg
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Arsenic	7.29	-		mg/kg
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Beryllium	0.836	-		mg/kg
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Radium-226	1.25	-		pCi/g
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Radium-228	0.888	-		pCi/g
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Thorium-228	0.888	-		pCi/g
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Thorium-232	0.888	-		pCi/g
A5A-PC04	A5A-PC04A-5	A5A-PC04A-5^RM	Uranium, Total	9.31	-		mg/kg
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Arsenic	6.9	-		mg/kg
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Beryllium	0.806	-		mg/kg
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Radium-226	1.2	-		pCi/g
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Radium-228	0.911	-		pCi/g
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Thorium-228	0.906	-		pCi/g
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Thorium-232	0.911	-		pCi/g
A5A-PC04	A5A-PC04A-6	A5A-PC04A-6^RM	Uranium, Total	10.7	-		mg/kg
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Arsenic	6.5	-		mg/kg
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Beryllium	0.73	-		mg/kg
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Radium-226	1.12	-		pCi/g
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Radium-228	0.962	-		pCi/g
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Thorium-228	0.955	-		pCi/g
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Thorium-232	0.962	-		pCi/g
A5A-PC04	A5A-PC04A-8	A5A-PC04A-8^RM	Uranium, Total	5.17	-		mg/kg
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Arsenic	4.9	-		mg/kg
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Beryllium	0.54	-		mg/kg
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Radium-226	0.971	J		pCi/g
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Radium-228	0.87	-		pCi/g
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Thorium-228	0.87	-		pCi/g
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Thorium-232	0.87	-		pCi/g
A5A-PC04	A5A-PC04A-9	A5A-PC04A-9^RM	Uranium, Total	15.9	-		mg/kg
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Arsenic	5.7	-		mg/kg
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Beryllium	0.673	-		mg/kg
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Radium-226	1.41	-		pCi/g
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Radium-228	1.15	-		pCi/g
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Thorium-228	1.14	-		pCi/g
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Thorium-232	1.15	-		pCi/g
A5A-PC04	A5A-PC04A-10	A5A-PC04A-10^RM	Uranium, Total	47.1	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Arsenic	6.01	-		mg/kg
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Beryllium	0.616	-		mg/kg
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Radium-226	0.985	-		pCi/g
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Radium-228	0.773	-		pCi/g
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Thorium-228	0.782	-		pCi/g
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Thorium-232	0.773	-		pCi/g
A5A-PC04	A5A-PC04A-12	A5A-PC04A-12^RM	Uranium, Total	4.76	U		mg/kg
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Arsenic	5.71	-		mg/kg
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Beryllium	0.551	-		mg/kg
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Radium-226	1.04	-		pCi/g
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Radium-228	0.811	-		pCi/g
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Thorium-228	0.836	-		pCi/g
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Thorium-232	0.811	-		pCi/g
A5A-PC04	A5A-PC04A-13	A5A-PC04A-13^RM	Uranium, Total	5.41	J		mg/kg
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Arsenic	5.02	-		mg/kg
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Beryllium	0.584	-		mg/kg
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Radium-226	1.28	-		pCi/g
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Radium-228	1	-		pCi/g
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Thorium-228	1.02	-		pCi/g
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Thorium-232	1	-		pCi/g
A5A-PC04	A5A-PC04A-15	A5A-PC04A-15^RM	Uranium, Total	35.5	-		mg/kg
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Arsenic	5.79	-		mg/kg
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Beryllium	0.587	-		mg/kg
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Radium-226	1.14	-		pCi/g
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Radium-228	0.994	-		pCi/g
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Thorium-228	0.98	-		pCi/g
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Thorium-232	0.994	-		pCi/g
A5A-PC04	A5A-PC04A-16	A5A-PC04A-16^RM	Uranium, Total	4.67	U		mg/kg
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Arsenic	5.67	-		mg/kg
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Beryllium	0.447	-		mg/kg
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Radium-226	0.924	-		pCi/g
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Radium-228	0.867	-		pCi/g
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Thorium-228	0.869	-		pCi/g
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Thorium-232	0.867	-		pCi/g
A5A-PC05	A5A-PC05A-1	A5A-PC05A-1^RM	Uranium, Total	6.83	-		mg/kg
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Arsenic	8.24	-		mg/kg
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Beryllium	0.716	-		mg/kg
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Radium-226	1.27	-		pCi/g
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Radium-228	0.923	-		pCi/g
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Thorium-228	0.93	-		pCi/g
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Thorium-232	0.923	-		pCi/g
A5A-PC05	A5A-PC05A-2	A5A-PC05A-2^RM	Uranium, Total	9.06	-		mg/kg
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Arsenic	5.31	-		mg/kg
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Beryllium	0.555	-		mg/kg
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Radium-226	1.16	-		pCi/g
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Radium-228	0.888	-		pCi/g
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Thorium-228	0.898	-		pCi/g
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Thorium-232	0.888	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

GU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC05	A5A-PC05A-4	A5A-PC05A-4^RM	Uranium, Total	3.88	U		mg/kg
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Arsenic	7.67	-		mg/kg
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Beryllium	0.713	-		mg/kg
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Radium-226	1.38	-		pCi/g
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Radium-228	0.96	-		pCi/g
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Thorium-228	0.978	-		pCi/g
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Thorium-232	0.96	-		pCi/g
A5A-PC05	A5A-PC05A-5	A5A-PC05A-5^RM	Uranium, Total	9.33	-		mg/kg
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Arsenic	4.44	-		mg/kg
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Beryllium	0.532	-		mg/kg
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Radium-226	1.45	-		pCi/g
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Radium-228	1.17	-		pCi/g
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Thorium-228	1.2	-		pCi/g
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Thorium-232	1.17	-		pCi/g
A5A-PC05	A5A-PC05A-7	A5A-PC05A-7^RM	Uranium, Total	7.33	-		mg/kg
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Arsenic	8	-		mg/kg
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Beryllium	0.685	-		mg/kg
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Radium-226	1.38	-		pCi/g
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Radium-228	1.06	-		pCi/g
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Thorium-228	1.08	-		pCi/g
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Thorium-232	1.06	-		pCi/g
A5A-PC05	A5A-PC05A-8	A5A-PC05A-8^RM	Uranium, Total	5.99	-		mg/kg
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Arsenic	8.11	-		mg/kg
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Beryllium	0.647	-		mg/kg
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Radium-226	1.38	-		pCi/g
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Radium-228	0.975	-		pCi/g
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Thorium-228	0.98	-		pCi/g
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Thorium-232	0.975	-		pCi/g
A5A-PC05	A5A-PC05A-9	A5A-PC05A-9^RM	Uranium, Total	7.95	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Arsenic	6	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Arsenic	5.42	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Beryllium	0.573	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Beryllium	0.466	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Radium-226	1.08	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Radium-226	1.18	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Radium-228	0.829	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Radium-228	0.827	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Thorium-228	0.843	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Thorium-228	0.831	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Thorium-232	0.829	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Thorium-232	0.827	-		pCi/g
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM	Uranium, Total	10.1	-		mg/kg
A5A-PC05	A5A-PC05A-11	A5A-PC05A-11^RM-D	Uranium, Total	11.8	-		mg/kg
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Arsenic	5.82	-		mg/kg
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Beryllium	1.16	-		mg/kg
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Radium-226	1.7	-		pCi/g
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Radium-228	1.34	-		pCi/g
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Thorium-228	1.4	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Thorium-232	1.34	-		pCi/g
A5A-PC05	A5A-PC05A-12	A5A-PC05A-12^RM	Uranium, Total	8.6	-		mg/kg
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Arsenic	6.26	-		mg/kg
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Beryllium	0.557	-		mg/kg
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Radium-226	1.49	-		pCi/g
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Radium-228	1.14	-		pCi/g
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Thorium-228	1.13	-		pCi/g
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Thorium-232	1.14	-		pCi/g
A5A-PC05	A5A-PC05A-13	A5A-PC05A-13^RM	Uranium, Total	74.6	-		mg/kg
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Arsenic	5.88	-		mg/kg
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Beryllium	0.514	-		mg/kg
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Radium-226	1.18	-		pCi/g
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Radium-228	0.755	-		pCi/g
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Thorium-228	0.743	-		pCi/g
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Thorium-232	0.755	-		pCi/g
A5A-PC05	A5A-PC05A-14	A5A-PC05A-14^RM	Uranium, Total	5.02	J		mg/kg
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Arsenic	6.72	-		mg/kg
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Beryllium	0.746	-		mg/kg
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Radium-226	1.26	-		pCi/g
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Radium-228	0.93	-		pCi/g
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Thorium-228	0.913	-		pCi/g
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Thorium-232	0.93	-		pCi/g
A5A-PC05	A5A-PC05A-15	A5A-PC05A-15^RM	Uranium, Total	7.44	J		mg/kg
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Arsenic	8.14	-		mg/kg
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Beryllium	0.709	-		mg/kg
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Radium-226	1.13	J		pCi/g
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Radium-228	0.863	J		pCi/g
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Thorium-228	0.857	J		pCi/g
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Thorium-232	0.863	J		pCi/g
A5A-PC06	A5A-PC06A-1	A5A-PC06A-1^RM	Uranium, Total	6.01	J		mg/kg
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Arsenic	12.4	-		mg/kg
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Beryllium	0.773	-		mg/kg
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Radium-226	1.21	J		pCi/g
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Radium-228	0.941	J		pCi/g
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Thorium-228	0.933	J		pCi/g
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Thorium-232	0.941	J		pCi/g
A5A-PC06	A5A-PC06A-3	A5A-PC06A-3^RM	Uranium, Total	7.5	J		mg/kg
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Arsenic	7.73	-		mg/kg
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Beryllium	0.986	-		mg/kg
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Radium-226	1.26	J		pCi/g
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Radium-228	0.943	J		pCi/g
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Thorium-228	0.884	J		pCi/g
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Thorium-232	0.943	J		pCi/g
A5A-PC06	A5A-PC06A-4	A5A-PC06A-4^RM	Uranium, Total	14	J		mg/kg
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Arsenic	6.27	-		mg/kg
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Beryllium	0.483	-		mg/kg
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Radium-226	0.884	J		pCi/g
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Radium-228	0.842	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Thorium-228	0.874	J		pCi/g
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Thorium-232	0.842	J		pCi/g
A5A-PC06	A5A-PC06A-5	A5A-PC06A-5^RM	Uranium, Total	3.06	J		mg/kg
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Arsenic	7.6	-		mg/kg
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Beryllium	0.598	-		mg/kg
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Radium-226	1.11	J		pCi/g
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Radium-228	1	J		pCi/g
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Thorium-228	0.988	J		pCi/g
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Thorium-232	1	J		pCi/g
A5A-PC06	A5A-PC06A-6	A5A-PC06A-6^RM	Uranium, Total	7.47	J		mg/kg
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Arsenic	4.9	-		mg/kg
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Beryllium	0.439	-		mg/kg
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Radium-226	0.993	J		pCi/g
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Radium-228	0.823	J		pCi/g
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Thorium-228	0.833	J		pCi/g
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Thorium-232	0.823	J		pCi/g
A5A-PC06	A5A-PC06A-7	A5A-PC06A-7^RM	Uranium, Total	5.84	J		mg/kg
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Arsenic	7	-		mg/kg
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Beryllium	0.671	-		mg/kg
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Radium-226	1.05	J		pCi/g
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Radium-228	0.837	J		pCi/g
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Thorium-228	0.826	J		pCi/g
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Thorium-232	0.837	J		pCi/g
A5A-PC06	A5A-PC06A-9	A5A-PC06A-9^RM	Uranium, Total	9.13	J		mg/kg
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Arsenic	7.68	-		mg/kg
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Beryllium	0.711	-		mg/kg
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Radium-226	1.1	J		pCi/g
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Radium-228	0.908	J		pCi/g
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Thorium-228	0.899	J		pCi/g
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Thorium-232	0.908	J		pCi/g
A5A-PC06	A5A-PC06A-10	A5A-PC06A-10^RM	Uranium, Total	7.87	J		mg/kg
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Arsenic	4.96	-		mg/kg
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Beryllium	0.496	-		mg/kg
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Radium-226	0.81	J		pCi/g
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Radium-228	0.696	J		pCi/g
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Thorium-228	0.682	J		pCi/g
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Thorium-232	0.696	J		pCi/g
A5A-PC06	A5A-PC06A-11	A5A-PC06A-11^RM	Uranium, Total	3.28	J		mg/kg
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Arsenic	6.35	-		mg/kg
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Beryllium	0.498	-		mg/kg
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Radium-226	1	J		pCi/g
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Radium-228	0.802	J		pCi/g
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Thorium-228	0.821	J		pCi/g
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Thorium-232	0.802	J		pCi/g
A5A-PC06	A5A-PC06A-14	A5A-PC06A-14^RM	Uranium, Total	4.64	J		mg/kg
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Arsenic	5.81	-		mg/kg
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Arsenic	6.61	-		mg/kg
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Beryllium	0.602	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Beryllium	0.631	-		mg/kg
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Radium-226	1.39	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Radium-226	1.3	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Radium-228	1.32	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Radium-228	0.979	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Thorium-228	1.38	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Thorium-228	0.98	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Thorium-232	1.32	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Thorium-232	0.979	J		pCi/g
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM	Uranium, Total	13.7	J		mg/kg
A5A-PC06	A5A-PC06A-15	A5A-PC06A-15^RM-D	Uranium, Total	10.6	J		mg/kg
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Arsenic	8.07	-		mg/kg
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Beryllium	0.831	-		mg/kg
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Radium-226	1.29	J		pCi/g
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Radium-228	0.805	J		pCi/g
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Thorium-228	0.839	J		pCi/g
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Thorium-232	0.805	J		pCi/g
A5A-PC06	A5A-PC06A-16	A5A-PC06A-16^RM	Uranium, Total	6.6	J		mg/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	1,1,1-Trichloroethane	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	1,1-Dichloroethene	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	1,2-Dichloroethene (Total)	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Aroclor-1254	5.6	J		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Aroclor-1260	3.6	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Arsenic	5.2	-		mg/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Benzo(a)pyrene	120	J		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Benzo(b)fluoranthene	165	J		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Beryllium	0.6	-		mg/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	Bromodichloromethane	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Cesium-137	0.0639	U		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Chromium	16	J		mg/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Dibenzo(a,h)anthracene	35.8	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Dieldrin	1.4	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Fluoride	5.18	J		mg/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Indeno(1,2,3-cd)pyrene	79.7	J		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Lead-210	1.07	J		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Radium-226	0.976326	-		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Radium-228	0.655	-		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Technetium-99	1.6	U		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	Tetrachloroethene	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Thorium-228	0.652	-		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Thorium-230	1.16	-		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Thorium-232	0.655	-		pCi/g
A5A-PC08	A5A-PC08-1	A5A-PC08-1^L	Trichloroethene	1.2	U		ug/kg
A5A-PC08	A5A-PC08-1	A5A-PC08-1^RMPS	Uranium, Total	6.7	-		mg/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	1,1,1-Trichloroethane	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	1,1-Dichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	1,2-Dichloroethene (Total)	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Aroclor-1254	3.6	J		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Aroclor-1260	3.6	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Arsenic	5.5	-		mg/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Benzo(a)pyrene	110	J		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Benzo(b)fluoranthene	192	J		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Beryllium	0.55	-		mg/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	Bromodichloromethane	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Cesium-137	0.0801	U		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Chromium	15.5	J		mg/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Dibenzo(a,h)anthracene	35.6	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Dieldrin	1.4	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Fluoride	3.86	J		mg/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Indeno(1,2,3-cd)pyrene	62	J		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Lead-210	0.838	U		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Radium-226	1.1111	-		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Radium-228	0.812	-		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Technetium-99	1.35	U		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	Tetrachloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Thorium-228	0.815	-		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Thorium-230	1.64	-		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Thorium-232	0.812	-		pCi/g
A5A-PC08	A5A-PC08-2	A5A-PC08-2^L	Trichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-2	A5A-PC08-2^RMPS	Uranium, Total	6.2	-		mg/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	1,2-Dichloroethene (Total)	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Aroclor-1254	3.7	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Arsenic	5.6	-		mg/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Benzo(a)pyrene	42	J		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Benzo(b)fluoranthene	56.5	J		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Beryllium	0.55	-		mg/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	Bromodichloromethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Cesium-137	0.0961	U		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Chromium	15.9	J		mg/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Dibenzo(a,h)anthracene	36.6	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Fluoride	4.73	J		mg/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Indeno(1,2,3-cd)pyrene	36.6	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Lead-210	1.57	J		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Radium-226	1.21641	-		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Radium-228	0.772	-		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Technetium-99	1.32	U		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	Tetrachloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Thorium-228	0.762	-		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Thorium-230	1.39	-		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Thorium-232	0.772	-		pCi/g
A5A-PC08	A5A-PC08-4	A5A-PC08-4^L	Trichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-4	A5A-PC08-4^RMPS	Uranium, Total	5.54	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	1,1,1-Trichloroethane	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	1,1-Dichloroethene	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	1,2-Dichloroethene (Total)	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Aroclor-1254	5.3		J	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Aroclor-1260	3.7		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Arsenic	5.4		-	mg/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Benzo(a)pyrene	243		-	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Benzo(b)fluoranthene	403		J	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Beryllium	0.55		-	mg/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	Bromodichloromethane	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Cesium-137	0.0949		U	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Chromium	15.3		J	mg/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Dibenzo(a,h)anthracene	36.8		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Dieldrin	1.5		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Fluoride	4.95		J	mg/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Indeno(1,2,3-cd)pyrene	126		J	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Lead-210	0.975		U	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Radium-226	1.20588		-	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Radium-228	0.783		-	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Technetium-99	1.56		U	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	Tetrachloroethene	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Thorium-228	0.818		-	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Thorium-230	1.59		-	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Thorium-232	0.783		-	pCi/g
A5A-PC08	A5A-PC08-5	A5A-PC08-5^L	Trichloroethene	1		U	ug/kg
A5A-PC08	A5A-PC08-5	A5A-PC08-5^RMPS	Uranium, Total	7.21		-	mg/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	1,1,1-Trichloroethane	1		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	1,1-Dichloroethene	1		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	1,2-Dichloroethene (Total)	1		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Aroclor-1254	3.7		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Aroclor-1260	3.7		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Arsenic	5.3		-	mg/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Benzo(a)pyrene	65.3		J	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Benzo(b)fluoranthene	117		J	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Beryllium	0.53		-	mg/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	Bromodichloromethane	1		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Cesium-137	0.0735		U	pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Chromium	18.9		J	mg/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Dibenzo(a,h)anthracene	36.8		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Dieldrin	1.5		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Fluoride	2.85		J	mg/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Indeno(1,2,3-cd)pyrene	36.8		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Lead-210	0.781		U	pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Radium-226	1.0374		-	pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Radium-228	0.712		-	pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Technetium-99	1.51		U	pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	Tetrachloroethene	1		U	ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Thorium-228	0.722		-	pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Thorium-230	1.77	-		pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Thorium-232	0.712	-		pCi/g
A5A-PC08	A5A-PC08-7	A5A-PC08-7^L	Trichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-7	A5A-PC08-7^RMPS	Uranium, Total	6.4	-		mg/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	1,1,1-Trichloroethane	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	1,1-Dichloroethene	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	1,2-Dichloroethene (Total)	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Aroclor-1254	8.9	J		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Aroclor-1260	4.4	J		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Arsenic	5.2	-		mg/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Benzo(a)pyrene	134	J		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Benzo(b)fluoranthene	234	J		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Beryllium	0.48	-		mg/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	Bromodichloromethane	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Cesium-137	0.0807	U		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Chromium	13.3	J		mg/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Dibenzo(a,h)anthracene	36.3	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Fluoride	4.04	J		mg/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Indeno(1,2,3-cd)pyrene	65.3	J		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Lead-210	0.789	U		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Radium-226	1.07952	-		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Radium-228	0.743	-		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Technetium-99	1.7	J		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	Tetrachloroethene	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Thorium-228	0.742	-		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Thorium-230	1.82	-		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Thorium-232	0.743	-		pCi/g
A5A-PC08	A5A-PC08-8	A5A-PC08-8^L	Trichloroethene	1.1	U		ug/kg
A5A-PC08	A5A-PC08-8	A5A-PC08-8^RMPS	Uranium, Total	11.6	-		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	1,1,1-Trichloroethane	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	1,1-Dichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	1,2-Dichloroethene (Total)	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	1,2-Dichloroethene (Total)	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Aroclor-1254	6.3	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Aroclor-1254	5.1	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Aroclor-1260	3.8	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Aroclor-1260	3.8	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Arsenic	5.76	-		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Arsenic	5.17	-		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Benzo(a)pyrene	130	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Benzo(a)pyrene	173	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Benzo(b)fluoranthene	197	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Benzo(b)fluoranthene	270	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Beryllium	0.599	-		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Beryllium	0.526	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

GU	Boring	SampleID	Parameter	Val	Res	VO	Units
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	Bromodichloromethane	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	Bromodichloromethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Cesium-137	0.0455	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Cesium-137	0.0484	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Chromium	14.7	J		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Chromium	13.4	J		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Dibenzo(a,h)anthracene	141	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Dibenzo(a,h)anthracene	145	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Fluoride	0.794	J		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Fluoride	0.736	J		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Indeno(1,2,3-cd)pyrene	146	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Indeno(1,2,3-cd)pyrene	162	J		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Lead-210	5.36	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Lead-210	5.49	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Radium-226	1.05846	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Radium-226	1.07952	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Radium-228	0.684	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Radium-228	0.693	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Technetium-99	0.868	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Technetium-99	0.848	U		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	Tetrachloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	Tetrachloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Thorium-228	0.66	J		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Thorium-228	0.686	J		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Thorium-230	1.15	J		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Thorium-230	1.72	J		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Thorium-232	0.684	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Thorium-232	0.693	-		pCi/g
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L	Trichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^L-D	Trichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS	Uranium, Total	8.8	-		mg/kg
A5A-PC08	A5A-PC08-9	A5A-PC08-9^RMPS-D	Uranium, Total	8.77	-		mg/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	1,1,1-Trichloroethane	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	1,1-Dichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	1,2-Dichloroethene (Total)	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Aroclor-1254	18.8	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Aroclor-1260	18.8	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Arsenic	3.85	-		mg/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Benzo(a)pyrene	296	-		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Benzo(b)fluoranthene	488	J		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Beryllium	1.72	-		mg/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	Bromodichloromethane	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Cesium-137	0.0467	U		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Chromium	12.5	J		mg/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Dibenzo(a,h)anthracene	160	J		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Dieldrin	1.5	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	QA	Units
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Fluoride	0.586	J		mg/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Indeno(1,2,3-cd)pyrene	215	J		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Lead-210	5.33	U		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Radium-226	0.746772	-		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Radium-228	0.583	-		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Technetium-99	0.807	U		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	Tetrachloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Thorium-228	0.596	J		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Thorium-230	1.02	J		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Thorium-232	0.583	-		pCi/g
A5A-PC08	A5A-PC08-11	A5A-PC08-11^L	Trichloroethene	1	U		ug/kg
A5A-PC08	A5A-PC08-11	A5A-PC08-11^RMPS	Uranium, Total	11.2	-		mg/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	1,2-Dichloroethene (Total)	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Aroclor-1254	3.8	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Aroclor-1260	3.8	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Arsenic	4.8	-		mg/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Benzo(a)pyrene	38.2	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Benzo(b)fluoranthene	106	J		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Beryllium	0.527	-		mg/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	Bromodichloromethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Cesium-137	0.0549	U		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Chromium	13.6	J		mg/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Dibenzo(a,h)anthracene	38.2	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Fluoride	0.738	J		mg/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Indeno(1,2,3-cd)pyrene	127	J		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Lead-210	5.48	U		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Radium-226	0.895245	-		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Radium-228	0.729	-		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Technetium-99	0.866	U		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	Tetrachloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Thorium-228	0.739	J		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Thorium-230	1.14	J		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Thorium-232	0.729	-		pCi/g
A5A-PC08	A5A-PC08-12	A5A-PC08-12^L	Trichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-12	A5A-PC08-12^RMPS	Uranium, Total	6.56	-		mg/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	1,2-Dichloroethene (Total)	0.9	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Aroclor-1254	3.8	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Aroclor-1260	3.8	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Arsenic	4.65	-		mg/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Benzo(a)pyrene	348	-		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Benzo(b)fluoranthene	629	J		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Beryllium	0.464	-		mg/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	Bromodichloromethane	0.9	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Cesium-137	0.0797	J		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Chromium	12.1	J		mg/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Dibenzo(a,h)anthracene	37.8	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Fluoride	0.647	J		mg/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Indeno(1,2,3-cd)pyrene	235	J		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Lead-210	5.35	U		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Radium-226	0.81627	-		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Radium-228	0.647	-		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Technetium-99	0.945	U		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	Tetrachloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Thorium-228	0.61	J		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Thorium-230	1.25	J		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Thorium-232	0.647	-		pCi/g
A5A-PC08	A5A-PC08-13	A5A-PC08-13^L	Trichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-13	A5A-PC08-13^RMPS	Uranium, Total	4.41	J		mg/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	1,1,1-Trichloroethane	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	1,1-Dichloroethene	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	1,2-Dichloroethene (Total)	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Aroclor-1254	3.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Aroclor-1260	3.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Arsenic	5.99	-		mg/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Benzo(a)pyrene	270	-		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Benzo(b)fluoranthene	412	J		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Beryllium	0.527	-		mg/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	Bromodichloromethane	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Cesium-137	0.0473	U		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Chromium	14.4	J		mg/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Dibenzo(a,h)anthracene	38	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Fluoride	0.652	J		mg/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Indeno(1,2,3-cd)pyrene	195	J		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Lead-210	5.71	U		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Radium-226	0.886821	-		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Radium-228	0.712	-		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Technetium-99	0.859	U		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	Tetrachloroethene	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Thorium-228	0.709	J		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Thorium-230	1.18	J		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Thorium-232	0.712	-		pCi/g
A5A-PC08	A5A-PC08-15	A5A-PC08-15^L	Trichloroethene	0.8	U		ug/kg
A5A-PC08	A5A-PC08-15	A5A-PC08-15^RMPS	Uranium, Total	2.88	U		mg/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	1,2-Dichloroethene (Total)	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Aroclor-1254	3.7	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Arsenic	4.14	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Benzo(a)pyrene	283	-		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Benzo(b)fluoranthene	421	J		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Beryllium	0.43	-		mg/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	Bromodichloromethane	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Cesium-137	0.141	-		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Chromium	10.5	J		mg/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Dibenzo(a,h)anthracene	37.2	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Fluoride	0.645	J		mg/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Indeno(1,2,3-cd)pyrene	249	J		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Lead-210	5.2	U		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Radium-226	0.895245	-		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Radium-228	0.709	-		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Technetium-99	0.865	U		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	Tetrachloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Thorium-228	0.697	J		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Thorium-230	1.16	J		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Thorium-232	0.709	-		pCi/g
A5A-PC08	A5A-PC08-16	A5A-PC08-16^L	Trichloroethene	0.9	U		ug/kg
A5A-PC08	A5A-PC08-16	A5A-PC08-16^RMPS	Uranium, Total	6.91	-		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	1,1,1-Trichloroethane	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	1,1-Dichloroethene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	1,2-Dichloroethane	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	4-Methyl-2-pentanone	6.4	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Acetone	6.4	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Antimony	2.02	UJ		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Aroclor-1254	3.8	J		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Aroclor-1260	3.5	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Arsenic	7.2	J		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Barium	105	-		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Benzene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Benzo(a)anthracene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Benzo(a)pyrene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Benzo(b)fluoranthene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Benzo(g,h,i)perylene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Benzo(k)fluoranthene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Beryllium	0.64	-		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Cadmium	0.504	U		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Carbon Tetrachloride	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Cesium-137	0.044	U		pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Chromium	20.9	J		mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Chrysene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Dibenzo(a,h)anthracene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Dieldrin	1.4	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Ethylbenzene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Fluoranthene	38.4	J		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Indeno(1,2,3-cd)pyrene	35.1	U		ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Lead	11.9	J		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	VQ	Units
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Mercury	0.024	J	mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Methylene chloride	6.4	J	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Molybdenum	1.01	U	mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Phenanthrene	35.1	U	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Pyrene	38.1	J	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Radium-226	1.010022	-	pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Radium-228	0.946	-	pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Selenium	16.8	J	mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Silver	1.1	-	mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Technetium-99	1.44	U	pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Tetrachloroethene	1.3	U	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Thorium-228	0.948	-	pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Thorium-232	0.946	-	pCi/g
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Toluene	3.8	J	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Trichloroethene	1.3	U	ug/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^RMPS	Uranium, Total	8.79	-	mg/kg
A5A-PC09	A5A-PC09-1	A5A-PC09-1^L	Xylenes, Total	6.2	J	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	1,1,1-Trichloroethane	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	1,1-Dichloroethene	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	1,2-Dichloroethane	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	4-Methyl-2-pentanone	6.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Acetone	6.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Antimony	0.454	UJ	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Aroclor-1254	3.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Aroclor-1260	3.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Arsenic	6.4	J	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Barium	102	-	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Benzene	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Benzo(a)anthracene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Benzo(a)pyrene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Benzo(b)fluoranthene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Benzo(g,h,i)perylene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Benzo(k)fluoranthene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Beryllium	0.6	-	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Cadmium	0.113	U	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Carbon Tetrachloride	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Cesium-137	0.055	U	pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Chromium	20.1	J	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Chrysene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Dibenzo(a,h)anthracene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Dieldrin	1.5	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Ethylbenzene	1.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Fluoranthene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Indeno(1,2,3-cd)pyrene	37.8	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Lead	12.9	J	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Mercury	0.022	J	mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Methylene chloride	6.3	U	ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Molybdenum	1	U	mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Phenanthrene	37.8	U		ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Pyrene	37.8	U		ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Radium-226	1.018446	-		pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Radium-228	0.919	-		pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Selenium	8.3	J		mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Silver	1	-		mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Technetium-99	1.4	U		pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Tetrachloroethene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Thorium-228	0.918	-		pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Thorium-232	0.919	-		pCi/g
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Toluene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Trichloroethene	1.3	U		ug/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^RMPS	Uranium, Total	6.78	-		mg/kg
A5A-PC09	A5A-PC09-3	A5A-PC09-3^L	Xylenes, Total	1.3	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	1,1,1-Trichloroethane	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	1,1,1-Trichloroethane	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	1,1-Dichloroethene	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	1,1-Dichloroethene	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	1,2-Dichloroethane	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	1,2-Dichloroethane	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	4-Methyl-2-pentanone	5	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	4-Methyl-2-pentanone	4.7	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Acetone	5	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Acetone	4.7	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Antimony	2.16	UJ		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Antimony	2.16	UJ		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Aroclor-1254	8	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Aroclor-1254	6	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Arsenic	4.7	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Arsenic	6.8	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Barium	109	-		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Barium	102	-		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Benzene	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Benzene	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Benzo(a)anthracene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Benzo(a)anthracene	37.2	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Benzo(a)pyrene	59	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Benzo(a)pyrene	37.2	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Benzo(b)fluoranthene	101	-		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Benzo(b)fluoranthene	124	-		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Benzo(g,h,i)perylene	43.5	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Benzo(g,h,i)perylene	48.5	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Benzo(k)fluoranthene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Benzo(k)fluoranthene	113	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Beryllium	0.51	-		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Beryllium	0.62	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Cadmium	0.108	U		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Cadmium	0.108	U		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Carbon Tetrachloride	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Carbon Tetrachloride	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Cesium-137	0.058	U		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Cesium-137	0.05	U		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Chromium	18.9	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Chromium	17	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Chrysene	59.9	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Chrysene	96.1	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Dibenzo(a,h)anthracene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Dibenzo(a,h)anthracene	37.2	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Ethylbenzene	1	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Ethylbenzene	0.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Fluoranthene	76.8	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Fluoranthene	175	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Indeno(1,2,3-cd)pyrene	39.8	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Indeno(1,2,3-cd)pyrene	37.2	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Lead	12.7	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Lead	13.3	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Mercury	0.028	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Mercury	0.03	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Methylene chloride	5	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Methylene chloride	4.7	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Molybdenum	0.99	U		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Molybdenum	1.2	U		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Phenanthrene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Phenanthrene	109	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Pyrene	78.7	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Pyrene	145	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Radium-226	1.023711	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Radium-226	0.922623	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Radium-228	0.921	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Radium-228	0.88	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Selenium	5.9	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Selenium	5.7	J		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Silver	1.2	-		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Silver	1.1	-		mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Technetium-99	1.43	U		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Technetium-99	1.52	U		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Tetrachloroethene	3.7	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Tetrachloroethene	1.4	J		ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Thorium-228	0.904	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Thorium-228	0.872	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Thorium-232	0.921	-		pCi/g
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Thorium-232	0.88	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

GU	Boring	SampleID	Parameter	Val:Res	UQ	Units
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Toluene	1	U	ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Toluene	0.9	U	ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Trichloroethene	1	U	ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Trichloroethene	0.9	U	ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS	Uranium, Total	15	-	mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^RMPS-D	Uranium, Total	14.2	-	mg/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L	Xylenes, Total	1.5	J	ug/kg
A5A-PC09	A5A-PC09-4	A5A-PC09-4^L-D	Xylenes, Total	0.9	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	1,1,1-Trichloroethane	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	1,1-Dichloroethene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	1,2-Dichloroethane	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	4-Methyl-2-pentanone	5.9	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Acetone	5.9	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Antimony	0.444	UJ	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Aroclor-1254	3.8	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Aroclor-1260	3.8	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Arsenic	6.3	J	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Barium	108	-	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Benzene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Benzo(a)anthracene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Benzo(a)pyrene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Benzo(b)fluoranthene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Benzo(g,h,i)perylene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Benzo(k)fluoranthene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Beryllium	0.69	-	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Cadmium	0.111	U	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Carbon Tetrachloride	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Cesium-137	0.052	U	pCi/g
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Chromium	18.2	J	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Chrysene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Dibenzo(a,h)anthracene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Dieldrin	1.5	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Ethylbenzene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Fluoranthene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Indeno(1,2,3-cd)pyrene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Lead	12.8	J	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Mercury	0.03	J	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Methylene chloride	5.9	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Molybdenum	0.67	U	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Phenanthrene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Pyrene	38.4	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Radium-226	0.912093	-	pCi/g
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Radium-228	1.04	-	pCi/g
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Selenium	11.4	J	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Silver	0.77	-	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Technetium-99	1.57	U	pCi/g
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Tetrachloroethene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Thorium-228	1.03	-	pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	VQ	Units
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Thorium-232	1.04	-	pCi/g
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Toluene	2	J	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Trichloroethene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^RMPS	Uranium, Total	6	-	mg/kg
A5A-PC09	A5A-PC09-5	A5A-PC09-5^L	Xylenes, Total	3	J	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	1,1,1-Trichloroethane	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	1,1-Dichloroethene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	1,2-Dichloroethane	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	4-Methyl-2-pentanone	6.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Acetone	6.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Antimony	0.423	UJ	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Aroclor-1254	3.7	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Aroclor-1260	3.7	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Arsenic	7.7	J	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Barium	100	-	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Benzene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Benzo(a)anthracene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Benzo(a)pyrene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Benzo(b)fluoranthene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Benzo(g,h,i)perylene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Benzo(k)fluoranthene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Beryllium	0.68	-	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Cadmium	0.106	U	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Carbon Tetrachloride	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Cesium-137	0.046	U	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Chromium	18.8	J	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Chrysene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Dibenzo(a,h)anthracene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Dieldrin	1.5	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Ethylbenzene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Fluoranthene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Indeno(1,2,3-cd)pyrene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Lead	11.1	J	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Mercury	0.017	J	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Methylene chloride	6.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Molybdenum	1.1	U	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Phenanthrene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Pyrene	37	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Radium-226	0.970008	-	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Radium-228	0.965	-	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Selenium	7.3	J	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Silver	0.93	-	mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Technetium-99	1.48	U	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Tetrachloroethene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Thorium-228	0.926	-	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Thorium-232	0.965	-	pCi/g
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Toluene	1.2	U	ug/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Trichloroethene	1.2	U	ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-7	A5A-PC09-7^RMPS	Uranium, Total	9.42	-		mg/kg
A5A-PC09	A5A-PC09-7	A5A-PC09-7^L	Xylenes, Total	1.2	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	1,1,1-Trichloroethane	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	1,1-Dichloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	1,2-Dichloroethane	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	4-Methyl-2-pentanone	5.4	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Acetone	5.4	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Antimony	2.18	UJ		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Aroclor-1254	3.7	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Arsenic	10.5	J		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Barium	129	-		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Benzene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Benzo(a)anthracene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Benzo(a)pyrene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Benzo(b)fluoranthene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Benzo(g,h,i)perylene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Benzo(k)fluoranthene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Beryllium	0.76	-		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Cadmium	0.544	U		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Carbon Tetrachloride	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Cesium-137	0.055	U		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Chromium	24.6	J		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Chrysene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Dibenzo(a,h)anthracene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Ethylbenzene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Fluoranthene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Indeno(1,2,3-cd)pyrene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Lead	14.3	J		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Mercury	0.027	J		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Methylene chloride	5.4	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Molybdenum	1.09	U		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Phenanthrene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Pyrene	37.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Radium-226	1.33224	-		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Radium-228	1.14	-		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Selenium	27	J		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Silver	1.5	-		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Technetium-99	1.46	U		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Tetrachloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Thorium-228	1.13	-		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Thorium-232	1.14	-		pCi/g
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Toluene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Trichloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^RMPS	Uranium, Total	5.31	-		mg/kg
A5A-PC09	A5A-PC09-8	A5A-PC09-8^L	Xylenes, Total	1.1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	1,1,1-Trichloroethane	1	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	1,1-Dichloroethene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	1,2-Dichloroethane	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	4-Methyl-2-pentanone	4.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Acetone	4.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Antimony	2.9	U		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Aroclor-1254	3.7	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Arsenic	6.3	J		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Barium	103	-		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Benzene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Benzo(a)anthracene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Benzo(a)pyrene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Benzo(b)fluoranthene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Benzo(g,h,i)perylene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Benzo(k)fluoranthene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Beryllium	0.57	-		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Cadmium	0.538	U		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Carbon Tetrachloride	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Cesium-137	0.069	U		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Chromium	19.9	J		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Chrysene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Dibenzo(a,h)anthracene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Ethylbenzene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Fluoranthene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Indeno(1,2,3-cd)pyrene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Lead	13.9	J		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Mercury	0.022	J		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Methylene chloride	4.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Molybdenum	2.2	-		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Phenanthrene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Pyrene	36.9	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Radium-226	1.06899	-		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Radium-228	0.793	-		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Selenium	9.4	J		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Silver	1.5	-		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Technetium-99	1.52	U		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Tetrachloroethene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Thorium-228	0.795	-		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Thorium-232	0.793	-		pCi/g
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Toluene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Trichloroethene	1	U		ug/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^RMPS	Uranium, Total	6.29	-		mg/kg
A5A-PC09	A5A-PC09-9	A5A-PC09-9^L	Xylenes, Total	1	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	1,1,1-Trichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	1,1-Dichloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	1,2-Dichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	4-Methyl-2-pentanone	6.1	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Acetone	6.1	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Antimony	2.18	UJ		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Aroclor-1254	3.7	U		ug/kg
5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Arsenic	9.4	J		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Barium	58.1	-		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Benzene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Benzo(a)anthracene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Benzo(a)pyrene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Benzo(b)fluoranthene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Benzo(g,h,i)perylene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Benzo(k)fluoranthene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Beryllium	0.75	-		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Cadmium	0.109	U		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Carbon Tetrachloride	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Cesium-137	0.047	U		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Chromium	10.9	J		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Chrysene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Dibenzo(a,h)anthracene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Ethylbenzene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Fluoranthene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Indeno(1,2,3-cd)pyrene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Lead	9.4	J		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Mercury	0.022	J		mg/kg
5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Methylene chloride	6.1	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Molybdenum	0.91	U		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Phenanthrene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Pyrene	37.4	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Radium-226	0.980538	-		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Radium-228	0.978	-		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Selenium	13.1	J		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Silver	1.8	-		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Technetium-99	1.43	U		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Tetrachloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Thorium-228	0.982	-		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Thorium-232	0.978	-		pCi/g
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Toluene	2.6	J		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Trichloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^RMPS	Uranium, Total	5.73	-		mg/kg
A5A-PC09	A5A-PC09-10	A5A-PC09-10^L	Xylenes, Total	3.2	J		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	1,1,1-Trichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	1,1-Dichloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	1,2-Dichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	4-Methyl-2-pentanone	5.7	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Acetone	5.7	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Antimony	2.13	UJ		mg/kg
A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Aroclor-1254	3.7	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Aroclor-1260	3.7	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Arsenic	5.7	J		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Barium	195	J		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Benzene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Benzo(a)anthracene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Benzo(a)pyrene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Benzo(b)fluoranthene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Benzo(g,h,i)perylene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Benzo(k)fluoranthene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Beryllium	0.69	-		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Cadmium	1	-		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Carbon Tetrachloride	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Cesium-137	0.062	U		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Chromium	26.7	J		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Chrysene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Dibenzo(a,h)anthracene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Ethylbenzene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Fluoranthene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Indeno(1,2,3-cd)pyrene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Lead	14.6	J		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Mercury	0.03	J		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Methylene chloride	5.7	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Molybdenum	1.4	-		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Phenanthrene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Pyrene	37.3	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Radium-226	0.934206	-		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Radium-228	0.957	-		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Selenium	3.2	U		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Silver	0.107	U		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Technetium-99	1.5	U		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Tetrachloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Thorium-228	0.962	-		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Thorium-232	0.957	-		pCi/g
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Toluene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Trichloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^RMPS	Uranium, Total	5.04	-		mg/kg
A5A-PC09	A5A-PC09-12	A5A-PC09-12^L	Xylenes, Total	1.2	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	1,1,1-Trichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	1,1-Dichloroethene	1.2	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	1,2-Dichloroethane	1.2	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	4-Methyl-2-pentanone	5.9	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Acetone	5.9	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Antimony	3	U		mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Aroclor-1254	3.6	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Aroclor-1260	3.6	U		ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Arsenic	7.4	J		mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Barium	113	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Benzene	1.2		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Benzo(a)anthracene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Benzo(a)pyrene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Benzo(b)fluoranthene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Benzo(g,h,i)perylene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Benzo(k)fluoranthene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Beryllium	0.64		-	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Cadmium	0.105		U	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Carbon Tetrachloride	1.2		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Cesium-137	0.052		U	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Chromium	18.7		J	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Chrysene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Dibenzo(a,h)anthracene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Dieldrin	1.5		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Ethylbenzene	1.2		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Fluoranthene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Indeno(1,2,3-cd)pyrene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Lead	13.2		J	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Mercury	0.022		J	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Methylene chloride	6.2		J	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Molybdenum	1.1		U	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Phenanthrene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Pyrene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Radium-226	1.06899		-	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Radium-228	0.926		-	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Selenium	7		J	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Silver	1.3		-	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Technetium-99	1.5		U	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Tetrachloroethene	1.2		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Thorium-228	0.919		-	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Thorium-232	0.926		-	pCi/g
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Toluene	2.4		J	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Trichloroethene	1.2		U	ug/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^RMPS	Uranium, Total	8.46		-	mg/kg
A5A-PC09	A5A-PC09-13	A5A-PC09-13^L	Xylenes, Total	3.6		J	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	1,1,1-Trichloroethane	1.1		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	1,1-Dichloroethene	1.1		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	1,2-Dichloroethane	1.1		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	4-Methyl-2-pentanone	5.5		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Acetone	5.5		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Antimony	2.16		UJ	mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Aroclor-1254	12		J	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Aroclor-1260	6.3		J	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Arsenic	7.7		J	mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Barium	116		-	mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Benzene	1.1		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Benzo(a)anthracene	36.3		U	ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Benzo(a)pyrene	36.3		U	ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Benzo(b)fluoranthene	36.3	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Benzo(g,h,i)perylene	36.3	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Benzo(k)fluoranthene	36.3	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Beryllium	0.74	-		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Cadmium	0.54	U		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Carbon Tetrachloride	1.1	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Cesium-137	0.156	-		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Chromium	20.9	J		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Chrysene	39.3	J		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Dibenzo(a,h)anthracene	36.3	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Dieldrin	1.5	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Ethylbenzene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Fluoranthene	71.3	J		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Indeno(1,2,3-cd)pyrene	36.3	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Lead	16.6	J		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Mercury	0.029	J		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Methylene chloride	5.5	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Molybdenum	1.3	U		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Phenanthrene	38.1	J		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Pyrene	61.6	J		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Radium-226	1.07952	-		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Radium-228	1.11	-		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Selenium	20.6	J		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Silver	1.2	-		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Technetium-99	1.49	U		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Tetrachloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Thorium-228	1.1	-		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Thorium-232	1.11	-		pCi/g
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Toluene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Trichloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^RMPS	Uranium, Total	18.8	-		mg/kg
A5A-PC09	A5A-PC09-15	A5A-PC09-15^L	Xylenes, Total	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	1,1,1-Trichloroethane	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	1,1-Dichloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	1,2-Dichloroethane	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	4-Methyl-2-pentanone	5.7	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Acetone	5.7	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Antimony	3.4	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Aroclor-1254	8.1	J		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Aroclor-1260	3.5	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Arsenic	6.1	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Barium	84.4	-		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Benzene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Benzo(a)anthracene	151	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Benzo(a)pyrene	260	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Benzo(b)fluoranthene	367	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Benzo(g,h,i)perylene	239	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Benzo(k)fluoranthene	34.8	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Beryllium	0.56	-		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Cadmium	0.104	U		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Carbon Tetrachloride	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Cesium-137	0.052	U		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Chromium	17	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Chrysene	189	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Dibenzo(a,h)anthracene	34.8	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Dieldrin	1.4	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Ethylbenzene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Fluoranthene	323	J		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Indeno(1,2,3-cd)pyrene	198	-		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Lead	10.3	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Mercury	0.022	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Methylene chloride	5.7	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Molybdenum	0.84	U		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Phenanthrene	161	J		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Pyrene	273	J		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Radium-226	1.04793	-		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Radium-228	0.981	-		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Selenium	3.12	J		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Silver	1.4	-		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Technetium-99	1.42	U		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Tetrachloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Thorium-228	0.978	-		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Thorium-232	0.981	-		pCi/g
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Toluene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Trichloroethene	1.1	U		ug/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^RMPS	Uranium, Total	14.4	-		mg/kg
A5A-PC09	A5A-PC09-16	A5A-PC09-16^L	Xylenes, Total	1.1	U		ug/kg
A5WPL-PC01	A5WPL-PC01-1	A5WPL-PC01-1^R	Radium-226	1.1	J		pCi/g
A5WPL-PC01	A5WPL-PC01-1	A5WPL-PC01-1^R	Radium-228	0.854	J		pCi/g
A5WPL-PC01	A5WPL-PC01-1	A5WPL-PC01-1^R	Thorium-228	0.87	-		pCi/g
A5WPL-PC01	A5WPL-PC01-1	A5WPL-PC01-1^R	Thorium-232	0.854	J		pCi/g
A5WPL-PC01	A5WPL-PC01-1	A5WPL-PC01-1^R	Uranium, Total	8.72	-		mg/kg
A5WPL-PC01	A5WPL-PC01-2	A5WPL-PC01-2^R	Radium-226	1.17	J		pCi/g
A5WPL-PC01	A5WPL-PC01-2	A5WPL-PC01-2^R	Radium-228	0.973	J		pCi/g
A5WPL-PC01	A5WPL-PC01-2	A5WPL-PC01-2^R	Thorium-228	1.03	-		pCi/g
A5WPL-PC01	A5WPL-PC01-2	A5WPL-PC01-2^R	Thorium-232	0.973	J		pCi/g
A5WPL-PC01	A5WPL-PC01-2	A5WPL-PC01-2^R	Uranium, Total	13.6	-		mg/kg
A5WPL-PC01	A5WPL-PC01-3	A5WPL-PC01-3^R	Radium-226	1.12	J		pCi/g
A5WPL-PC01	A5WPL-PC01-3	A5WPL-PC01-3^R	Radium-228	0.815	J		pCi/g
A5WPL-PC01	A5WPL-PC01-3	A5WPL-PC01-3^R	Thorium-228	0.849	-		pCi/g
A5WPL-PC01	A5WPL-PC01-3	A5WPL-PC01-3^R	Thorium-232	0.815	J		pCi/g
A5WPL-PC01	A5WPL-PC01-3	A5WPL-PC01-3^R	Uranium, Total	7.89	-		mg/kg
A5WPL-PC01	A5WPL-PC01-4	A5WPL-PC01-4^R	Radium-226	0.908	J		pCi/g
A5WPL-PC01	A5WPL-PC01-4	A5WPL-PC01-4^R	Radium-228	0.614	J		pCi/g
A5WPL-PC01	A5WPL-PC01-4	A5WPL-PC01-4^R	Thorium-228	0.646	-		pCi/g
WPL-PC01	A5WPL-PC01-4	A5WPL-PC01-4^R	Thorium-232	0.614	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5WPL-PC01	A5WPL-PC01-4	A5WPL-PC01-4^R	Uranium, Total	3.47	J		mg/kg
A5WPL-PC01	A5WPL-PC01-5	A5WPL-PC01-5^R	Radium-226	0.871	J		pCi/g
A5WPL-PC01	A5WPL-PC01-5	A5WPL-PC01-5^R	Radium-228	0.506	J		pCi/g
A5WPL-PC01	A5WPL-PC01-5	A5WPL-PC01-5^R	Thorium-228	0.526	-		pCi/g
A5WPL-PC01	A5WPL-PC01-5	A5WPL-PC01-5^R	Thorium-232	0.506	J		pCi/g
A5WPL-PC01	A5WPL-PC01-5	A5WPL-PC01-5^R	Uranium, Total	4.28	J		mg/kg
A5WPL-PC01	A5WPL-PC01-6	A5WPL-PC01-6^R	Radium-226	0.913	J		pCi/g
A5WPL-PC01	A5WPL-PC01-6	A5WPL-PC01-6^R	Radium-228	0.765	J		pCi/g
A5WPL-PC01	A5WPL-PC01-6	A5WPL-PC01-6^R	Thorium-228	0.827	-		pCi/g
A5WPL-PC01	A5WPL-PC01-6	A5WPL-PC01-6^R	Thorium-232	0.765	J		pCi/g
A5WPL-PC01	A5WPL-PC01-6	A5WPL-PC01-6^R	Uranium, Total	5.49	-		mg/kg
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R	Radium-226	1.11	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R-D	Radium-226	0.979	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R	Radium-228	0.926	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R-D	Radium-228	0.749	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R	Thorium-228	0.913	-		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R-D	Thorium-228	0.803	-		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R	Thorium-232	0.926	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R-D	Thorium-232	0.749	J		pCi/g
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R	Uranium, Total	3.47	U		mg/kg
A5WPL-PC01	A5WPL-PC01-7	A5WPL-PC01-7^R-D	Uranium, Total	3.78	J		mg/kg
A5WPL-PC01	A5WPL-PC01-8	A5WPL-PC01-8^R	Radium-226	1.08	J		pCi/g
A5WPL-PC01	A5WPL-PC01-8	A5WPL-PC01-8^R	Radium-228	0.809	J		pCi/g
A5WPL-PC01	A5WPL-PC01-8	A5WPL-PC01-8^R	Thorium-228	0.833	-		pCi/g
A5WPL-PC01	A5WPL-PC01-8	A5WPL-PC01-8^R	Thorium-232	0.809	J		pCi/g
A5WPL-PC01	A5WPL-PC01-8	A5WPL-PC01-8^R	Uranium, Total	3.12	J		mg/kg
A5WPL-PC01	A5WPL-PC01-9	A5WPL-PC01-9^R	Radium-226	1.04	J		pCi/g
A5WPL-PC01	A5WPL-PC01-9	A5WPL-PC01-9^R	Radium-228	0.777	J		pCi/g
A5WPL-PC01	A5WPL-PC01-9	A5WPL-PC01-9^R	Thorium-228	0.794	-		pCi/g
A5WPL-PC01	A5WPL-PC01-9	A5WPL-PC01-9^R	Thorium-232	0.777	J		pCi/g
A5WPL-PC01	A5WPL-PC01-9	A5WPL-PC01-9^R	Uranium, Total	3.75	J		mg/kg
A5WPL-PC01	A5WPL-PC01-10	A5WPL-PC01-10^R	Radium-226	1.14	J		pCi/g
A5WPL-PC01	A5WPL-PC01-10	A5WPL-PC01-10^R	Radium-228	0.79	J		pCi/g
A5WPL-PC01	A5WPL-PC01-10	A5WPL-PC01-10^R	Thorium-228	0.797	-		pCi/g
A5WPL-PC01	A5WPL-PC01-10	A5WPL-PC01-10^R	Thorium-232	0.79	J		pCi/g
A5WPL-PC01	A5WPL-PC01-10	A5WPL-PC01-10^R	Uranium, Total	3.28	U		mg/kg
A5WPL-PC01	A5WPL-PC01-11	A5WPL-PC01-11^R	Radium-226	1.21	J		pCi/g
A5WPL-PC01	A5WPL-PC01-11	A5WPL-PC01-11^R	Radium-228	0.907	J		pCi/g
A5WPL-PC01	A5WPL-PC01-11	A5WPL-PC01-11^R	Thorium-228	0.894	-		pCi/g
A5WPL-PC01	A5WPL-PC01-11	A5WPL-PC01-11^R	Thorium-232	0.907	J		pCi/g
A5WPL-PC01	A5WPL-PC01-11	A5WPL-PC01-11^R	Uranium, Total	7.9	-		mg/kg
A5WPL-PC01	A5WPL-PC01-12	A5WPL-PC01-12^R	Radium-226	1.12	J		pCi/g
A5WPL-PC01	A5WPL-PC01-12	A5WPL-PC01-12^R	Radium-228	0.974	J		pCi/g
A5WPL-PC01	A5WPL-PC01-12	A5WPL-PC01-12^R	Thorium-228	1	-		pCi/g
A5WPL-PC01	A5WPL-PC01-12	A5WPL-PC01-12^R	Thorium-232	0.974	J		pCi/g
A5WPL-PC01	A5WPL-PC01-12	A5WPL-PC01-12^R	Uranium, Total	7	-		mg/kg
A5WPL-PC01	A5WPL-PC01-13	A5WPL-PC01-13^R	Radium-226	0.954	J		pCi/g
A5WPL-PC01	A5WPL-PC01-13	A5WPL-PC01-13^R	Radium-228	0.781	J		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	QA	Units
A5WPL-PC01	A5WPL-PC01-13	A5WPL-PC01-13^R	Thorium-228	0.782	-	pCi/g
A5WPL-PC01	A5WPL-PC01-13	A5WPL-PC01-13^R	Thorium-232	0.781	J	pCi/g
A5WPL-PC01	A5WPL-PC01-13	A5WPL-PC01-13^R	Uranium, Total	4.96	J	mg/kg
A5WPL-PC01	A5WPL-PC01-14	A5WPL-PC01-14^R	Radium-226	1.16	J	pCi/g
A5WPL-PC01	A5WPL-PC01-14	A5WPL-PC01-14^R	Radium-228	0.893	J	pCi/g
A5WPL-PC01	A5WPL-PC01-14	A5WPL-PC01-14^R	Thorium-228	0.865	-	pCi/g
A5WPL-PC01	A5WPL-PC01-14	A5WPL-PC01-14^R	Thorium-232	0.893	J	pCi/g
A5WPL-PC01	A5WPL-PC01-14	A5WPL-PC01-14^R	Uranium, Total	5.87	-	mg/kg
A5WPL-PC01	A5WPL-PC01-15	A5WPL-PC01-15^R	Radium-226	0.99	J	pCi/g
A5WPL-PC01	A5WPL-PC01-15	A5WPL-PC01-15^R	Radium-228	0.788	J	pCi/g
A5WPL-PC01	A5WPL-PC01-15	A5WPL-PC01-15^R	Thorium-228	0.794	-	pCi/g
A5WPL-PC01	A5WPL-PC01-15	A5WPL-PC01-15^R	Thorium-232	0.788	J	pCi/g
A5WPL-PC01	A5WPL-PC01-15	A5WPL-PC01-15^R	Uranium, Total	7.4	-	mg/kg
A5WPL-PC01	A5WPL-PC01-16	A5WPL-PC01-16^R	Radium-226	0.944	J	pCi/g
A5WPL-PC01	A5WPL-PC01-16	A5WPL-PC01-16^R	Radium-228	0.82	J	pCi/g
A5WPL-PC01	A5WPL-PC01-16	A5WPL-PC01-16^R	Thorium-228	0.84	-	pCi/g
A5WPL-PC01	A5WPL-PC01-16	A5WPL-PC01-16^R	Thorium-232	0.82	J	pCi/g
A5WPL-PC01	A5WPL-PC01-16	A5WPL-PC01-16^R	Uranium, Total	3.55	J	mg/kg
A5WPL-PC02	A5WPL-PC02-1	A5WPL-PC02-1^R	Radium-226	1.21	J	pCi/g
A5WPL-PC02	A5WPL-PC02-1	A5WPL-PC02-1^R	Radium-228	1.01	J	pCi/g
A5WPL-PC02	A5WPL-PC02-1	A5WPL-PC02-1^R	Thorium-228	1.01	J	pCi/g
A5WPL-PC02	A5WPL-PC02-1	A5WPL-PC02-1^R	Thorium-232	1.01	J	pCi/g
A5WPL-PC02	A5WPL-PC02-1	A5WPL-PC02-1^R	Uranium, Total	2.72	J	mg/kg
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R	Radium-226	1.47	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R-D	Radium-226	1.76	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R	Radium-228	1.11	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R-D	Radium-228	1.41	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R	Thorium-228	1.07	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R-D	Thorium-228	1.47	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R	Thorium-232	1.11	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R-D	Thorium-232	1.41	J	pCi/g
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R	Uranium, Total	4.01	-	mg/kg
A5WPL-PC02	A5WPL-PC02-2	A5WPL-PC02-2^R-D	Uranium, Total	6.63	-	mg/kg
A5WPL-PC02	A5WPL-PC02-3	A5WPL-PC02-3^R	Radium-226	1.14	J	pCi/g
A5WPL-PC02	A5WPL-PC02-3	A5WPL-PC02-3^R	Radium-228	0.911	J	pCi/g
A5WPL-PC02	A5WPL-PC02-3	A5WPL-PC02-3^R	Thorium-228	0.942	J	pCi/g
A5WPL-PC02	A5WPL-PC02-3	A5WPL-PC02-3^R	Thorium-232	0.911	J	pCi/g
A5WPL-PC02	A5WPL-PC02-3	A5WPL-PC02-3^R	Uranium, Total	3.14	-	mg/kg
A5WPL-PC02	A5WPL-PC02-4	A5WPL-PC02-4^R	Radium-226	1.31	J	pCi/g
A5WPL-PC02	A5WPL-PC02-4	A5WPL-PC02-4^R	Radium-228	0.916	J	pCi/g
A5WPL-PC02	A5WPL-PC02-4	A5WPL-PC02-4^R	Thorium-228	0.915	J	pCi/g
A5WPL-PC02	A5WPL-PC02-4	A5WPL-PC02-4^R	Thorium-232	0.916	J	pCi/g
A5WPL-PC02	A5WPL-PC02-4	A5WPL-PC02-4^R	Uranium, Total	4.22	-	mg/kg
A5WPL-PC02	A5WPL-PC02-5	A5WPL-PC02-5^R	Radium-226	1.21	J	pCi/g
A5WPL-PC02	A5WPL-PC02-5	A5WPL-PC02-5^R	Radium-228	0.875	J	pCi/g
A5WPL-PC02	A5WPL-PC02-5	A5WPL-PC02-5^R	Thorium-228	0.876	J	pCi/g
A5WPL-PC02	A5WPL-PC02-5	A5WPL-PC02-5^R	Thorium-232	0.875	J	pCi/g
A5WPL-PC02	A5WPL-PC02-5	A5WPL-PC02-5^R	Uranium, Total	3.71	-	mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

GU	Boring	SampleID	Parameter	Val:Res	VQ	Units
A5WPL-PC02	A5WPL-PC02-6	A5WPL-PC02-6^R	Radium-226	0.889	J	pCi/g
A5WPL-PC02	A5WPL-PC02-6	A5WPL-PC02-6^R	Radium-228	0.747	J	pCi/g
A5WPL-PC02	A5WPL-PC02-6	A5WPL-PC02-6^R	Thorium-228	0.73	J	pCi/g
A5WPL-PC02	A5WPL-PC02-6	A5WPL-PC02-6^R	Thorium-232	0.747	J	pCi/g
A5WPL-PC02	A5WPL-PC02-6	A5WPL-PC02-6^R	Uranium, Total	3.74	U	mg/kg
A5WPL-PC02	A5WPL-PC02-7	A5WPL-PC02-7^R	Radium-226	1.17	J	pCi/g
A5WPL-PC02	A5WPL-PC02-7	A5WPL-PC02-7^R	Radium-228	0.75	J	pCi/g
A5WPL-PC02	A5WPL-PC02-7	A5WPL-PC02-7^R	Thorium-228	0.741	J	pCi/g
A5WPL-PC02	A5WPL-PC02-7	A5WPL-PC02-7^R	Thorium-232	0.75	J	pCi/g
A5WPL-PC02	A5WPL-PC02-7	A5WPL-PC02-7^R	Uranium, Total	3.73	U	mg/kg
A5WPL-PC02	A5WPL-PC02-8	A5WPL-PC02-8^R	Radium-226	0.956	J	pCi/g
A5WPL-PC02	A5WPL-PC02-8	A5WPL-PC02-8^R	Radium-228	0.675	J	pCi/g
A5WPL-PC02	A5WPL-PC02-8	A5WPL-PC02-8^R	Thorium-228	0.689	J	pCi/g
A5WPL-PC02	A5WPL-PC02-8	A5WPL-PC02-8^R	Thorium-232	0.675	J	pCi/g
A5WPL-PC02	A5WPL-PC02-8	A5WPL-PC02-8^R	Uranium, Total	3.9	J	mg/kg
A5WPL-PC02	A5WPL-PC02-9	A5WPL-PC02-9^R	Radium-226	1.17	J	pCi/g
A5WPL-PC02	A5WPL-PC02-9	A5WPL-PC02-9^R	Radium-228	0.894	J	pCi/g
A5WPL-PC02	A5WPL-PC02-9	A5WPL-PC02-9^R	Thorium-228	0.866	J	pCi/g
A5WPL-PC02	A5WPL-PC02-9	A5WPL-PC02-9^R	Thorium-232	0.894	J	pCi/g
A5WPL-PC02	A5WPL-PC02-9	A5WPL-PC02-9^R	Uranium, Total	3.9	U	mg/kg
A5WPL-PC02	A5WPL-PC02-10	A5WPL-PC02-10^R	Radium-226	1.04	J	pCi/g
A5WPL-PC02	A5WPL-PC02-10	A5WPL-PC02-10^R	Radium-228	0.845	J	pCi/g
A5WPL-PC02	A5WPL-PC02-10	A5WPL-PC02-10^R	Thorium-228	0.864	J	pCi/g
A5WPL-PC02	A5WPL-PC02-10	A5WPL-PC02-10^R	Thorium-232	0.845	J	pCi/g
A5WPL-PC02	A5WPL-PC02-10	A5WPL-PC02-10^R	Uranium, Total	3.41	U	mg/kg
A5WPL-PC02	A5WPL-PC02-11	A5WPL-PC02-11^R	Radium-226	0.935	J	pCi/g
A5WPL-PC02	A5WPL-PC02-11	A5WPL-PC02-11^R	Radium-228	0.802	J	pCi/g
A5WPL-PC02	A5WPL-PC02-11	A5WPL-PC02-11^R	Thorium-228	0.838	J	pCi/g
A5WPL-PC02	A5WPL-PC02-11	A5WPL-PC02-11^R	Thorium-232	0.802	J	pCi/g
A5WPL-PC02	A5WPL-PC02-11	A5WPL-PC02-11^R	Uranium, Total	3.3	U	mg/kg
A5WPL-PC02	A5WPL-PC02-12	A5WPL-PC02-12^R	Radium-226	1.1	J	pCi/g
A5WPL-PC02	A5WPL-PC02-12	A5WPL-PC02-12^R	Radium-228	0.867	J	pCi/g
A5WPL-PC02	A5WPL-PC02-12	A5WPL-PC02-12^R	Thorium-228	0.861	J	pCi/g
A5WPL-PC02	A5WPL-PC02-12	A5WPL-PC02-12^R	Thorium-232	0.867	J	pCi/g
A5WPL-PC02	A5WPL-PC02-12	A5WPL-PC02-12^R	Uranium, Total	6.5	-	mg/kg
A5WPL-PC02	A5WPL-PC02-13	A5WPL-PC02-13^R	Radium-226	1.01	J	pCi/g
A5WPL-PC02	A5WPL-PC02-13	A5WPL-PC02-13^R	Radium-228	0.722	J	pCi/g
A5WPL-PC02	A5WPL-PC02-13	A5WPL-PC02-13^R	Thorium-228	0.685	J	pCi/g
A5WPL-PC02	A5WPL-PC02-13	A5WPL-PC02-13^R	Thorium-232	0.722	J	pCi/g
A5WPL-PC02	A5WPL-PC02-13	A5WPL-PC02-13^R	Uranium, Total	6.48	-	mg/kg
A5WPL-PC02	A5WPL-PC02-14	A5WPL-PC02-14^R	Radium-226	0.915	J	pCi/g
A5WPL-PC02	A5WPL-PC02-14	A5WPL-PC02-14^R	Radium-228	0.693	J	pCi/g
A5WPL-PC02	A5WPL-PC02-14	A5WPL-PC02-14^R	Thorium-228	0.721	J	pCi/g
A5WPL-PC02	A5WPL-PC02-14	A5WPL-PC02-14^R	Thorium-232	0.693	J	pCi/g
A5WPL-PC02	A5WPL-PC02-14	A5WPL-PC02-14^R	Uranium, Total	4.47	J	mg/kg
A5WPL-PC02	A5WPL-PC02-15	A5WPL-PC02-15^R	Radium-226	1.09	J	pCi/g
A5WPL-PC02	A5WPL-PC02-15	A5WPL-PC02-15^R	Radium-228	0.805	J	pCi/g
A5WPL-PC02	A5WPL-PC02-15	A5WPL-PC02-15^R	Thorium-228	0.811	J	pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	VQ	Units
A5WPL-PC02	A5WPL-PC02-15	A5WPL-PC02-15^R	Thorium-232	0.805	J	pCi/g
A5WPL-PC02	A5WPL-PC02-15	A5WPL-PC02-15^R	Uranium, Total	3.79	J	mg/kg
A5WPL-PC02	A5WPL-PC02-16	A5WPL-PC02-16^R	Radium-226	1.14	J	pCi/g
5WPL-PC02	A5WPL-PC02-16	A5WPL-PC02-16^R	Radium-228	0.806	J	pCi/g
A5WPL-PC02	A5WPL-PC02-16	A5WPL-PC02-16^R	Thorium-228	0.811	J	pCi/g
A5WPL-PC02	A5WPL-PC02-16	A5WPL-PC02-16^R	Thorium-232	0.806	J	pCi/g
A5WPL-PC02	A5WPL-PC02-16	A5WPL-PC02-16^R	Uranium, Total	6.9	-	mg/kg
A5WPL-PC03	A5WPL-PC03-1	A5WPL-PC03-1^R	Radium-226	1.19	-	pCi/g
A5WPL-PC03	A5WPL-PC03-1	A5WPL-PC03-1^R	Radium-228	0.832	-	pCi/g
A5WPL-PC03	A5WPL-PC03-1	A5WPL-PC03-1^R	Thorium-228	0.843	-	pCi/g
A5WPL-PC03	A5WPL-PC03-1	A5WPL-PC03-1^R	Thorium-232	0.832	-	pCi/g
A5WPL-PC03	A5WPL-PC03-1	A5WPL-PC03-1^R	Uranium, Total	4.66	-	mg/kg
A5WPL-PC03	A5WPL-PC03-2	A5WPL-PC03-2^R	Radium-226	1.16	-	pCi/g
A5WPL-PC03	A5WPL-PC03-2	A5WPL-PC03-2^R	Radium-228	0.918	-	pCi/g
A5WPL-PC03	A5WPL-PC03-2	A5WPL-PC03-2^R	Thorium-228	0.906	-	pCi/g
A5WPL-PC03	A5WPL-PC03-2	A5WPL-PC03-2^R	Thorium-232	0.918	-	pCi/g
A5WPL-PC03	A5WPL-PC03-2	A5WPL-PC03-2^R	Uranium, Total	6.8	-	mg/kg
A5WPL-PC03	A5WPL-PC03-3	A5WPL-PC03-3^R	Radium-226	1.48	-	pCi/g
A5WPL-PC03	A5WPL-PC03-3	A5WPL-PC03-3^R	Radium-228	1.34	-	pCi/g
A5WPL-PC03	A5WPL-PC03-3	A5WPL-PC03-3^R	Thorium-228	1.38	-	pCi/g
A5WPL-PC03	A5WPL-PC03-3	A5WPL-PC03-3^R	Thorium-232	1.34	-	pCi/g
A5WPL-PC03	A5WPL-PC03-3	A5WPL-PC03-3^R	Uranium, Total	6.35	-	mg/kg
A5WPL-PC03	A5WPL-PC03-4	A5WPL-PC03-4^R	Radium-226	1.35	-	pCi/g
A5WPL-PC03	A5WPL-PC03-4	A5WPL-PC03-4^R	Radium-228	1.19	-	pCi/g
A5WPL-PC03	A5WPL-PC03-4	A5WPL-PC03-4^R	Thorium-228	1.2	-	pCi/g
WPL-PC03	A5WPL-PC03-4	A5WPL-PC03-4^R	Thorium-232	1.19	-	pCi/g
A5WPL-PC03	A5WPL-PC03-4	A5WPL-PC03-4^R	Uranium, Total	10.9	-	mg/kg
A5WPL-PC03	A5WPL-PC03-5	A5WPL-PC03-5^R	Radium-226	1.03	-	pCi/g
A5WPL-PC03	A5WPL-PC03-5	A5WPL-PC03-5^R	Radium-228	0.766	-	pCi/g
A5WPL-PC03	A5WPL-PC03-5	A5WPL-PC03-5^R	Thorium-228	0.765	-	pCi/g
A5WPL-PC03	A5WPL-PC03-5	A5WPL-PC03-5^R	Thorium-232	0.766	-	pCi/g
A5WPL-PC03	A5WPL-PC03-5	A5WPL-PC03-5^R	Uranium, Total	5.46	-	mg/kg
A5WPL-PC03	A5WPL-PC03-6	A5WPL-PC03-6^R	Radium-226	1.51	-	pCi/g
A5WPL-PC03	A5WPL-PC03-6	A5WPL-PC03-6^R	Radium-228	1.27	-	pCi/g
A5WPL-PC03	A5WPL-PC03-6	A5WPL-PC03-6^R	Thorium-228	1.3	-	pCi/g
A5WPL-PC03	A5WPL-PC03-6	A5WPL-PC03-6^R	Thorium-232	1.27	-	pCi/g
A5WPL-PC03	A5WPL-PC03-6	A5WPL-PC03-6^R	Uranium, Total	16.1	-	mg/kg
A5WPL-PC03	A5WPL-PC03-7	A5WPL-PC03-7^R	Radium-226	1.07	-	pCi/g
A5WPL-PC03	A5WPL-PC03-7	A5WPL-PC03-7^R	Radium-228	0.751	-	pCi/g
A5WPL-PC03	A5WPL-PC03-7	A5WPL-PC03-7^R	Thorium-228	0.758	-	pCi/g
A5WPL-PC03	A5WPL-PC03-7	A5WPL-PC03-7^R	Thorium-232	0.751	-	pCi/g
A5WPL-PC03	A5WPL-PC03-7	A5WPL-PC03-7^R	Uranium, Total	9.79	-	mg/kg
A5WPL-PC03	A5WPL-PC03-8	A5WPL-PC03-8^R	Radium-226	1.28	-	pCi/g
A5WPL-PC03	A5WPL-PC03-8	A5WPL-PC03-8^R	Radium-228	1.01	-	pCi/g
A5WPL-PC03	A5WPL-PC03-8	A5WPL-PC03-8^R	Thorium-228	1.02	-	pCi/g
A5WPL-PC03	A5WPL-PC03-8	A5WPL-PC03-8^R	Thorium-232	1.01	-	pCi/g
A5WPL-PC03	A5WPL-PC03-8	A5WPL-PC03-8^R	Uranium, Total	16.5	-	mg/kg
WPL-PC03	A5WPL-PC03-9	A5WPL-PC03-9^R	Radium-226	1.31	-	pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC03	A5WPL-PC03-9	A5WPL-PC03-9^R	Radium-228	1.08	-		pCi/g
A5WPL-PC03	A5WPL-PC03-9	A5WPL-PC03-9^R	Thorium-228	1.07	-		pCi/g
A5WPL-PC03	A5WPL-PC03-9	A5WPL-PC03-9^R	Thorium-232	1.08	-		pCi/g
A5WPL-PC03	A5WPL-PC03-9	A5WPL-PC03-9^R	Uranium, Total	7.77	-		mg/kg
A5WPL-PC03	A5WPL-PC03-10	A5WPL-PC03-10^R	Radium-226	1.32	-		pCi/g
A5WPL-PC03	A5WPL-PC03-10	A5WPL-PC03-10^R	Radium-228	0.975	-		pCi/g
A5WPL-PC03	A5WPL-PC03-10	A5WPL-PC03-10^R	Thorium-228	0.975	-		pCi/g
A5WPL-PC03	A5WPL-PC03-10	A5WPL-PC03-10^R	Thorium-232	0.975	-		pCi/g
A5WPL-PC03	A5WPL-PC03-10	A5WPL-PC03-10^R	Uranium, Total	4.33	-		mg/kg
A5WPL-PC03	A5WPL-PC03-11	A5WPL-PC03-11^R	Radium-226	1.07	-		pCi/g
A5WPL-PC03	A5WPL-PC03-11	A5WPL-PC03-11^R	Radium-228	0.81	-		pCi/g
A5WPL-PC03	A5WPL-PC03-11	A5WPL-PC03-11^R	Thorium-228	0.809	-		pCi/g
A5WPL-PC03	A5WPL-PC03-11	A5WPL-PC03-11^R	Thorium-232	0.81	-		pCi/g
A5WPL-PC03	A5WPL-PC03-11	A5WPL-PC03-11^R	Uranium, Total	5.68	-		mg/kg
A5WPL-PC03	A5WPL-PC03-12	A5WPL-PC03-12^R	Radium-226	1.32	-		pCi/g
A5WPL-PC03	A5WPL-PC03-12	A5WPL-PC03-12^R	Radium-228	0.966	-		pCi/g
A5WPL-PC03	A5WPL-PC03-12	A5WPL-PC03-12^R	Thorium-228	0.998	-		pCi/g
A5WPL-PC03	A5WPL-PC03-12	A5WPL-PC03-12^R	Thorium-232	0.966	-		pCi/g
A5WPL-PC03	A5WPL-PC03-12	A5WPL-PC03-12^R	Uranium, Total	5.06	J		mg/kg
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R	Radium-226	1.19	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R-D	Radium-226	1.29	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R	Radium-228	1.02	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R-D	Radium-228	1.04	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R	Thorium-228	1.04	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R-D	Thorium-228	1.04	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R	Thorium-232	1.02	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R-D	Thorium-232	1.04	-		pCi/g
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R	Uranium, Total	4.54	J		mg/kg
A5WPL-PC03	A5WPL-PC03-13	A5WPL-PC03-13^R-D	Uranium, Total	3.91	U		mg/kg
A5WPL-PC03	A5WPL-PC03-14	A5WPL-PC03-14^R	Radium-226	1.3	-		pCi/g
A5WPL-PC03	A5WPL-PC03-14	A5WPL-PC03-14^R	Radium-228	1.03	-		pCi/g
A5WPL-PC03	A5WPL-PC03-14	A5WPL-PC03-14^R	Thorium-228	1.05	-		pCi/g
A5WPL-PC03	A5WPL-PC03-14	A5WPL-PC03-14^R	Thorium-232	1.03	-		pCi/g
A5WPL-PC03	A5WPL-PC03-14	A5WPL-PC03-14^R	Uranium, Total	6.4	-		mg/kg
A5WPL-PC03	A5WPL-PC03-15	A5WPL-PC03-15^R	Radium-226	1.31	-		pCi/g
A5WPL-PC03	A5WPL-PC03-15	A5WPL-PC03-15^R	Radium-228	1.02	-		pCi/g
A5WPL-PC03	A5WPL-PC03-15	A5WPL-PC03-15^R	Thorium-228	1.03	-		pCi/g
A5WPL-PC03	A5WPL-PC03-15	A5WPL-PC03-15^R	Thorium-232	1.02	-		pCi/g
A5WPL-PC03	A5WPL-PC03-15	A5WPL-PC03-15^R	Uranium, Total	5.7	J		mg/kg
A5WPL-PC03	A5WPL-PC03-16	A5WPL-PC03-16^R	Radium-226	1.1	-		pCi/g
A5WPL-PC03	A5WPL-PC03-16	A5WPL-PC03-16^R	Radium-228	0.901	-		pCi/g
A5WPL-PC03	A5WPL-PC03-16	A5WPL-PC03-16^R	Thorium-228	0.925	-		pCi/g
A5WPL-PC03	A5WPL-PC03-16	A5WPL-PC03-16^R	Thorium-232	0.901	-		pCi/g
A5WPL-PC03	A5WPL-PC03-16	A5WPL-PC03-16^R	Uranium, Total	5.36	-		mg/kg
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Arsenic	8.15	-		mg/kg
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Radium-226	1.17	-		pCi/g
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Radium-228	0.969	-		pCi/g
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Thorium-228	0.984	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Thorium-232	0.969	-		pCi/g
A5WPL-PC04	A5WPL-PC04-1	A5WPL-PC04-1^RM	Uranium, Total	7.13	-		mg/kg
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Arsenic	4.63	-		mg/kg
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Radium-226	1.34	-		pCi/g
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Radium-228	1.06	-		pCi/g
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Thorium-228	1.08	-		pCi/g
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Thorium-232	1.06	-		pCi/g
A5WPL-PC04	A5WPL-PC04-2	A5WPL-PC04-2^RM	Uranium, Total	3.94	U		mg/kg
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Arsenic	5.39	-		mg/kg
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Radium-226	1.23	-		pCi/g
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Radium-228	0.849	-		pCi/g
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Thorium-228	0.9	-		pCi/g
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Thorium-232	0.849	-		pCi/g
A5WPL-PC04	A5WPL-PC04-3	A5WPL-PC04-3^RM	Uranium, Total	11.7	-		mg/kg
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Arsenic	4.31	-		mg/kg
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Radium-226	1.6	-		pCi/g
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Radium-228	1.28	-		pCi/g
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Thorium-228	1.33	-		pCi/g
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Thorium-232	1.28	-		pCi/g
A5WPL-PC04	A5WPL-PC04-4	A5WPL-PC04-4^RM	Uranium, Total	4.07	U		mg/kg
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Arsenic	6.07	-		mg/kg
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Radium-226	1.27	-		pCi/g
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Radium-228	1.06	-		pCi/g
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Thorium-228	1.14	-		pCi/g
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Thorium-232	1.06	-		pCi/g
A5WPL-PC04	A5WPL-PC04-5	A5WPL-PC04-5^RM	Uranium, Total	4.12	J		mg/kg
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Arsenic	6.37	-		mg/kg
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Radium-226	1.19	-		pCi/g
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Radium-228	0.905	-		pCi/g
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Thorium-228	0.969	-		pCi/g
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Thorium-232	0.905	-		pCi/g
A5WPL-PC04	A5WPL-PC04-6	A5WPL-PC04-6^RM	Uranium, Total	7.78	-		mg/kg
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Arsenic	7.1	-		mg/kg
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Radium-226	1.65	-		pCi/g
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Radium-228	1.34	-		pCi/g
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Thorium-228	1.33	-		pCi/g
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Thorium-232	1.34	-		pCi/g
A5WPL-PC04	A5WPL-PC04-7	A5WPL-PC04-7^RM	Uranium, Total	12.3	-		mg/kg
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Arsenic	7.73	-		mg/kg
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Radium-226	1.22	-		pCi/g
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Radium-228	1.05	-		pCi/g
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Thorium-228	1.08	-		pCi/g
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Thorium-232	1.05	-		pCi/g
A5WPL-PC04	A5WPL-PC04-8	A5WPL-PC04-8^RM	Uranium, Total	3.2	U		mg/kg
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Arsenic	5.77	-		mg/kg
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Arsenic	5.2	-		mg/kg
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Radium-226	1.53	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Radium-226	1.58	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Radium-228	1.23	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Radium-228	1.14	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Thorium-228	1.26	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Thorium-228	1.19	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Thorium-232	1.23	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Thorium-232	1.14	-		pCi/g
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM	Uranium, Total	3.98	U		mg/kg
A5WPL-PC04	A5WPL-PC04-9	A5WPL-PC04-9^RM-D	Uranium, Total	6.96	-		mg/kg
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Arsenic	6.82	-		mg/kg
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Radium-226	1.55	-		pCi/g
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Radium-228	1.26	-		pCi/g
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Thorium-228	1.32	-		pCi/g
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Thorium-232	1.26	-		pCi/g
A5WPL-PC04	A5WPL-PC04-10	A5WPL-PC04-10^RM	Uranium, Total	4.21	J		mg/kg
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Arsenic	3.9	-		mg/kg
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Radium-226	1.17	-		pCi/g
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Radium-228	0.862	-		pCi/g
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Thorium-228	0.905	-		pCi/g
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Thorium-232	0.862	-		pCi/g
A5WPL-PC04	A5WPL-PC04-11	A5WPL-PC04-11^RM	Uranium, Total	6.37	J		mg/kg
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Arsenic	3	-		mg/kg
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Radium-226	1.32	-		pCi/g
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Radium-228	0.917	-		pCi/g
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Thorium-228	0.908	-		pCi/g
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Thorium-232	0.917	-		pCi/g
A5WPL-PC04	A5WPL-PC04-12	A5WPL-PC04-12^RM	Uranium, Total	3.68	U		mg/kg
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Arsenic	4.48	-		mg/kg
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Radium-226	1.4	-		pCi/g
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Radium-228	1.09	-		pCi/g
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Thorium-228	1.05	-		pCi/g
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Thorium-232	1.09	-		pCi/g
A5WPL-PC04	A5WPL-PC04-13	A5WPL-PC04-13^RM	Uranium, Total	7.39	-		mg/kg
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Arsenic	7	-		mg/kg
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Radium-226	1.28	-		pCi/g
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Radium-228	1.04	-		pCi/g
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Thorium-228	1.04	-		pCi/g
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Thorium-232	1.04	-		pCi/g
A5WPL-PC04	A5WPL-PC04-14	A5WPL-PC04-14^RM	Uranium, Total	3.65	U		mg/kg
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Arsenic	4.16	-		mg/kg
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Radium-226	1.32	-		pCi/g
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Radium-228	1.03	-		pCi/g
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Thorium-228	1.04	-		pCi/g
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Thorium-232	1.03	-		pCi/g
A5WPL-PC04	A5WPL-PC04-15	A5WPL-PC04-15^RM	Uranium, Total	4.68	J		mg/kg
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Arsenic	6.08	-		mg/kg
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Radium-226	1.24	-		pCi/g
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Radium-228	0.951	-		pCi/g
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Thorium-228	1.01	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	UQ	Units
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Thorium-232	0.951	-		pCi/g
A5WPL-PC04	A5WPL-PC04-16	A5WPL-PC04-16^RM	Uranium, Total	9.77	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	4-Methyl-2-pentanone	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Acetone	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Antimony	0.57	J		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Aroclor-1254	7.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Aroclor-1260	3.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Arsenic	6.8	J		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Barium	89.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Benzo(a)anthracene	109	-		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Benzo(a)pyrene	117	-		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Benzo(b)fluoranthene	210	-		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Benzo(g,h,i)perylene	109	-		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Benzo(k)fluoranthene	35	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Beryllium	0.51	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Cadmium	0.51	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Cesium-137	0.049	U		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Chromium	18.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Chrysene	114	-		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Dibenzo(a,h)anthracene	35	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Dieldrin	1.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Fluoranthene	141	J		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Indeno(1,2,3-cd)pyrene	35	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Lead	10.5	J		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Mercury	0.018	J		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Methylene chloride	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Molybdenum	1.4	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Phenanthrene	43.2	J		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Pyrene	167	J		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Radium-226	1.12164	-		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Radium-228	0.842	-		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Selenium	0.628	U		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Silver	0.105	U		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Technetium-99	2.05	U		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Thorium-228	0.845	-		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Thorium-232	0.842	-		pCi/g
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Toluene	2.1	J		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^RMPS	Uranium, Total	10.3	-		mg/kg
A5WPL-PC05	A5WPL-PC05-1	A5WPL-PC05-1^L	Xylenes, Total	3.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	1,1,1-Trichloroethane	1	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	4-Methyl-2-pentanone	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Acetone	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Antimony	0.62	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Aroclor-1254	3.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Aroclor-1260	3.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Arsenic	4.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Barium	53.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Benzo(a)anthracene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Benzo(a)pyrene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Benzo(b)fluoranthene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Benzo(g,h,i)perylene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Benzo(k)fluoranthene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Beryllium	0.35	-		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Cadmium	0.36	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Cesium-137	0.039	U		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Chromium	11.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Chrysene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Dibenzo(a,h)anthracene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Dieldrin	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Fluoranthene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Indeno(1,2,3-cd)pyrene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Lead	6.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Mercury	0.0093	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Methylene chloride	5.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Molybdenum	1.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Phenanthrene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Pyrene	36.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Radium-226	0.767832	-		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Radium-228	0.641	-		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Selenium	0.634	U		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Silver	0.106	U		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Technetium-99	1.99	U		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Thorium-228	0.647	-		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Thorium-232	0.641	-		pCi/g
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Toluene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^RMPS	Uranium, Total	2.44	J		mg/kg
A5WPL-PC05	A5WPL-PC05-2	A5WPL-PC05-2^L	Xylenes, Total	1.2	J		ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	1,1,1-Trichloroethane	0.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	1,1-Dichloroethene	0.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	1,2-Dichloroethane	0.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	4-Methyl-2-pentanone	4.7	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val/Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Acetone	4.7	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Antimony	2.25	UJ	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Aroclor-1254	7.3	J	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Aroclor-1260	3.8	J	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Arsenic	12.3	J	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Barium	98.3	-	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Benzene	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Benzo(a)anthracene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Benzo(a)pyrene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Benzo(b)fluoranthene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Benzo(g,h,i)perylene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Benzo(k)fluoranthene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Beryllium	0.67	-	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Cadmium	0.562	U	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Carbon Tetrachloride	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Cesium-137	0.0474	J	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Chromium	22.8	J	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Chrysene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Dibenzo(a,h)anthracene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Dieldrin	1.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Ethylbenzene	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Fluoranthene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Indeno(1,2,3-cd)pyrene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Lead	12.9	J	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Mercury	0.022	J	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Methylene chloride	4.7	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Molybdenum	1.2	-	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Phenanthrene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Pyrene	37.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Radium-226	0.968955	-	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Radium-228	0.867	-	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Selenium	3.37	U	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Silver	0.112	U	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Technetium-99	1.99	U	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Tetrachloroethene	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Thorium-228	0.852	-	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Thorium-232	0.867	-	pCi/g
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Toluene	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Trichloroethene	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^RMPS	Uranium, Total	8.39	-	mg/kg
A5WPL-PC05	A5WPL-PC05-3	A5WPL-PC05-3^L	Xylenes, Total	0.9	U	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	1,1,1-Trichloroethane	1.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	1,1-Dichloroethene	2.4	J	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	1,2-Dichloroethane	1.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	4-Methyl-2-pentanone	7.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Acetone	7.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Antimony	2.04	UJ	mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Aroclor-1254	3.5	U	ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Aroclor-1260	3.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Arsenic	5.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Barium	94.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Benzene	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Benzo(a)anthracene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Benzo(a)pyrene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Benzo(b)fluoranthene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Benzo(g,h,i)perylene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Benzo(k)fluoranthene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Beryllium	0.74	-		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Cadmium	0.509	U		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Carbon Tetrachloride	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Cesium-137	0.044	U		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Chromium	20.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Chrysene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Dibenzo(a,h)anthracene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Dieldrin	1.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Ethylbenzene	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Fluoranthene	54.4	J		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Indeno(1,2,3-cd)pyrene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Lead	9.1	J		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Mercury	0.018	J		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Methylene chloride	7.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Molybdenum	1.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Phenanthrene	34.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Pyrene	49.2	J		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Radium-226	0.917358	-		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Radium-228	0.835	-		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Selenium	3.05	U		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Silver	0.102	U		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Technetium-99	2.06	U		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Tetrachloroethene	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Thorium-228	0.829	-		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Thorium-232	0.835	-		pCi/g
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Toluene	5.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Trichloroethene	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^RMPS	Uranium, Total	5.49	-		mg/kg
A5WPL-PC05	A5WPL-PC05-5	A5WPL-PC05-5^L	Xylenes, Total	5.7	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	1,1,1-Trichloroethane	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	1,1-Dichloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	1,2-Dichloroethane	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	4-Methyl-2-pentanone	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Acetone	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Antimony	0.44	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Aroclor-1254	3.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Aroclor-1260	3.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Arsenic	6.8	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Barium	66	-		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VO	Units
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Benzene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Benzo(a)anthracene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Benzo(a)pyrene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Benzo(b)fluoranthene	78	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Benzo(g,h,i)perylene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Benzo(k)fluoranthene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Beryllium	0.62	-		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Cadmium	0.27	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Carbon Tetrachloride	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Cesium-137	0.0601	-		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Chromium	14.5	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Chrysene	52.2	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Dibenzo(a,h)anthracene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Dieldrin	1.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Ethylbenzene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Fluoranthene	70.8	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Indeno(1,2,3-cd)pyrene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Lead	8.6	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Mercury	0.018	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Methylene chloride	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Molybdenum	1	-		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Phenanthrene	35.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Pyrene	58.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Radium-226	0.81627	-		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Radium-228	0.818	-		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Selenium	0.636	U		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Silver	0.106	U		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Technetium-99	2.05	U		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Tetrachloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Thorium-228	0.828	-		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Thorium-232	0.818	-		pCi/g
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Toluene	1.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Trichloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^RMPS	Uranium, Total	3.65	J		mg/kg
A5WPL-PC05	A5WPL-PC05-6	A5WPL-PC05-6^L	Xylenes, Total	2	J		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	4-Methyl-2-pentanone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Acetone	5.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Antimony	1	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Aroclor-1254	3.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Aroclor-1260	3.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Arsenic	7.5	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Barium	86.5	-		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Benzo(a)anthracene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Benzo(a)pyrene	38	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VO	Units
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Benzo(b)fluoranthene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Benzo(g,h,i)perylene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Benzo(k)fluoranthene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Beryllium	0.64	-		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Cadmium	0.31	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Cesium-137	0.071	U		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Chromium	19.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Chrysene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Dibenzo(a,h)anthracene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Dieldrin	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Fluoranthene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Indeno(1,2,3-cd)pyrene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Lead	10.8	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Mercury	0.017	J		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Methylene chloride	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Molybdenum	1.4	-		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Phenanthrene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Pyrene	38	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Radium-226	1.04793	-		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Radium-228	0.942	-		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Selenium	0.677	U		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Silver	0.113	U		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Technetium-99	1.9	U		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Thorium-228	0.95	-		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Thorium-232	0.942	-		pCi/g
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Toluene	1.8	J		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^RMPS	Uranium, Total	3.82	-		mg/kg
A5WPL-PC05	A5WPL-PC05-7	A5WPL-PC05-7^L	Xylenes, Total	2.7	J		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	4-Methyl-2-pentanone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Acetone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Antimony	2.43	UJ		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Aroclor-1254	4.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Aroclor-1260	4.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Arsenic	14.3	J		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Barium	103	-		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Benzo(a)anthracene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Benzo(a)pyrene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Benzo(b)fluoranthene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Benzo(g,h,i)perylene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Benzo(k)fluoranthene	40.6	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VO	Units
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Beryllium	0.74	-		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Cadmium	0.606	U		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Cesium-137	0.07	U		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Chromium	25.4	J		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Chrysene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Dibenzo(a,h)anthracene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Dieldrin	1.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Fluoranthene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Indeno(1,2,3-cd)pyrene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Lead	8.8	J		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Mercury	0.016	J		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Methylene chloride	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Molybdenum	2.1	-		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Phenanthrene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Pyrene	40.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Radium-226	0.893139	-		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Radium-228	0.841	-		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Selenium	3.64	U		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Silver	0.121	U		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Technetium-99	2.19	U		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Thorium-228	0.816	-		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Thorium-232	0.841	-		pCi/g
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Toluene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^RMPS	Uranium, Total	3.02	J		mg/kg
A5WPL-PC05	A5WPL-PC05-9	A5WPL-PC05-9^L	Xylenes, Total	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	4-Methyl-2-pentanone	5.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Acetone	7.3	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Antimony	0.62	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Aroclor-1254	4.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Aroclor-1260	4.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Arsenic	6.6	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Barium	71.7	-		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Benzo(a)anthracene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Benzo(a)pyrene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Benzo(b)fluoranthene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Benzo(g,h,i)perylene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Benzo(k)fluoranthene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Beryllium	0.74	-		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Cadmium	0.24	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Carbon Tetrachloride	1	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Cesium-137	0.045	U		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Chromium	15.3	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Chrysene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Dibenzo(a,h)anthracene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Dieldrin	1.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Fluoranthene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Indeno(1,2,3-cd)pyrene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Lead	8.1	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Mercury	0.013	J		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Methylene chloride	5.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Molybdenum	1.5	-		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Phenanthrene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Pyrene	40.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Radium-226	0.798369	-		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Radium-228	0.739	-		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Selenium	0.725	U		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Silver	0.121	U		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Technetium-99	2.02	U		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Thorium-228	0.747	-		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Thorium-232	0.739	-		pCi/g
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Toluene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^RMPS	Uranium, Total	4.97	-		mg/kg
A5WPL-PC05	A5WPL-PC05-10	A5WPL-PC05-10^L	Xylenes, Total	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	1,1,1-Trichloroethane	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	1,1,1-Trichloroethane	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	1,1-Dichloroethene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	1,1-Dichloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	1,2-Dichloroethane	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	1,2-Dichloroethane	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	4-Methyl-2-pentanone	5.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	4-Methyl-2-pentanone	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Acetone	16.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Acetone	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Antimony	2.32	UJ		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Antimony	2.34	UJ		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Aroclor-1254	3.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Aroclor-1254	4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Aroclor-1260	3.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Aroclor-1260	4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Arsenic	6.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Arsenic	7.1	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Barium	91.9	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Barium	93.1	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Benzene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Benzene	1.2	U		ug/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

006314

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Benzo(a)anthracene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Benzo(a)anthracene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Benzo(a)pyrene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Benzo(a)pyrene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Benzo(b)fluoranthene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Benzo(b)fluoranthene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Benzo(g,h,i)perylene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Benzo(g,h,i)perylene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Benzo(k)fluoranthene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Benzo(k)fluoranthene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Beryllium	0.69	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Beryllium	0.61	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Cadmium	0.58	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Cadmium	0.585	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Carbon Tetrachloride	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Carbon Tetrachloride	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Cesium-137	0.082	U		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Cesium-137	0.036	U		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Chromium	21	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Chromium	19.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Chrysene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Chrysene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Dibenzo(a,h)anthracene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Dibenzo(a,h)anthracene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Dieldrin	1.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Dieldrin	1.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Ethylbenzene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Ethylbenzene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Fluoranthene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Fluoranthene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Indeno(1,2,3-cd)pyrene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Indeno(1,2,3-cd)pyrene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Lead	13.6	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Lead	14.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Mercury	0.021	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Mercury	0.021	J		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Methylene chloride	5.4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Methylene chloride	5.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Molybdenum	1.2	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Molybdenum	1.6	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Phenanthrene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Phenanthrene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Pyrene	39.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Pyrene	39.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Radium-226	1.1111	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Radium-226	0.957372	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Radium-228	0.876	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Radium-228	0.822	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Selenium	3.48	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Selenium	3.51	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Silver	0.116	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Silver	0.117	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Technetium-99	1.98	U		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Technetium-99	2.31	U		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Tetrachloroethene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Tetrachloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Thorium-228	0.835	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Thorium-228	0.808	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Thorium-232	0.876	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Thorium-232	0.822	-		pCi/g
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Toluene	1.3	J		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Toluene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Trichloroethene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Trichloroethene	1.2	U		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS	Uranium, Total	2.34	U		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^RMPS-D	Uranium, Total	3.82	-		mg/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L	Xylenes, Total	1.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-12	A5WPL-PC05-12^L-D	Xylenes, Total	1.3	J		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	4-Methyl-2-pentanone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Acetone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Antimony	2.13	UJ		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Aroclor-1254	3.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Aroclor-1260	3.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Arsenic	6.1	J		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Barium	80.6	-		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Benzo(a)anthracene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Benzo(a)pyrene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Benzo(b)fluoranthene	51.5	J		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Benzo(g,h,i)perylene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Benzo(k)fluoranthene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Beryllium	0.6	-		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Cadmium	0.533	U		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Cesium-137	0.043	U		pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Chromium	19.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Chrysene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Dibenzo(a,h)anthracene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Dieldrin	1.5	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Fluoranthene	38.6	J		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Indeno(1,2,3-cd)pyrene	36.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Lead	10.9	J		mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val:Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Mercury	0.016	J	mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Methylene chloride	4.8	U	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Molybdenum	1.5	-	mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Phenanthrene	36.8	U	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Pyrene	41.1	J	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Radium-226	0.939471	-	pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Radium-228	0.898	-	pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Selenium	3.2	U	mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Silver	0.107	U	mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Technetium-99	1.99	U	pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Tetrachloroethene	1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Thorium-228	0.904	-	pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Thorium-232	0.898	-	pCi/g
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Toluene	1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Trichloroethene	1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^RMPS	Uranium, Total	4.62	J	mg/kg
A5WPL-PC05	A5WPL-PC05-13	A5WPL-PC05-13^L	Xylenes, Total	1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	1,1,1-Trichloroethane	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	1,1-Dichloroethene	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	1,2-Dichloroethane	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	4-Methyl-2-pentanone	5.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Acetone	5.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Antimony	2.17	UJ	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Aroclor-1254	10.7	J	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Aroclor-1260	3.6	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Arsenic	7.4	J	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Barium	103	-	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Benzene	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Benzo(a)anthracene	339	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Benzo(a)pyrene	379	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Benzo(b)fluoranthene	691	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Benzo(g,h,i)perylene	278	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Benzo(k)fluoranthene	36.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Beryllium	0.73	-	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Cadmium	0.542	U	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Carbon Tetrachloride	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Cesium-137	0.044	U	pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Chromium	23.4	J	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Chrysene	360	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Dibenzo(a,h)anthracene	36.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Dieldrin	1.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Ethylbenzene	1.1	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Fluoranthene	683	J	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Indeno(1,2,3-cd)pyrene	246	-	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Lead	14.7	J	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Mercury	0.021	J	mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Methylene chloride	5.5	U	ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Molybdenum	1.4	-	mg/kg

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Phenanthrene	290	J		ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Pyrene	486	J		ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Radium-226	1.11111	-		pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Radium-228	1.01	-		pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Selenium	3.25	U		mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Silver	0.108	U		mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Technetium-99	2.1	U		pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Tetrachloroethene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Thorium-228	1.03	-		pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Thorium-232	1.01	-		pCi/g
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Toluene	1.7	J		ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Trichloroethene	1.1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^RMPS	Uranium, Total	6.33	-		mg/kg
A5WPL-PC05	A5WPL-PC05-14	A5WPL-PC05-14^L	Xylenes, Total	3	J		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	1,1,1-Trichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	1,1-Dichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	1,2-Dichloroethane	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	4-Methyl-2-pentanone	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Acetone	7.7	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Antimony	2.38	UJ		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Aroclor-1254	4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Aroclor-1260	4	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Arsenic	9.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Barium	182	-		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Benzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Benzo(a)anthracene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Benzo(a)pyrene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Benzo(b)fluoranthene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Benzo(g,h,i)perylene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Benzo(k)fluoranthene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Beryllium	0.84	-		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Cadmium	0.596	U		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Carbon Tetrachloride	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Cesium-137	0.049	U		pCi/g
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Chromium	25.7	J		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Chrysene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Dibenzo(a,h)anthracene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Dieldrin	1.6	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Ethylbenzene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Fluoranthene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Indeno(1,2,3-cd)pyrene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Lead	13.9	J		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Mercury	0.024	J		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Methylene chloride	4.8	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Molybdenum	1.1	-		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Phenanthrene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Pyrene	39.9	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Radium-226	1.017393	-		pCi/g

Area 5 Administration Area, WPL, Haul Road, and 60-inch Line Precertification Data

CU	Boring	SampleID	Parameter	Val	Res	VQ	Units
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Radium-228	1.15	-		pCi/g
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Selenium	3.57	U		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Silver	0.119	U		mg/kg
5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Technetium-99	2.09	U		pCi/g
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Tetrachloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Thorium-228	1.12	-		pCi/g
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Thorium-232	1.15	-		pCi/g
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Toluene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Trichloroethene	1	U		ug/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^RMPS	Uranium, Total	4.81	-		mg/kg
A5WPL-PC05	A5WPL-PC05-16	A5WPL-PC05-16^L	Xylenes, Total	1	U		ug/kg