

Henry F. Dalton
December 15, 1997
97-RF-06591
Page 2

Attachment:
As stated

cc:
Paul M. Golan w/o attach
Dave J. Nickless w/o attach



RF/RMRS-97-124.UN

**RECONNAISSANCE LEVEL CHARACTERIZATION REPORT
FOR THE 886 CLUSTER DECOMMISSIONING PROJECT**

**December 15, 1997
Revision 0**

RECONNAISSANCE LEVEL CHARACTERIZATION REPORT FOR THE 886 CLUSTER DECOMMISSIONING PROJECT

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
1.0 EXECUTIVE SUMMARY	1
2.0 INTRODUCTION	1
2.1 Report Purpose	4
2.2 Characterization Scope	4
2.3 Report Content	4
3.0 SUMMARY OF CHARACTERIZATION ACTIVITIES	4
3.1 Data Quality Objectives Used	5
3.2 Sampling and Field Measurement Methods, Equipment, and Procedures	6
3.3 Laboratory Analysis	7
4.0 CLUSTER OPERATING HISTORY	7
4.1 History of Buildings	7
4.2 Significant Releases and Events	7
4.3 Current Operations	8
4.4 RCRA and CERCLA Designated Areas	8
5.0 PHYSICAL DESCRIPTION	8
5.1 Summary Description	8
5.2 Specific Description	8
6.0 IDENTIFIED HAZARDS	10
6.1 Physical Hazards	14
6.2 Radiological Hazards	15
6.3 Chemical Hazards	17
6.4 Asbestos	17
6.5 Pressurized Gas and Liquid Nitrogen	19
6.6 Electrical	19
6.7 Wastes	19
7.0 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES	19
8.0 DATA QUALITY ASSESSMENTS	20
8.1 Project Decisions	20
8.2 Inputs to the Decisions	21
8.3 Decision, Rules, and Error Limits	21
8.4 PARCC Parameters	21
9.0 INFORMATION SOURCES	23
10.0 REFERENCES	23

TABLE OF CONTENTS (Cont.)

<u>Section</u>	<u>Page</u>
11.0 APPENDICES	23

LIST OF TABLES

<u>Table</u>	<u>Page</u>
Table 3-1. Laboratory Analysis Methods	7
Table 5-1. Building 886 Equipment	9
Table 6-0. Hazard Summary	11
Table 6-1. Summary of contamination values for Unrestricted Release	16
Table 7-1. Estimated Wastes From the 886 Cluster Decommissioning Project	20
Table 8-4. Precision Results by Method	22

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
Figure 1-1. 886 Cluster location at RFETS	2
Figure 1-2. 886 Cluster	3

ACRONYMS

ACM	Asbestos Containing Materials
AHERA	Asbestos Hazard Emergency Response Act
ALARA	As Low As Reasonably Achievable
BIO	Basis for Interim Operation
CA	Contamination Area
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CML	Critical Mass Laboratory
COCs	Contaminants of Concern
DOE	Department of Energy
EDDs	Electronic Data Deliverables
dpm	Disintegrations Per Minute
DQO	Data Quality Objectives
HCA	High Contamination Area
HEPA	High Efficiency Particulate Air filter
HEUN	Highly Enriched Uranyl Nitrate
HVAC	Heating Ventilation and Air Conditioning
IM/IRA	Interim Measure/Interim Remedial Action
LLMW	Low Level Mixed Waste
LLW	Low Level Waste
MAA	Material Access Area
MSDs	Matrix Spike Duplicates
PARCC	Precision, Accuracy, Representativeness, Completeness, and Comparability
PCBs	Polychlorinated biphenyls
PLM	Polarized Light Microscopy
ppm	Parts Per Million
RCA	Radiation Control Area
RCRA	Resource Conservation and Recovery Act
RFCA	Rocky Flats Cleanup Agreement
RFETS	Rocky Flats Environmental Technology Site
RLCP	Reconnaissance Level Characterization Plan
RLCR	Reconnaissance Level Characterization Report
RPD	Relative Percent Difference
SNM	Special Nuclear Material
SOE	Stationary Operating Engineer
TCLP	Toxic Characteristic Leachate Procedure
TRU	Transuranic
TSI	Thermal System Insulation
UCL	Upper Confidence Level

RECONNAISSANCE LEVEL CHARACTERIZATION REPORT FOR THE 886 CLUSTER DECOMMISSIONING PROJECT

1.0 EXECUTIVE SUMMARY

Building 886 housed the Critical Mass Laboratory and was operated from 1965 until 1987. Since then, operations within the building have been limited to maintaining the safety envelope and compliance with the Basis of Interim Operation. Since Building 886 and its associated facilities have no mission, the cluster is being decommissioned to reduce operating costs and to eliminate hazards within the cluster's buildings. Deactivation activities are not yet complete, but had progressed to the point where a meaningful characterization could be conducted. The purpose of this Reconnaissance Level Characterization Report is to present the historical data and process information pertaining to the 886 Cluster to provide a baseline of information for hazards within the building cluster. The reconnaissance level characterization of the Building 886 Cluster included a review of historical records and the collection of process knowledge and samples to determine the extent of contamination within the cluster.

The characterization of the 886 Cluster has revealed that the cluster has been maintained within the safety envelope required by the Basis for Interim Operation. The hazards which will need to be considered in developing plans for and executing decommission activities can be summarized in the following list.

- Physical Hazards (i.e., trip and fall hazards, noise hazards, sharp edges, etc.) - Hazards are found in Buildings 886, 875, 888A, 828, and 880.
- Radiological Hazards - Contamination areas are found in Buildings 886, 875, and 880. High contamination areas are found in Buildings 886 and 875.
- Chemical Hazards - Primarily lead and other metals in building paints, and some limited polychlorinated biphenyls (PCB) sources. No beryllium has been identified associated with the cluster either through process knowledge or analytical results.
- Asbestos Hazards - Asbestos containing materials are found throughout the cluster with the exception of T886A. An asbestos abatement plan will be required as part of the decommissioning activities.
- Pressurized Gas Cylinders Hazards - Only one nitrogen gas container remains in the 886 Cluster.
- Electrical Hazards - Electrical systems are currently in a safe and compliant condition. However, when decommissioning activities begin, significant electrical hazards in Buildings 886, 875, and 888A will need to be addresses.

2.0 INTRODUCTION

The Building 886 Cluster (Figure 1-1) is comprised of Buildings 886, 888A, 880, 875, 828, T886A, and an underground tunnel with ventilation ducts that connects Building 886 to Building 875 (Figure 1-2). Because Building 886 and its associated facilities have no mission, the cluster is being decommissioned to reduce operating costs and to eliminate hazards within the cluster's buildings. Consistent with the Rocky Flats Cleanup Agreement (RFCA), the 886 Cluster Decommissioning Project is being conducted as a Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) removal action. The 886 Cluster Decommissioning Project is one of the decommissioning activities at the Rocky Flats Environmental Technology Site (RFETS) selected to meet the site's goals.

BUILDING 886 SITE LOCATION




Figure 1-1. 886 Cluster Location at RFETS

BUILDING 886 AREA




Figure 1-2. 886 Cluster

2.1 Report Purpose

The purpose of this Reconnaissance Level Characterization Report (RLCR) is to present the historical data and process information pertaining to the 886 Cluster to provide a baseline of information for hazards within the building cluster. Characterization includes identification of the type, quantity, condition, and location of radioactive and hazardous materials which are, or which may be present as residual contamination in the subject facilities. Information from the report will be incorporated into an Interim Measure/Interim Remedial Action (IM/IRA) plan for the 886 Cluster Decommissioning Project.

2.2 Characterization Scope

The reconnaissance level characterization of the Building 886 Cluster included a review of historical records and the collection of process knowledge information covering the operational time period for the facility from original construction to present. This information was evaluated to identify data needs for the characterization effort. Samples were then collected from throughout the cluster and analyzed to complete the information needed to represent the current condition of the buildings and associated contamination.

2.3 Report Content

Information and data presented in this report specifically pertain to the Building 886 Cluster. The report includes a summary of the characterization activities, a brief physical description of the facilities, identifies the hazards within the cluster, estimates the types and volumes of wastes which will be generated during decommissioning activities, presents a data quality assessment, and lists the information source and references used in compiling the characterization of the Building 886 Cluster.

3.0 SUMMARY OF CHARACTERIZATION ACTIVITIES

The characterization effort for the 886 cluster included a review of historical records pertaining to the cluster and collecting process knowledge regarding conditions within the buildings. As part of this investigation, comprehensive physical inspections of all accessible areas of the 886 Cluster were conducted during November and December, 1997. The primary purpose of these inspections were:

- confirm the accuracy of file documentation of as-built or modified facility construction, equipment installations, and general facility conditions;
- obtain volume estimates for wastes that will be generated during removal activities;
- identify equipment, structures, process lines, and associated items that will require hazardous and/or radioactive surveys and analytical sampling to further characterize the cluster;
- identify potential sources of lead and asbestos;
- identify potential chemical contamination;
- identify physical hazards;
- locate, identify, and document any facility condition or problem situation which had not been previously identified or otherwise documented in appropriate building records or files; and
- identify equipment, structures, process lines, and associated items which require field surveys and/or analytical sampling for the purpose of characterizing the cluster for radioactive and hazardous contaminants.

The final portion of the characterization effort involved the development and execution of a Reconnaissance Level Characterization Plan (RLCP). This document stated the sampling effort to be conducted in the cluster buildings. It included plans for sampling areas potentially containing or contaminated with asbestos, polychlorinated biphenyls

(PCBs), and lead and metals. The plan was reviewed and approved and the execution was directly supervised by a State of Colorado certified asbestos inspector. Radiological contamination was sufficiently characterized by process knowledge and existing surveys.

3.1 Data Quality Objectives Used

Data Quality Objectives (DQOs) were established and defined in Section 3.0 of the RLCP. Definition of DQOs is a quality requirement as well as a proven tool for optimizing sampling and analysis costs relative to attaining adequate confidence in technical project decisions. The DQO process was designed after EPA (EPA, 1994, G-4) and DOE guidelines. All DQOs were consistent with applicable state and federal regulations governing the contaminants of concern (COCs). A concise summary of the DQOs as presented in the RLCP is given below.

THE PROBLEM

Several contaminants were suspected within the 886 Cluster, but the quantities and concentrations of contaminated media were unknown relative to the requirements associated with D&D activities. Determination of the types and quantities of contamination, and the associated consequent waste streams, are required for successful implementation of D&D. Based on historical process knowledge of the 886 Cluster, the potential COCs are asbestos, PCBs, lead/metals, and radionuclides.

THE DECISIONS

The critical technical decisions for the project were as follows:

- What materials (e.g., paint, concrete, pipe insulation, etc), media (e.g., water, oil, solid, sludge, etc), or equipment within the facility are contaminated or, conversely, not contaminated?
- What are the generic classification categories by which the materials, equipment, and/or media will be managed, relative to an eventual assignment as contaminated (hazardous, radiological, or mixed) or not contaminated (nonhazardous)? In other words, what are the categories of waste streams that will result from the D&D of the 886 Cluster?
- What are the ultimate dispositions (i.e., waste classifications) of the waste streams, including quantities (e.g., a completed summary table)?

INPUTS to the DECISIONS

Inputs to the decisions were designed to be both qualitative and quantitative. Qualitative information consisted of nominal data (e.g., paint color or equipment type) derived from visual observation of buildings' equipment and materials. Quantitative data was produced from analytical and petrographic analyses of samples (for characteristic metals, PCBs, and asbestos). Radiation activities were estimated based on historical surveys.

PROJECT BOUNDARIES

The 886 Building cluster (i.e., the buildings themselves) and all equipment/materials contained within, was relegated as within the project boundaries, whereas environmental media outside the buildings were not.

DECISION RULES and ERROR LIMITS

All decision rules were based on objective, reproducible, and verifiable quantitative criteria as stated in Section 3.5 of the RLCP. Decision error tolerance was established at 5% (i.e., a 95% upper confidence limit) for data sets representing homogeneous media.

OPTIMIZATION OF DESIGN

Any modifications to the DQOs hinged on visual observations and new information revealing data gaps as the project progressed, and are discussed in the Data Quality Analysis.

3.2 Sampling and Field Measurement Methods, Equipment, and Procedures

Acquisition of a sample directly depends on the sampling team's observations of the material, equipment, equipment components, or media of interest. Because of excess equipment noted in some of the rooms and/or buildings, access to all potential survey points is not possible. In addition, the cluster is not through deactivation. These deactivation activities (such as size reduction and removal of radiologically contaminated materials and equipment) may jeopardize the characterization surveys. Therefore, if data gaps are identified subsequent to the characterization sampling and decisions described herein (i.e., the decision cannot be made with confidence), additional sampling of source materials and/or waste streams will be conducted.

As stated earlier in this report, the radiological contamination within the 886 Cluster was able to be characterized using process knowledge and existing surveys. Similarly, process knowledge was conclusive concerning the absence of beryllium contamination with the 886 Cluster. Thus, the characterization effort focused on the following hazardous constituents: asbestos, PCBs, and lead and metals. The sampling and field measurements, equipment, and procedures used to perform the characterization for these contaminants are described below.

Asbestos

Asbestos containing materials (ACM) were inspected and sampled by a State of Colorado certified inspector in accordance with the Colorado Code of Regulations 8 and the Asbestos Hazard Emergency Response Act (AHERA), 40 Code of Federal Regulation (CFR) 763. The materials evaluated include thermal systems (e.g., pipe insulation), surfacing materials (e.g., fireproofing, ceiling texture), and miscellaneous materials (floor tiles, ceiling panels, concrete foundations and walls). Bulk samples were taken using coring bits or hammer and chisel in accordance with the RLCP.

Polychlorinated Biphenyls (PCBs)

Potential PCB contamination was evaluated in accordance with 40 CFR 761.125. To assess material against the regulatory threshold of 50 parts per million (ppm), a practical quantitation limit of 5 ppm (one order of magnitude less than the regulatory action level) was used. Material sampled included transformers, capacitors, fluorescent light ballasts, gaskets in potential PCB-containing systems, and paints in accordance with the RLCP.

Lead and Metals

All materials suspected of containing or being coated with lead or other Resource Conservation and Recovery Act (RCRA) regulated metals were representatively sampled. This included paint, gloveboxes, shielding, piping, plates, lead fills in walls, skirting, and additives (e.g., plaster). The bulk samples were collected as described in American Standard for Testing Materials (ASTM) Method E 1729-95 using chisels, scrapers, and cutting tools in accordance with the RLCP. The analysis routinely includes evaluation for beryllium.

3.3 Laboratory Analysis

Table 3-1 summarizes the analytical methods performed on the various samples taken during the characterization effort.

Table 3-1. Laboratory Analysis Methods

Suspected Contaminant	Laboratory Analysis Method
Asbestos	Polarized Light Microscopy
PCBs	SW8081
Lead and Metals	SW6010A

4.0 CLUSTER OPERATING HISTORY

The purpose of the 886 Cluster was to conduct criticality experiments on liquid, powder, and solid forms of fissionable materials. The date of the last criticality experiment was October 1987. These experiments were essential to validate computer models used to establish nuclear criticality safety limits, now called Criticality Safety Operating Limits.

4.1 History of Buildings

The construction of Buildings 886, 875, and 888A was completed in 1964 and commissioned in 1965. The trailer T886A was located east of Building in approximately 1980; a breeze-way connected the two at a later date. The construction date of Building 880 is unknown. The last criticality experiment was conducted in October 1987. Since then the buildings have been maintained within the safety envelope, but the facility is not operational.

4.2 Significant Releases and Events

There reportedly have been five incidents where uranyl nitrate was spilled onto the floor of the Critical Mass Laboratory (CML). The largest spill involved between 50 and 60 gallons of solution. The laboratory floors are sealed and bermed to contain such spills, and in no case did solution escape the building. The solution was recovered for further use. In another case in the late 1960's, an accumulation of uranyl nitrate salt was found inside the base of the ventilation system filter plenum outside of Building 886. This accumulation, about one foot square and one-quarter inch thick, is thought to have most likely resulted from an incident in which some solution overflowed into a vent line and dried, with subsequent air flow over the vent carrying the salt to the filter plenum.

There are no recorded instances where contamination was released to the environment.

4.3 Current Operations

Building 886 is not currently operational. The buildings have been vacated except for three individuals who are planning moves and T886A, which is being utilized as a project support trailer. Deactivation activities were suspended in late FY97 to because resources were diverted to other efforts. The only ongoing operations are those necessary to maintain the safety envelope and comply with the basis for operation (BIO) building authorization.

4.4 RCRA and CERCLA Designated Areas

There are no RCRA or CERCLA designated areas within the 886 cluster. However, the 886 Cluster Decommissioning Project is being conducted as a CERCLA removal action.

5.0 PHYSICAL DESCRIPTION

The 886 Cluster is located in the RFETS industrial area at the east central portion of the site. It is located just south of Central Avenue and just east of the pedestrian traffic signal. The buildings were used in support of criticality experimentation from 1965 through 1987. Primary construction materials used in the buildings include concrete masonry, steel, and wood with siding.

5.1 Summary Description

The buildings associated with the cluster are 886, 888A, 880, 875, and T886A. The cluster also includes an outside concrete pit containing two raschig ring tanks also referred to as building 828, and an underground tunnel linking the Air Filter Plenum Building (875) with Building 886. All the structures are single story buildings, with the exception of the criticality laboratory portion of Building 886 which is two stories high. The individual buildings are described in more detail in the following sections.

5.2 Specific Description

Building 886

Building 886 contains the Critical Mass Laboratory (CML) where criticality experiments were performed. It is approximately 10,785 square feet, of which approximately 4,000 square feet constitutes the radiological control area (RCA). The remaining area is comprised of office space. The facility has no basement. The RCA is comprised of rooms 101, 102, and 103; and a hallway, referred to as room 108; all with slightly different construction from each other.

Room 101 is the assembly room where all criticality experiments were performed. It is approximately 2,000 square feet. It has four to five feet three thick concrete walls and the north wall is reinforced concrete. The ceiling is 30 feet above the floor and is also thick concrete. The floor is concrete and is a floating floor with respect to the walls.

Room 102 was a storage vault for special nuclear material (SNM). It is approximately 600 square feet. The walls are double reinforced concrete with a cast integral concrete roof.

Room 103 is the mixing room which serves as a fissile solution mixing and storage area. It is approximately 900 square feet. It has three walls that are reinforced concrete with the west wall constructed of back filled cinder blocks with rebar. The roof is sheet metal with a tar overlay. Approximately half of the room is two to four feet below the building's floor level.

Room 108 is the hallway within the CML connecting Rooms 101, 102, and 103. It is approximately 500 square feet.

Outside of the RCA, Room 111 is the Utility Room and Room 112 is the Control Room. Room 141 is the Stationary Operating Engineer (SOE) Control Room. The remaining rooms within the building are considered office space. The floor of these rooms is a slab on grade and the walls are back filled cinder block with a built up roof.

Recent removal of containers of low enriched uranium oxides and two check sources of Cobalt-60 and one check source of Californium-252 was completed as a risk reduction activity. Highly enriched uranyl nitrate (HEUN) was drained from the tanks in Building 886 and the raschig rings were removed from the tanks in Room 103 as part of a risk reduction activity.

The equipment located in Building 886 is listed in Table 5-1.

Table 5-1. Building 886 Equipment

Equipment	Quantity	Equipment	Quantity
Horizontal Split Table (RCA)	1	Concrete Reflector Panels (RCA)	8
Vertical Split Table (RCA)	1	Solution Transfer Pump (RCA)	6
Solution Base (RCA)	1	Reactor Control Console	1
Water Reflector Apparatus (RCA)	1	Air Compressors	2
Elevated Platform (RCA)	1	Bridgeport Mill	1
Walk-in Hood (RCA)	1	Logan Lathe	1
Stainless Steel Tanks (RCA)	11	Lektriever	1
Glovebox Type Enclosures (RCA)	2		

Building 875

Building 875 is approximately 3,900 square feet and houses the filter plenums that filter air which has been circulated through the Building 886 Exhaust System. The building is cinder block construction with a concrete floor. The roof is tar impregnated felt.

The facility has a concrete pit on the north end which accesses the tunnel. The tunnel connecting 875 and 886 is considered part of this facility. Plenum 501 is a two-stage high efficiency particulate air (HEPA) filter servicing the office area. Plenum 502 is a four-stage HEPA filter plenum servicing the material access area

(MAA) exhaust air. Tank D-501 is the plenum deluge tank. The building also contains a 1,200-gallon critically safe tank filled with raschig rings. A metal cabinet containing sources is also in the facility. Groundwater seepage into the raschig ring tank area is routinely pumped out. Drummed waste located in Building 875 has been packaged and radiologically surveyed and is presently awaiting shipment.

Building 888A

Building 888A is an approximately 400 square feet enclosure, and is an electrical substation for the cluster's buildings. It consists of two cinder block walls on the north and west, with the remaining sides consisting of chain link fence with razor wire top. There is no roof and the floor is natural ground. The structure encloses one feeder transformer that operates at 13,800 volts which supplies power to Buildings 886 and 875. The transformer has been previously tagged indicating that polychlorinated biphenyls (PCBs) are not present.

Building 880

Building 880 is an unpainted, metal building of approximately 800 square feet currently being used for excess storage. It is a metal "Butler" type building 100 feet south of Building 886. It has several items of used experimental equipment waiting anticipated re-use. Some of these items were, at one time, contaminated with enriched uranium and packaged in the then-acceptable contained configuration. While contaminated materials and equipment are included in the current inventory, no materials are being moved in or out of the building. The majority of waste streams are considered, and will be packaged and handled as, low-level waste.

Building T886A

Building T886A is approximately 1,900 square feet and is an officer trailer attached to the northeast corner of Building 886. It serves as office space for the 886 Cluster Decommissioning Project and is of standard trailer construction.

Building 828

Building 828 is an outside concrete pit containing two 1,000 liter tanks filled with unused raschig rings. Groundwater has historically seeped into the pit and was pumped out to a tanker, sampled, and transported for appropriate disposal.

6.0 IDENTIFIED HAZARDS

The hazards identified during the reconnaissance level characterization for the 886 Cluster are summarized in Table 6-0 and described in the following sections by hazard category and by area.

Reconnaissance Level Characterization Report
 For the 886 Cluster
 Decommissioning Project

RF/RMRS-97-124.UN
 Revision 0, Page 11 of 23
 Effective Date: 12/15/97

Table 6-0. Hazard Summary

Bldg./ Room	Description	Square Feet	Hazard	Matrix	Max. Concentration
B886	General Building (specific rooms detailed below)	10,785	Asbestos	Piping insulation, skim coat on cinder block, floor and ceiling tiles, filler, wiring insulation, roof	
101	Critical Mass Laboratory	2,000	Press. Gas	one cylinder of nitrogen gas	
			Physical	Elevated platform, overhead equipment, falls	N/A
			Radiological	Tanks, process lines, ventilation ducts, assembly hood, floor, and equipment	N/A
			Hold up	2 tanks with raschig rings, SCRAM tank, annular tank	HCA Limits
102	Storage Vault		Lead	Paint (by color)	Classified
			PCBs		
103	Mixing Room	600	Radiological	Potential fixed contamination in floor	
			Lead	Paint	HCA Limits
		900	Physical	Un-secured ladder, protruding piping and valves	N/A
			Radiological	Tanks, process lines, ventilation ducts, glovebox, floor	HCA Limits
			Hold up	Pumps	
			Lead	Paint (by color)	Classified
108	Hallway		PCBs		
		500	Radiological	Potential loose surface contamination	HCA Limit

Reconnaissance Level Characterization Report
 For the 886 Cluster
 Decommissioning Project

Bldg./ Room	Description	Square Feet	Hazard	Matrix	Max. Concentration
			Lead	Paint	N/A
		1,000	Physical	Sharp edges, corners, protruding piping and valves	
111	Utility Room		Lead	Paint (by color)	
			PCBs		480 V
			Electrical	Equipment, electrical panels	N/A
		480	Physical	Control boxes and sheet metal with sharp edges	
112	Control Room		Lead	Paint	480 V
			Electrical	Control boxes, electrical panels	N/A
		5,300	Physical	Sheet metal with sharp edges	
All others	Offices		Lead	Paint	N/A
			Physical	Noise, sharp edges	HCA Limits
B875	Filter Plenum Facility	3,900	Radiological	Filter Plenum	
			Lead	Paint	
			PCBs		
			Asbestos	Piping insulation, roof	480 V
			Electrical	Equipment, electrical panels	N/A
		800	Physical	Trip and fall, protruding edges	
B880	Storage				

Reconnaissance Level Characterization Report
 For the 886 Cluster
 Decommissioning Project

RF/RMRS-97-124.UN
 Revision 0, Page 13 of 23
 Effective Date: 12/15/97

Bldg./ Room	Description	Square Feet	Hazard	Matrix	Max. Concentration
			Radiological	Stored waste	HCA Limits
			Lead	Paint (by color)	
			PCBs		
B828	Tank Pit	170	Physical	Confined space, falls, protruding pipes and valves, slips, spiders	N/A
			Lead	Paint	
B888A	Electrical Substation	400	Physical	Razor wire	N/A
			Asbestos	Wiring insulation, arc chutes, arc protection, insulators, conduit trays	
			Electrical	Substation	
T886A	Project Trailer	1,900	Lead	Paint	13.8 kV

6.1 Physical Hazards

The buildings within the 886 Cluster have been maintained within the safety envelope required by the BIO. As a result, there are no physical hazards from damaged or dilapidated infrastructure. However, some physical hazards are intrinsic with portions of the cluster and are described below.

Building 886

Room 101 has an elevated platform with equipment located on it as well as an overhead crane. These may represent an overhead hazard when D&D activities begin. Work on the platform has fall hazards associated with it.

Room 103 has a ladder going to an elevated platform which is not secure and has been barricaded. The room also has protruding piping and valves which represent a hazard to workers when they are working closely around the equipment.

Room 111 has numerous sharp edges, corners, and protruding pieces of equipment, pipes, and valves. Although safe for current operations in that they do not impinge on the walk ways, when workers begin D&D operations in this room, they will need to be cognizant of these hazards.

Room 112 has numerous control boxes and sheet metal with sharp edges.

Throughout the building, and the rest of the cluster, there is sheet metal with sharp edges. Although not normally accessible, as D&D activities begin around the sheet metal, attention to cutting edges will be required.

Building 875

The operation of the air filtration system in Building 875 creates a noise hazard which requires the use of hearing protection within the building when the filter plenum system is in operation.

Building 888A

This enclosure around the electrical substation has razor wire around the top. This represents a hazard to the workers when they proceed with D&D activities.

Building 828

Building 828 is a below grade confined space. Any work within the pit will require a confined space permit. Furthermore, the pit represents a falling hazard if left open and consideration will need to be given during the D&D process to maintaining fall protection or barricades around it.

The pit also contains numerous protruding pipes and valves which will be a hazard for workers in the pit.

Historically, there have been numerous occasions when ground water has enter 828. This water was pumped out, but the pit is wet, muddy, and slick.

The pit is also a natural breeding ground for spiders. Measures have been taken in the past to eliminate the spiders before beginning work in the pit. Similar precautions will be needed for the D&D activities.

Building 880

Building 880 has been used for storage. The material stored in the building creates numerous trip and fall hazards, and protruding edges if moving among the containers.

6.2 Radiological Hazards

Past Activities

Deactivation activities had previously begun in Building 886 prior to the initiation of this project. Those activities involved the draining and offsite shipment of the highly enriched uranyl nitrate (HEUN) as well as deactivation of most the HEUN storage tanks. There are several tanks in the cluster that still require the raschig rings to be removed which could potentially contain solution hold up. Deactivation will be completed prior to strip-out of the tanks for waste packaging. Extensive decontamination efforts were also completed to bring all areas of the cluster into current Site radiological requirements. Although the HEUN solutions were removed to the maximum extent possible, there is known to be dry residues contained within the storage tanks and the associated piping. This residue will result in higher levels of contamination during deactivation activities than those currently shown in the cluster routine surveys.

Current Conditions

The Building 886 Cluster radiological areas are posted and controlled in accordance with 10 CFR 835. Contamination control criteria for this project include postings that are currently applicable to the radiological conditions in the 886 Cluster. Those postings are Contamination Area (CA) and High Contamination Area (HCA). There are presently CAs in Building 886, 875, and 880. HCAs are located in Buildings 886 and 875. All control levels for these areas are based on the transuranic limits due to possible uncertainty concerning quantity and locating plutonium handling in Building 886 (transuranic limits are the most conservative). This control process is consistent with DOE radiological policy for other activities at the Site.

Contamination Areas are controlled to a limit of 2000 disintegrations per minute (dpm) per 100 square centimeters. See Table 6-1 for the summary of contamination values used to establish radiological control areas. Radiological surveys are being performed for in-process work and on a regular basis for all areas of the cluster, usually weekly, to ensure that contamination is maintained below requisite levels. As deactivation is completed in each of the remaining areas, decontamination surveys will be the used as the baseline for future decommissioning activities.

The cluster safety envelope has been maintained throughout its life cycle. There is good continuity of personnel from the deactivation and HEUN removal projects. Based on these factors, process and historical knowledge as well as the radiological conditions documented on the survey logs are believed to be very reliable.

As Low As Reasonably Achievable (ALARA)

As Low As Reasonably Achievable (ALARA) principles will be used in the planning and execution of D&D activities to minimize exposures to workers and public. The DOE RadCon Manual and 10 CFR 835 give general guidance on field implementation (e.g., ALARA Committee, Pre-Job Planning, Post-Job Review) of ALARA principles. Project specific work procedures will include ALARA considerations to minimize worker exposure during D&D activities. ALARA principles will also be reflected in the final release criteria to minimize public exposure following D&D.

Table 6-1. Summary of contamination values for Unrestricted Release

Radionuclide	Average Total (Fixed + Removable) Contamination (dpm/100cm ²)	Maximum Total (Fixed + Removable) Contamination (dpm/100cm ²)	Removable Contamination (dpm/100cm ²)
Transuranic: Ra- ²²⁶ , Ra- ²²⁸ , Th- ²²⁸ , Pa- ²³¹ , Ac- ²²⁷ , I- ¹²⁵ , I- ¹²⁹	100	300	20
Th-Natural: Th- ²³² , Sr- ⁹⁰ , Ra- ²²³ , Ra- ²²⁴ , U- ²³² , I- ¹³¹ , I- ¹³³	1,000	3,000	200
U-Natural: U- ²³⁵ , U- ²³⁸ , and associated decay products, alpha emitters	5,000	15,000	1,000
Beta-gamma emitters (radionuclides with decay modes other than the alpha emission or spontaneous fission) except Sr- ⁹⁰ and others noted above.	5,000	15,000	1,000

Isotopes of Concern

The principal DOE isotopes of concern include:

- Uranium-235,
- Uranium-234,
- Uranium-238,
- Plutonium-239, and
- Americium-241.

The specific isotopes were identified based on survey results, personnel interviews, and historical records. Trace amounts of some decay products may be present and will be evaluated during waste characterization.

Surveys Performed/Evaluated

Radiological surveys have been performed in representative areas of the 886 Cluster. The level of detail for specific surveys was based on the radioactive contamination potential for the area. Extensive radiological survey information was used for this characterization effort in lieu of new surveys.

Additional routine surveys were performed in accordance with procedures. In addition to removable alpha surveys, removable beta was also determined. Buildings 875 and 880 were also surveyed in accordance with routine survey procedures. Appendix A contains copies of the surveys that are the basis for this radiological characterization.

As stated previously, the downdraft unit and associated glovebox in Room 103, the assembly hood in Room 101, process piping in Rooms 101 and 103, and the ventilation plenum in Building 875 were not characterized as part of this effort but will be characterized as deactivation activities are completed. These

areas are associated with high levels of contamination (HCAs) and will require deactivation and decontamination prior to decommissioning of the 886 Cluster.

6.3 Chemical Hazards

ANALYTICAL RESULTS PENDING

Appendix B will contain the analytical results used to characterize the chemical hazards.

A discussion of each of the following applicable contaminants will be included.

- Lead
- Beryllium
- Other Metals
- PCBs
- Others

6.4 Asbestos

During the inspection process, historical records were accessed and evaluated, along with physical inspection of the cluster. The investigation reviewed original specifications and blueprints, asbestos and lead in paint bulk samples, and interviews with facility occupants, including the Facility Manager. The findings of the characterization are discussed by building in the following sections and Appendix C contains the Certified Asbestos Inspector's Report.

Building 886

Building 886 is the main structure of the cluster. The inspection process discovered asbestos containing thermal systems insulation (TSI) on piping and tanks associated with the domestic water, chiller system, steam system in the interior and exterior of the building, and on a small heating ventilation and air conditioning (HVAC) system located outside on the west side of Building 886. This TSI is generally in good condition and appears to have regular maintenance.

Asbestos containing surface materials discovered during the inspection were limited to a light skim coat on the interior cinder block associated with the oldest section of the structure. This material is covered with a minimum of one coat of paint and is in good condition. Due to the thinness of the application and the relatively low percentage of asbestos (trace to five percent), point counting analysis was utilized to more accurately evaluate asbestos content with results indicating levels consistently above one percent. This material must remain as part of the asbestos waste stream even though a composite of this skim coat and the cinder block would reduce the asbestos percentage to far less than one percent.

Miscellaneous asbestos containing material (ACM) discovered during the inspection included nine inch and twelve inch floor tiles dispersed throughout the cold side of the facility, including under the sheet vinyl in the hallways. The adhesive associated with the floor tiles tested negative for asbestos except in Room 110, the janitorial closet. The tiles are in generally good condition and appear to receive regular maintenance.

The predominant pattern of ceiling tiles (2 by 4 feet white with wide latitudinal grooves, pits, and pin holes) tested positive for asbestos. Due to the modular nature of a suspended ceiling, the remaining patterns must be

assumed to be contaminated with asbestos. The suspended ceiling system was in good condition at the time of the inspection.

A filler between the HVAC ducts and wall penetrations is 98 percent asbestos. This filler was not observed in all locations, but is predominant throughout the facility. At the time of the inspection, the filler was painted and in good condition where observable.

A previous inspector acquired a sample of the electrical wiring in Room 114 which indicated asbestos in the insulation. Until the building circuits are de-energized and a comprehensive survey can be completed, it must be assumed that all original wiring insulation for the structure, and for the original structures in the cluster, is asbestos containing.

Building 886 has a built up roof system that was specified as containing asbestos in the felt and tar. As such, the roof is assumed to be asbestos containing without the need of sampling. Tar impregnated roofing felts may be disposed of with normal demolition debris under most circumstances.

Building 828

The Building 828 exterior walls are assumed to be asbestos containing based on historical data from other locations on the Site and on the expert judgement of the Certified Asbestos Inspector. The piping associated with the underground storage tanks is not insulated.

Building T886A

T886A is a modular trailer (S.N. 3404) constructed by Elder in 1984. Alan Koenig from G.E. Capital, the parent company of Elder, verified that this particular structure was not constructed with any materials that contained either lead or asbestos.

Building 888

Although not included as part of the 886 Cluster, Building 888 is powered from 886 and will be impacted by the demolition of the 886 Cluster. Because of this, the inspector evaluated the building on the chance that it may be included, or that work may be required on it during the 886 D&D activities. The building is a guard post constructed in the mid 1980's. As such, building materials have a low possibility of containing asbestos. Based on visual inspection, all materials were eliminated as suspect asbestos containing materials except the roofing and the drywall systems. Samples were acquired of the drywall system and the analytical results were non-detects. The built-up roofing can be assumed to be asbestos containing tar impregnated roofing felt, which can be disposed of with the regular construction debris in most cases.

Building 875

Building 875 is the Plenum Facility for Building 886 and includes the service tunnel to 886. Since this structure is of the same construction date as Building 886, suspected ACM are shared. As such, all piping insulation must be considered to be asbestos containing unless it can be eliminated by physical touch as either foam or fiberglass insulation. The asbestos insulation was predominantly confined to the fittings, reductions, hangers, tees, and elbows, while the straight runs were predominantly foam and fiberglass.

The roofing of Building 875 is similar in construction to that of Building 886. As such, the original specification called for the use of tar and felt containing asbestos. Based on this information, the roofing

materials are assumed to be asbestos containing. These materials may be treated as regular demolition debris in most cases.

Building 880

At the time of inspection, no asbestos containing building materials were discovered in Building 880.

Building 888A

Building 888A is the electrical substation for the facility. Due to the inherent safety concerns with sampling live electrical equipment, no samples were acquired. Suspect ACM include wiring insulation, arc chutes, arc protection, insulators, and conduit trays. Once the substation is de-energized, samples can be safely acquired of these materials. In the interim, these materials are assumed to be asbestos containing.

6.5 Pressurized Gas and Liquid Nitrogen

There is only one cylinder of pressurized gas in the 886 Cluster. It is nitrogen gas used for maintenance on the chiller unit. The bottle is located in a bottle rack outside Building 886 on the west side.

6.6 Electrical

The 886 Cluster is currently in a safe condition for electrical hazards. However, when D&D activities begin, significant electrical hazards are located through out the cluster, particularly in the control and utility rooms of Building 886, Building 875, and in and around Building 888A. Additionally, consideration will need to be given as to how to resupply the guard shack located next to 888A with power once the supply from 886 is interrupted.

It should be noted that numerous system changes have been made to the electrical system in the cluster over the years of operation. These changes are not reflected well in the as-built drawings for the facilities. The electrical system will require tracing of questionable lines with a tic tracer or similar device before D&D activities are implemented.

6.7 Wastes

When deactivation activities were suspended in the 886 Cluster in late FY97, some waste remained in the buildings. This waste is all low level (LL) waste. Plans are currently in place to remove this waste from the buildings. There are 80 55-gallon drums which have been assayed, 40 55-gallon drums that are in the process of being assayed, and three full-size waste crates that need to have their contents verified and assayed. In addition to this packaged waste, there is some unpackaged waste in Room 101. The majority of this waste is metal and is mainly excess equipment.

7.0 DECOMMISSIONING WASTE TYPES AND VOLUME ESTIMATES

Table 7-1 summarizes the types and quantities of wastes estimated for the deactivation of the 886 Cluster. These estimates were derived from existing documentation regarding equipment and materials in the cluster and from inventories compiled during walk-through of the facilities.

Table 7-1. Estimated Wastes From the 886 Cluster Decommissioning Project

Type of Waste	Primary Matrix	Quantity (cubic meters)	Type of Waste Package	Quantity of Waste Package
Hazardous	Painted materials	3	Standard Crate	1
Asbestos	Insulation, building materials, wiring, etc.	200	Bulk	N/A
Low-level	Paper/Glass/Plastic/Pipe	225	Standard Crate	75
Low-level Mixed	Plastic/Pipe	3	Standard Crate	1
TRU	None	0	N/A	N/A
TRU Mixed	None	0	N/A	N/A
Sanitary	Rubble	1,000	Bulk	N/A

8.0 DATA QUALITY ASSESSMENTS

The purpose of data quality assessment is to determine whether a set of data is adequate for its intended use, especially relative to supporting predefined project decisions with acceptable levels of confidence (after EPA G-9, 1996). EPA's approach to data quality assessment heavily emphasizes the use of statistical methodologies, which incorporate "ratio" data, i.e., data exhibiting a broad range of values relative to action levels. This reconnaissance level characterization, however, hinges primarily on nominal data (e.g., paint colors or equipment/material types), with associated analytical results indicating a nominal outcome from at least one judgmental (i.e., non-statistical) sample: Pass/Fail. Therefore, typical statistical (EPA) methodologies that might be used for comparing a project's data set with a background or baseline to evaluate significance is not well suited for use with most of the contaminants of concern evaluated for the 886 Cluster, with the exception of radionuclides. Based on the availability of previous radiological survey data within the areas of interest, DQOs were not formally presented for this reconnaissance effort, but will be addressed for final decontamination surveys.

Notwithstanding the limited statistical applications to the non-radionuclide contaminants of concern, a data quality analysis is still necessary to determine if the data collected are adequate for their intended use. Table 6-0 exhibits a summary of the samples collected for each contaminant category - by location and by nominal category represented (e.g., paint color).

8.1 Project Decisions

A summary of the project decisions is also given in Table 6-0 based on the original DQOs expressed in §3.1, which are:

- definition of the contaminated equipment and materials, based on sample representativeness and analytical results, and
- definition of the waste classifications and assignment of all contaminated equipment/media to those classifications (for subsequent treatment, storage, transport, and/or disposal). Table 7.1 provides estimated quantities of the waste types.

8.2 Inputs to the Decisions

Inputs to the decisions noted above consisted of the project's data, which is tabulated in Table 8.3. Data quality is addressed in terms of precision, accuracy, representativeness, completeness, and comparability -- the PARCC parameters -- in Section 8.4.

8.3 Decision, Rules, and Error Limits

With the exception of asbestos, statistically-based samples, particularly with respect to randomness and quantities, were neither taken nor required. Therefore, calculation of upper confidence limits on the data (e.g., 95% UCLs) are not needed; asbestos sample decisions are based on compliance with the 40 CFR 763.86. However, it should be noted that for the media sampled the contaminants of concern were either not detected (i.e., well below action levels) or were well above action levels (and therefore, of course, much greater than detection limits). These high ranges in the data suggest, semi-quantitatively, that there is little probability of either alpha (false-positives) or beta (false negatives) errors; stated differently, no data resides in the "gray regions", where results are within 5 times or 1/5 the action levels.

Further, in sampling situations where samples were not taken (see Sections 6.3 and 6.4 for example) -- typically due to safety precautions -- the media of interest is assumed to be contaminated. These assumptions increase the alpha (producer's) error, which translates into more cost for the RFETS, but reduce the beta (consumer's) error, which translates into greater safety for the workers and the public.

8.4 PARCC Parameters

In general, precision and accuracy are determined by analytical lab controls and subsequently qualified based on a data validation process. At least 25% of the results of the data are planned for formal data validation via the K-H APO. The primary components of interest within the validation process are listed within the subsections below.

Accuracy

Accuracies indicate how close the measured values are to "true" values, or conversely, accuracy quantifies the amount of error associated with the measured value as compared to a true value.

Precision

Precision quantifies how repeatable the sample measurements are. Precision is quantified with respect to both the lab and the overall project. Matrix spike duplicates (MSDs) are typically used by the lab whereas field duplicate samples, blind to the laboratory, are used to evaluate overall repeatability in the project. Precision results based on the field duplicate samples are given in Table 8-4 (by method); all duplicate values were within tolerance (40% RPD for solids, 30% RPD for liquids). The formula for RPD is also given.

Table 8-4. Precision Results by Method

	Asbestos	Metals	Metals (TCLP)	PCBs
Sample 1				
Sample 1 dupe				
RPD value (%)				

Table 8-4 will be completed when analytical data is returned.

Representativeness

The samples are representative of all potentially contaminated media visible within the 886 Cluster based on the following criteria:

- professional judgment of the sampling team
- walk-throughs and collaborations by and within the sampling team
- summary of the samples acquired and analyzed (Table 6-0)
- implementation of forensic Chain of Custody protocol
- compliance with sample preservation and holding times
- compliance with the RLCP (RMRS, 1997) - reviewed and approved by management consensus

RMRS quality assurance personnel performed surveillance 97-100 to verify compliance with the 886 Cluster RLCP. This surveillance used a checklist developed directly from the approved and controlled 886 Cluster RLCP. One deficiency was identified concerning the documentation of sampling equipment decontamination. This deficiency was resolved satisfactorily resolved prior to the completion of field sampling activities.

Comparability

Analytical results from this project are comparable with similar samples and media on a state-wide, nation-wide, or DOE-complex basis given the use of documented plans and procedures for sample collection and standardized EPA-approved methods for sample analysis.

Completeness

Completeness is typically defined as a percentage, calculated as the ratio of usable results to either 1) the number of samples planned or 2) the number of samples actually acquired for analysis. Because #1 is not applicable, the ratio with respect to #2 is the appropriate measure. Currently completeness of the data set is not available pending return of sample results. However, known data gaps due to components which have yet to be deactivated are listed below. The characterization will be performed and documented after these elements are deactivated.

- Bldg 888A - pending de-energization of the substations
- Assembly Hood - Pending deactivation
- Raschig Ring Tanks - Pending deactivation
- Glovebox - Pending deactivation

Completeness may be corroborated by referencing the associated quality records of analytical results, which include hardcopy data packages and electronic data deliverables (EDDs), managed by the K-H Analytical Projects Office.

9.0 INFORMATION SOURCES

886 Cluster as-built drawings

Site personnel

Task 3 and 4 Final Draft Report, Operations History, August 1992.

10.0 REFERENCES

Basis for Interim Operation Building 886, Revision 5, Kaiser-Hill 1997

Facility/Activity Responsibility Transfer Checklist, Building 886 Cluster Landlord Functions, RMRS 1997.

Guidance for Data Quality Assessment, Practical Methods for Data Analysis, EPA QA/G-9 (QA 96 Version), EPA, 1996

Historical Release Report, DOE 1992.

Reconnaissance Level Characterization Plan for the 886 Cluster Decommissioning Project, Revision 0, RMRS 1997.

11.0 APPENDICES

- A Radiological Characterization Surveys
- B Chemical Hazards Characterization Results
- C Certified Asbestos Inspector's Report

**RECONNAISSANCE LEVEL
CHARACTERIZATION
REPORT FOR THE
886 CLUSTER
DECOMMISSIONING
PROJECT**

APPENDICES A, B&C

**RF/RMRS-97-124.UN
Rev. 0**

DECEMBER 15, 1997

APPENDIX A

RADIOLOGICAL CHARACTERIZATION SURVEYS

RADIOLOGICAL DOSE SURVEY

Taken by Paul Muller Employee #: [REDACTED]
Signature

Taken by _____ Employee #: _____
Signature

Taken by _____ Employee #: _____
Signature

Date: <u>12-2-97</u> Building: <u>886</u>	Survey Description: <u>886-5W</u>
Time: <u>0900</u> Room#: <u>C-A</u>	
Shift: <u>DAY</u>	Diagram/Sketch Attached: <input checked="" type="checkbox"/> yes <input type="checkbox"/> no

INSTRUMENTATION USED

Mfg.:	<u>Eberline</u>	<u>Ludlum</u>
Model:	<u>RO 20</u>	<u>12-4</u>
Serial#:	<u>183</u>	<u>71534</u>
Date. Cal.:	<u>7-17-97</u>	<u>9-11-97</u>
Cal. Due.:	<u>1-17-98</u>	<u>3-11-98</u>
BKGRD:	<u>20.5</u>	<u>21.0</u>

COMMENTS

Status:

- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman:

[Signature]
Signature

Date: 12-3-97

RADIOLOGICAL DOSE SURVEY FORM

LOG NUMBER: 886-5W

	GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴		GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴
1	<0.5	<1.0	<1.5	N	N/A	39					N/A
2	<0.5	<1.0	<1.5	N	N/A	40					N/A
3	<0.5	<1.0	<1.5	N	N/A	41					N/A
4	<0.5	<1.0	<1.5	N	N/A	42					N/A
5	<0.5	<1.0	<1.5	N	N/A	43					N/A
6	<0.5	<1.0	<1.5	N	N/A	44					N/A
7	<0.5	<1.0	<1.5	N	N/A	45					N/A
8	<0.5	<1.0	<1.5	N	N/A	46					N/A
9	<0.5	<1.0	<1.5	N	N/A	47					N/A
10	<0.5	<1.0	<1.5	N	N/A	48					N/A
11	<0.5	<1.0	<1.5	N	N/A	49					N/A
12	<0.5	<1.0	<1.5	N	N/A	50					N/A
13	<0.5	<1.0	<1.5	N	N/A	51					N/A
14	<0.5	<1.0	<1.5	N	N/A	52					N/A
15	<0.5	<1.0	<1.5	N	N/A	53					N/A
16					N/A	54					N/A
17					N/A	55					N/A
18					N/A	56					N/A
19					N/A	57					N/A
20					N/A	58					N/A
21					N/A	59					N/A
22					N/A	60					N/A
23					N/A	61					N/A
24					N/A	62					N/A
25					N/A	63					N/A
26					N/A	64					N/A
27					N/A	65					N/A
28					N/A	66					N/A
29					N/A	67					N/A
30					N/A	68					N/A
31					N/A	69					N/A
32					N/A	70					N/A
33					N/A	71					N/A
34					N/A	72					N/A
35					N/A	73					N/A
36					N/A	74					N/A
37					N/A	75					N/A
38					N/A	76					N/A

Handwritten notes:
 18-22-97
 12-2-97


Handwritten notes:
 12-2-97

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 886

RBA & CA

Gamma-Neutron of Room 101,102,103



RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: **886-4W**

PWRE _____ ROUTINE X
 R.W.P. _____ OTHER _____

BUILDING/LOCATION: **886** ROOM#: _____ AS REQ'D
 DATE: **12-3-97** TIME: **1100**

ITEM DESCRIPTION: **C.A Floor survey**

Removable Contamination Counters			
Mfg:	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4
Serial #:	984	1158	SAC-4
Date Calib'd:	9-18-97	9-17-97	
Cal. due Date:	3-18-98	3-17-98	

Mfg:	Eberline	Eberline	Eberline
Model:	BC-4	BC-4	BC-4
Serial #:	BC 763	BC 869	BC-4
Date Calib'd:	10-6-97	9-29-97	
Cal. due Date:	4-6-98	3-29-98	

Total (Fixed + Removable) Survey Instruments			
Mfg:	NE Electra	NE Electra	Bicron
Model:	DP6	DP6	A-100
Serial #:			
Date Calib'd:			
Cal Due Date:			
Background:			
Efficiency:			

Mfg:	Ludlum	Ludlum
Model:	31	31
Serial #:		
Date Calib'd:		
Cal Due Date:		
Background:		
Efficiency:		

STATUS: _____ RELEASABLE _____ NOT RELEASABLE

_____ POSTED _____ NOT POSTED


WITHIN LIMITS _____ LIMITS EXCEEDED

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Control# 886-4W

Building 886



● TOTAL SURVEY POINTS

RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: 886-3W

PWIRE: _____ ROUTINE: OTHER: _____

BUILDING/LOCATION: 880 ROOM#: C.A.

DATE: 12-1-97 TIME: 1030

ITEM DESCRIPTION: Control pt Survey

Removable Contamination Counters	
Eberline	Eberline
SAC-4	SAC-4
984	1158
9-18-97	9-17-97
3-18-98	3-17-98

Eberline	Eberline	Eberline
BC-4	BC-4	BC-4
8C 763	8C 869	
10-6-97	9-29-97	
4-6-98	3-29-98	


Total (Fixed + Removable) Survey Instruments

Mfg:	NE Electra	NE Electra	Bicron	Bicron
Model:	DP6	DP6	A-100	A-100
Serial #:				
Date Calib'd:				
Cal Due Date:				
Background:				
Efficiency:				
Mfg:	Ludlum	Ludlum		
Model:	31	31		
Serial #:				
Date Calib'd:				
Cal Due Date:				
Background:				
Efficiency:				

STATUS: _____ RELEASABLE _____ NOT RELEASABLE

_____ POSTED _____ NOT POSTED

WITHIN LIMITS _____ LIMITS EXCEEDED




ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Page 3 of 3

Control# 886-2W



12 TOTAL SURVEY POINTS

RADIOLOGICAL OPERATIONS CONTAMINATION SURVEY FORM

LOG# 886-2W
 Survey results (DPM/100CM2)

Survey results (DPM/100CM2)

Swipe #	Location/description	Removable			Total Alpha 60 sec count	Total Beta/ Gamma
		Alpha	Beta/ Gamma			
1	See map	< 18	< 205			
2	" "	< 18	< 205			
3	" "	< 18	< 205			
4	" "	< 18	< 205			
5	" "	< 18	< 205			
6	" "	< 18	< 205			
7	" "	< 18	< 205			
8	" "	< 18	< 205			
9	" "	< 18	< 205			
11	" "	< 18	< 205			
12	" "	< 18	< 205			
13	" "	< 18	< 205			
14	" "	< 18	< 205			
15	" "	< 18	< 205			
16	" "	< 18	< 205			
17	" "	< 18	< 205			
18	" "	< 18	< 205			
19	" "	< 18	< 205			
20	" "	< 18	< 205			
21	" "	< 18	< 205			

Swipe #	Location/description	Removable			Total Alpha 60 sec count	Total Beta/ Gamma
		Alpha	Beta/ Gamma			
<i>PM</i>						
<i>1-92</i>						

RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: 886-2W

P/WRE _____ ROUTINE OTHER _____

BUILDING/LOCATION: 880/CARGO CONTAIN. ROOM#: SEE ATTACHED

DATE: 11-6-97 TIME: 1400

ITEM DESCRIPTION: FLOOR SURVEY OF BLDG. 880 AND TWO CARGO CONTAINERS AND THE GRAY TRAILER R.M.A AREAS ONLY.

Mfg:		Removable Contamination Counters	
Model:	Eberline	Eberline	Eberline
Serial #:	SAC-4	SAC-4	SAC-4
Date Calib'd:	984	1158	961
Cal. due Date:	9-18-97	9-17-97	6-25-97
	3-18-98	3-17-98	12-25-97

Mfg:		Removable Contamination Counters	
Model:	Eberline	Eberline	Eberline
Serial #:	BC-4	BC-4	BC-4
Date Calib'd:			
Cal. due Date:			

COMMENTS:

Total (Fixed + Removable) Survey Instruments

Mfg:	Model:	Serial #:	Date Calib'd:	Cal Due Date:	Background:	Efficiency:
NE Electra	DP6					
NE Electra	DP6					
Bicron	A-100					
Bicron	A-100					
Ludlum	31					
Ludlum	31					
Ludlum	31					
N/A	N/A					

STATUS:

RELEASABLE NOT RELEASABLE

POSTED NOT POSTED

WITHIN LIMITS LIMITS EXCEEDED



RADIOLOGICAL OPERATIONS COTAMINATION SURVEY FORM

Survey results (DPM/100CM2)

LOG# _____ Survey results (DPM/100CM2)


Swipe #	Location/description	Removable		Total Alpha 60 sec count	Total Beta/Gamma
		Alpha	Beta/Gamma		
<i>Rm 11-6-97</i>					

Swipe #	Location/description	Removable		Total Alpha 60 sec count	Total Beta/Gamma
		Alpha	Beta/Gamma		
1	See map	< 18			
2	"	< 18			
3	"	< 18			
4	"	< 18			
5	"	< 18			
6	"	< 18			
7	"	< 18			
8	"	< 18			
9	"	< 18			
10	"	< 18			
11	"	< 18			
12	"	< 18			
<i>Rm 11-6-97</i>					

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Control# 886-2W



RADIOLOGICAL DOSE SURVEY

Taken by Paul Muller Employee #: 
Signature

Taken by _____ Employee #: _____
Signature

Taken by _____ Employee #: _____
Signature

Date: 11-4-97 Building: 886 Survey Description: 886-5W
Time: 1030 Room#: CA
Shift: DAY Diagram/Sketch Attached: yes no

INSTRUMENTATION USED

Mfg.:	<u>Ludlum</u>	<u>Eberline</u>
Model:	<u>12-4</u>	<u>RO 20</u>
Serial#:	<u>91015</u>	<u>191</u>
Date. Cal.:	<u>8-19-97</u>	<u>7-16-97</u>
Cal. Due.:	<u>2-19-98</u>	<u>1-16-98</u>
BKGRD:	<u>21.0</u>	<u>20.5</u>

COMMENTS

Status:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman:

Paul Muller Date: 11/4/97
Signature

RADIOLOGICAL DOSE SURVEY FORM

LOG NUMBER 886-5W

GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴		GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴
1	<0.5	<1.0	<1.5	N	N/A	39				N/A
2	<0.5	<1.0	<1.5	N	N/A	40				N/A
3	<0.5	<1.0	<1.5	N	N/A	41				N/A
4	<0.5	<1.0	<1.5	N	N/A	42				N/A
5	<0.5	<1.0	<1.5	N	N/A	43				N/A
6	<0.5	<1.0	<1.5	N	N/A	44				N/A
7	<0.5	<1.0	<1.5	N	N/A	45				N/A
8	<0.5	<1.0	<1.5	N	N/A	46				N/A
9	<0.5	<1.0	<1.5	N	N/A	47				N/A
10	<0.5	<1.0	<1.5	N	N/A	48				N/A
11	<0.5	<1.0	<1.5	N	N/A	49				N/A
12	<0.5	<1.0	<1.5	N	N/A	50				N/A
13	<0.5	<1.0	<1.5	N	N/A	51				N/A
14	<0.5	<1.0	<1.5	N	N/A	52				N/A
15	<0.5	<1.0	<1.5	N	N/A	53				N/A
16					N/A	54				N/A
17					N/A	55				N/A
18					N/A	56				N/A
19					N/A	57				N/A
20					N/A	58				N/A
21					N/A	59				N/A
22					N/A	60				N/A
23					N/A	61				N/A
24					N/A	62				N/A
25					N/A	63				N/A
26					N/A	64				N/A
27					N/A	65				N/A
28					N/A	66				N/A
29					N/A	67				N/A
30					N/A	68				N/A
31					N/A	69				N/A
32					N/A	70				N/A
33					N/A	71				N/A
34					N/A	72				N/A
35					N/A	73				N/A
36					N/A	74				N/A
37					N/A	75				N/A
38					N/A	76				N/A

Handwritten signature

Handwritten signature

Handwritten signature


Handwritten signature

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 886

RBA & CA

Gamma-Neutron of Room 101,102,103



RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER:	886-1D		
P/WIRE	ROUTINE	OTHER	XX
BUILDING/LOCATION	ROOM#:	AS REQ'D	
886			
DATE:	TIME:		
11-6-97			
ITEM DESCRIPTION:	Daily SOP control point survey.		
COMMENTS:			

Removable Contamination Counters			
Mfg:	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4
Serial #:	989	1158	961
Date Calib'd:	9-18-97	9-17-97	6-25-97
Cal. due Date:	3-18-98	3-17-98	12-25-97

Total (Fixed + Removable) Survey Instruments			
Mfg:	NE Electra	NE Electra	Bicron
Model:	DP6	DP6	A-100
Serial #:			
Date Calib'd:			
Cal Due Date:			
Background:			
Efficiency:			

Mfg:	Ludlum	Ludlum
Model:	31	31
Serial #:		
Date Calib'd:		
Cal Due Date:		
Background:		
Efficiency:	N/A	N/A

STATUS: RELEASABLE NOT RELEASABLE

POSTED NOT POSTED

WITHIN LIMITS


ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Page 3 of 3

Control# 886-4W

Building 886



● TOTAL SURVEY POINTS

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____
Employee #: [REDACTED]

Taken by [Signature]
Signature
Taken by _____
Signature
Taken by _____
Signature

Employee #: _____
Employee #: _____

Date: <u>10-19-94</u> Building: <u>886</u> Time: <u>1300</u> Room: <u>103</u> Shift: <u>Days</u>	Survey Description: <u>Overhead Survey Rm# 103</u> Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
--	---

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	_____	_____
Model:	31	12-1A	_____	_____
Serial#:	_____	<u>62753</u>	_____	_____
Date Cal.:	_____	<u>6-94</u>	_____	_____
Cal. Due:	_____	<u>12-94</u>	_____	_____
BKGRD:	_____	<u>6250</u>	_____	_____

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposted

Radiological Operations Foreman

[Signature] Date: 10-26-94
Signature

RADIOLOGICAL OPERATIONS
Alpha Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			RESURVEY		
CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (Smear)	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (Smear)
1	<250		1		
2	<250		2		
3	<250		3		
4	<250		4		
5	<250		5		
6	<250		6		
7	<250		7		
8	<250		8		
9	<250		9		
10	<250		10		
11	<250		11		
12	<250		12		
13	<250		13		
14	<250		14		
15	<250		15		
16	<250		16		
17	<250		17		
18	<250		18		
19	<250		19		
20	<250		20		
21	<250		21		
22	<250		22		
23	<250		23		
24	<250		24		
25	<250		25		
26	<250		26		
27	<250		27		
28	<250		28		
29	<250		29		
30	<250		30		
31	<250		31		
32	<250		32		
33	<250		33		
34	<250		34		
35	<250		35		
36	<250		36		
37	<250		37		
38	<250		38		
39	<250		39		
40	<250		40		
41	<250		41		
42	<250		42		
43	<250		43		
44	<250		44		
45	<250		45		

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey


RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46	<250		46		
47	<250		47		
48	<250		48		
49			49		
50			50		
51			51		
52			52		
53			53		
54			54		
55			55		
56			56		
57			57		
58			58		
59			59		
60			60		
61			61		
62			62		
63			63		
64			64		
65			65		
66			66		
67			67		
68			68		
69			69		
70			70		
71			71		
72			72		
73			73		
74			74		
75			75		
76			76		
77			77		
78			78		
79			79		
80			80		
81			81		
82			82		
83			83		
84			84		
85			85		
86			86		
87			87		
88			88		
89			89		
90			90		

**Radiological Operations
Area or Equipment Drawing Showing Survey Points**

ROOM# 103 BUILDING 886



RADIOLOGICAL OPERATIONS

Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: <u>9-17-94</u> Building: <u>886</u>	Survey Description: <u>Baseline Survey</u>
Time: <u>1500</u> Room: <u>103 Pit</u>	<u>of 103 Pit</u>
Shift: <u>Day</u>	Diagram/Sketch Attached: yes <u>X</u> no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>	<u>810</u>			
Date Cal.:	<u>10-5-93</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	<u>31</u>	<u>12-1A</u>		
Serial#:		<u>42744</u>		
Date Cal.:		<u>4-94</u>		
Cal. Due:		<u>10-94</u>		
BKGRD:		<u><250</u>		

COMMENTS: Survey points #23+24 have been deconned
23 - 93 dpm # 24 - 27 dpm

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

[Signature]
Signature

Date: 9/20/94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1	<250	<250	30			21
2	<250	<250	21			9
3	<250	<250	39			0
4	<250	<250	63			0
5	<250	<250	45			15
6	<250	25,000	24			0
7	<250	<250	36			0
8	<250	<250	93			0
9	<250	50,000	54			0
10	<250	<250	66			6
11	<250	<250	18			9
12	<250	<250	48			0
13	<250	<250	54			3
14	<250	<250	66			6
15	<250	<250	18			9
16	<250	<250	48			0
17	<250	<250	54			3
18	<250	<250	72			12
19	<250	<250	102			4
20	<250	<250	60			12
21	<250	<250	42			0
22	<250	<250	21			0
23	<250	<250	318			0
24	<250	<250	240			0
25	<250	<250	57			9
26	<250	<250	27			5
27	<250	<250	36			0
28	<250	<250	21			0
29	<250	<250	57			0
30	<250	<250	27			0
31	<250	<250	36			0
32	<250	<250	21			18
33	<250	<250	57			3
34	<250	<250	36			9
35	<250	<250	54			36
36	<250	<250	27			12
37	<250	<250	24			0
38	<250	<250	24			0
39	<250	<250	12			0
40	<250	<250	12			27
41	<250	<250	45			0
42	<250	<250	60			0
43	<250	<250	51			15
44	<250	<250	57			12
45	<250	<250	48			9



RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
46	<250	<250	15	46		24
47	<250	<250	27	47		0
48	<250	<250	21	48		12
49	<250	10 ⁶	27	49		6
50	<250	<250	42	50		0
51	<250	<250	99	51		0
52	<250	<250	45	52		3
53	<250	<250	15	53		21
54	<250	<250	36	54		9
55	<250	<250	3	55		15
56	<250	<250	6	56		0
57	<250	<250	45	57		0
58	<250	<250	9	58		12
59	<250	<250	42	59		15
60	<250	<250	36	60		3
61	<250	<250	15	61		0
62	<250	<250	6	62		0
63	<250	<250	12	63		0
64	<250	<250	15	64		0
65	<250	<250	105	65		15
66	<250	<250	90	66		39
67	<250	<250	12	67		3
68	<250	<250	45	68		0
69	<250	<250	150	69		0
70	<250	<250	33	70		0
71	<250	<250	57	71		0
72	<250	<250	27	72		9
73	<250	<250	36	73		6
74	<250	<250	21	74		15
75	<250	<250	57	75		0
76	<250	<250	36	76		3
77	<250	<250	54	77		0
78	<250	<250	27	78		0
79	<250	<250	24	79		0
80	<250	<250	24	80		12
81	<250	<250	12	81		21
82	<250	<250	12	82		9
83	<250	<250	45	83		3
84	<250	<250	60	84		3
85	<250	10 ⁶	51	85		0
86	<250	<250	57	86		0
87	<250	10 ⁶	48	87		0
88	<250	10 ⁶	15	88		6
89	<250	<250	27	89		9
90	<250	<250	21	90		0

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
91	<250	<250	21		0
92	<250	<250	36		0
93	<250	<250	27		6
94	<250	<250	21		12
95	<250	<250	45		0
96	<250	<250	21		0
97	<250	<250	24		9
98	<250	<250	12		3
99	<250	<250	45		0
100	<250	<250	60		0
101	<250	<250	72		0
102	<250	<250	93		6
103	<250	<250	54		18
104	<250	<250	48		0
105	<250	<250	15		39
106	<250	<250	36		6
107	<250	<250	21		3
108	<250	<250	102		0
109	<250	<250	15		0
110	<250	<250	9		0
111	<250	<250	6		9
112	<250	<250	3		15
113	<250	<250	21		0
114	<250	<250	15		3
115	<250	<250	9		6
116	<250	<250	12		21
117	<250	<250	36		6
118	<250	<250	18		18
119	<250	<250	54		0
120	<250	<250	36		0
121	<250	<250	12		3
122	<250	<250	27		0
123	<250	<250	30		6
124	<250	<250	33		0
125	<250	<250	45		0
126	<250	<250	21		0
127	<250	<250	57		3
128	<250	<250	36		6
129	<250	<250	21		15
130	<250	<250	27		36
131	<250	<250	18		0
132	<250	<250	9		6
133	<250	<250	15		3
134	<250	<250	24		3
135	<250	<250	12		6




RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
136	<250	<250	42			3
137	<250	<250	6			6
138	<250	<250	12			0
139	<250	<250	39			0
140	<250	<250	33			3
141	<250	<250	42			3
142	<250	<250	54			0
143	<250	<250	18			9
144	<250	<250	66			12
145	<250	<250	27			0
146	<250	<250	12			0
147	<250	<250	60			15
148	<250	<250	42			0
149	<250	<250	54			0
150	<250	<250	36			0
151	<250	<250	27			15
152	<250	<250	9			12
153	<250	<250	12			3
154	<250	<250	21			0
155						
156						
157						
158						
159						
160						
161						
162						
163						
164						
165						
166						
167						
168						
169						
170						
171						
172						
173						
174						
175						
176						
177						
178						
179						
180						

RADIATION PROTECTION
AREA OR EQUIPMENT DRAWING SHOWING SURVEY POINTS



103 PIT BASELINE SURVEY

154 total survey points

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: <u>10-27-94</u>	Building: <u>B86</u>	Survey Description: <u>Overhead Survey of walk-in glove box</u>
Time: <u>0430</u>	Room: <u>103</u>	Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
Shift: <u>Day</u>		

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	_____	_____
Model:	31	12-1A	_____	_____
Serial#:	_____	<u>6348</u>	_____	_____
Date Cal.:	_____	<u>10-94</u>	_____	_____
Cal. Due:	_____	<u>4-95</u>	_____	_____
BKGRD:	_____	<u>250</u>	_____	_____

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposited

Radiological Operations Foreman

[Signature]
Signature

Date: 11-2-94

RADIOLOGICAL OPERATIONS
Alpha Survey


RESULTS

Date: 10-27-94 Time: 0930 Building: 886 Room: 103

ALPHA			RESURVEY		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1	<250		1		
2	<250		2		
3	<250		3		
4	<250		4		
5	<250		5		
6	<250		6		
7	<250		7		
8	<250		8		
9	<250		9		
10	<250		10		
11	<250		11		
12	<250		12		
13	<250		13		
14	<250		14		
15	<250		15		
16	<250		16		
17	<250		17		
18	<250		18		
19			19		
20			20		
21			21		
22			22		
23			23		
24			24		
25			25		
26			26		
27			27		
28			28		
29			29		
30			30		
31			31		
32			32		
33			33		
34			34		
35			35		
36			36		
37			37		
38			38		
39			39		
40			40		
41			41		
42			42		
43			43		
44			44		
45			45		

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Overhead Survey of walk-in Glove box Rm#103



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: 10-27-94 Building: 886
Time: 1000 Room: 103
Shift: Day

Survey Description: wall Survey of
walk-in Glove box Rm# 103
Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:					
Date Cal.:					
Cal. Due:					

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:					
Date Cal.:					
Cal. Due:					

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:		6348		
Date Cal.:		10-94		
Cal. Due:		4-95		
BKGRD:		6250		

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 11-2-94

RADIOLOGICAL OPERATIONS
Alpha Survey

RESULTS

Date: 10-27-44 Time: 1000 Building: 886 Room: 103

	ALPHA			RESURVEY		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1	<250					
2	<250					
3	<250					
4	<250					
5	<250					
6	<250					
7	<250					
8	<250					
9	<250					
10	<250					
11	<250					
12	<250					
13	<250					
14	<250					
15	<250					
16	<250					
17	<250					
18	<250					
19	<250					
20	<250					
21	<250					
22	<250					
23	<250					
24	<250					
25	<250					
26	<250					
27	<250					
28	<250					
29	<250					
30	<250					
31	<250					
32	<250					
33	<250					
34	<250					
35	<250					
36	<250					
37	<250					
38	<250					
39	<250					
40	<250					
41	<250					
42	<250					
43	<250					
44	<250					
45	<250					

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey


RESULTS

Date: 10-27-94 Time: 1000 Building: 886 Room: 103

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46	<250		46		
47	<250		47		
48	<250		48		
49	<250		49		
50	<250		50		
51	<250		51		
52	<250		52		
53	<250		53		
54	<250		54		
55	<250		55		
56	<250		56		
57	<250		57		
58	<250		58		
59	<250		59		
60	<250		60		
61	<250		61		
62	<250		62		
63	<250		63		
64			64		
65			65		
66			66		
67			67		
68			68		
69			69		
70			70		
71			71		
72			72		
73			73		
74			74		
75			75		
76			76		
77			77		
78			78		
79			79		
80			80		
81			81		
82			82		
83			83		
84			84		
85			85		
86			86		
87			87		
88			88		
89			89		
90			90		

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Walk-In Glove Box
Rm # 103 walls



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey



Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by [Signature]
Signature

Employee #: [REDACTED]

Date: 8-2-94 Building: 886
Time: 1500 Room: 103
Shift: DAYS

Survey Description:
Base Line Rm 103
Diagram/Sketch Attached: yes ___ no ___

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>				
Date Cal.:	<u>10-5-93</u>				
Cal. Due:	<u>10-92</u>				

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>				
Date Cal.:	<u>10-1-93</u>				
Cal. Due:	<u>10-94</u>				

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 8-5-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-2-94 Time: 1500 Building: 886 Room: 103

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (smear)
1		3	1		3
2		15	2		<BKG
3		0	3		27
4		9	4		21
5		21	5		<BKG
6		9	6		36
7		6	7		27
8		15	8		24
9		18	9		6
10		27	10		<BKG
11		9	11		<BKG
12		30	12		60
13		39	13		24
14		12	14		30
15		18	15		<BKG
16		9	16		<BKG
17		15	17		3
18		30	18		<BKG
19		6	19		54
20		0	20		9
21		9	21		3
22		27	22		15
23		96	23		18
24		3	24		12
25		9	25		<BKG
26		0	26		<BKG
27		21	27		<BKG
28		0	28		21
29		18	29		12
30		12	30		18
31		27	31		48
32		33	32		<BKG
33		3	33		18
34		9	34		9
35		9	35		42
36		540	36		60
37		57	37		18
38		30	38		21
39		51	39		<BKG
40		24	40		<BKG
41		18	41		12
42		3	42		36
43		6	43		12
44		0	44		<BKG
45		18	45		<BKG

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS


Date: 8-2-94 Time: 1500 Building: 886 Room: 103

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46		12	46		15
47		6	47		<BKG
48		0	48		<BKG
49		9	49		<BKG
50		3	50		<BKG
51		0	51		15
52		0	52		<BKG
53		3	53		12
54		9	54		<BKG
55		3	55		<BKG
56		37	56		30
57		3	57		<BKG
58		15	58		6
59		18	59		<BKG
60		24	60		<BKG
61		30	61		3
62		3	62		62 #42
63		6	63		<BKG
64		3	64		<BKG
65		24	65		21
66		105	66		21
67		96	67		12
68		15	68		6
69		21	69		<BKG
70		15	70		<BKG
71		3	71		12
72		15	72		15
73		123	73		<BKG
74		3	74		<BKG
75		9	75		3
76		15	76		<BKG
77		102	77		3
78		6	78		21
79		6	79		<BKG
80		0	80		<BKG
81			81		
82			82		
83			83		
84			84		
85			85		
86			86		
87			87		
88			88		
89			89		
90			90		




EG&G ROCKY FLATS

Radiation Protection
Area or Equipment Drawing Showing Survey Points.



G&G ROCKY FLATS

Radiation Protection
Area or Equipment Drawing Showing Survey Points



Alpha - Beta Survey

Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by *[Signature]*
Signature

Employee #: 

Date: 7-28-94 Building: 880

Survey Description: _____

Time: 1340 Room: 103

Baseline Rm 103

Shift: Days

Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>				
Date Cal.:	<u>10-5-93</u>				
Cal. Due:	<u>10-94</u>				

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>				
Date Cal.:	<u>10-1-93</u>				
Cal. Due:	<u>10-94</u>				

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:	<u>82806</u>	<u>96781</u>			
Date Cal.:	<u>10-93</u>	<u>6-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			
BKGRD:	<u>75</u>	<u>2250</u>			

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

[Signature]
Signature

Date: 7/29/94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 7-29-94 Time: 1340 Building: 886 Room: 103

ALPHA

BETA

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1		12	1		<BKG
2		21	2		<BKG
3		33	3		<BKG
4		18	4		<BKG
5		21	5		<BKG
6		12	6		<BKG
7		6	7		6
8		12	8		<BKG
9		3	9		<BKG
10		9	10		<BKG
11		18	11		<BKG
12		63	12		<BKG
13		3	13		21
14		39	14		<BKG
15		6	15		<BKG
16		36	16		<BKG
17		9	17		<BKG
18		6	18		<BKG
19		30	19		36
20		31	20		9
21		18	21		6
22		36	22		<BKG
23		12	23		<BKG
24		15	24		<BKG
25		9	25		<BKG
26		6	26		6
27		3	27		<BKG
28		9	28		33
29		3	29		<BKG
30		3	30		18
31		9	31		3
32		6	32		27
33		15	33		<BKG
34		6	34		<BKG
35		3	35		3
36		3	36		12
37		3	37		<BKG
38		0	38		<BKG
39		9	39		<BKG
40		9	40		<BKG
41		9	41		<BKG
42		45	42		<BKG
43		24	43		33
44		6	44		45
45		0	45		21

Floor

Table

✓

RADIOLOGICAL MONITORING
Contamination Survey


RESULTS

	Initial			Resurvey			
	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (Smear)	Date Completed: 7-29-94	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (Smear)
Table	46.		18	46.			24
	47.		15	47.			6
	48.		42	48.			6
	49.		9	49.			51
	50.		177	50.			<8K6
Pig	51.		156	51.			45
	52.		15	52.			12
Trunk Ho-3	53.		9	53.			<8K6
	54.		9	54.			<8K6
Glove Box	55.		15	55.			9
	56.		15	56.			<8K6
	57.		6	57.			<8K6
	58.		12	58.			<8K6
	59.		0	59.			3
	60.		21	60.			<8K6
	61.		15	61.			6
	62.		159	62.			15
	63.		93	63.			60
	64.		9	64.			<8K6
	65.		3	65.			<8K6
	66.		78	66.			3
	67.		3	67.			<8K6
	68.		9	68.			<8K6
	69.		24	69.			<8K6
70.		15	70.			3	
71.		18	71.			<8K6	
Hood	72.		42	72.			3
	73.		21	73.			21
Table of 80ml	74.		6	74.			<8K6
	75.		6	75.			<8K6
C-cell	76.		9	76.			<8K6
	77.		9	77.			<8K6
	78.		36	78.			<8K6
	79.			79.			
	80.			80.			
	81.			81.			
	82.			82.			
	83.			83.			
	84.			84.			
	85.			85.			
	86.			86.			
	87.			87.			
	88.			88.			
	89.			89.			
	90.			90.			

✓

E G & G ROCKY FLATS

Radiation Protection
Area or Equipment Drawing Showing Survey Points.



GAMMA NEUTRON SURVEY

Control # 6B
Page 1 of 3

Taken by: _____ / _____ Emp. # _____
Signature Printed Name

Taken by: KL Creason / KL Creason Emp. # _____
Signature Printed Name

Taken by: T. CREASON / T.A. CREASON Emp. # _____
Signature Printed Name

Date: 7-18-94 Building 771^{CB} 686
 Time: 1000 Room #: 114^{CB} 103
 Shift: Days Area: Whole room

Survey Description: General area room 103
 Gamma / Neutron Survey Bldg 686
 Diagram/Sketch Attached: Yes No

INSTRUMENTATION USED

Mfg:	<u>Ludlum</u>	<u>Victoreen</u>	<u>Victoreen</u>	_____	_____
Model:	<u>12-4</u>	<u>450-6</u>	<u>40-B</u>	_____	_____
Serial #:	<u>9107</u>	<u>196</u>	<u>553</u>	_____	_____
Date Perf. Test	<u>7-18-94</u>	<u>7-18-94</u>	<u>7-18-94</u>	_____	_____
Date Calib'd:	<u>2-28-94</u>	<u>4-5-94</u>	<u>6-29-94</u>	_____	_____
Cal. Due Date:	<u>8-94</u>	<u>10-94</u>	<u>12-94</u>	_____	_____
Background:	<u>0.0</u>	<u>0.01</u>	<u>0.01</u>	_____	_____

Survey points 1-11
are of the 686,

 Survey points 12-14
are of the
rough cabinets.

COMMENTS

Survey point 15
is of core hood

Survey point 16+17
are of tank 446

Survey points 18+19 are of tank 447
 Survey points 20+21 are tank 441
 Survey points 22+23 are tank 442
 Survey points 24+25 are tank 443
 Survey points 26+27 are tank 444
 Survey points 28+29 are tank 445

STATUS:
 WITHIN LIMITS
 LIMITS EXCEEDED
 POSTED
 DEPOSTED

Survey points 30-33
are isle ways between tanks.

Radiological Operations Foreman Review:
Curtis Bear 7-18-94
 Signature Date

GAMMA AND NEUTRON SURVEY


Control # _____
Page _____ of _____

RESULTS

mrem/h				Area Posted (Y/N)	mrem/h				Area Posted (Y/N)
Gamma	Neutron	Total			Beta/ Gamma	Neutron	Total		
1.	0.10	0.0	0.10	N	1.074	0.10			
2.	0.20	0.1	0.30	N	2.48	0.21			
3.	0.08	0.0	0.08	N	3.427	0.10			
4.	0.30	0.1	0.40	N	4.421	0.25			
5.	0.10	0.0	0.10	N	5.424	0.10			
6.	0.30	0.0	0.30	N	6.502	0.20			
7.	0.50	0.0	0.50	N	7.584	0.30			
8.	0.40	0.0	0.40	N	8.682	0.20			
9.	0.20	0.0	0.20	N	9.782	0.10			
10.	0.20	0.0	0.20	N	10.884	0.10			
11.	0.10	0.0	0.10	N	11.982	0.05			
12.	0.10	0.0	0.10	N	12.982	0.10			
13.	0.05	0.1	0.15	N	13.982	0.06			
14.	0.03	0.0	0.03	N	14.982	0.05			
15.	0.06	0.0	0.06	N	15.982	0.05			
16.	0.25	0.0	0.25	N	16.982	0.18			
17.	0.30	0.0	0.30	N	17.982	0.20			
18.	2.40	0.10	2.50	N	18.982	0.18			
19.	2.80	0.20	3.00	N	19.982	0.20			
20.	2.70	0.00	2.70	N	20.982	2.40			
21.	2.60	0.00	2.60	N	21.982	2.20			
22.	3.40	0.1	3.50	N	22.982	2.40			
23.	3.0	0.1	3.10	N	23.982	2.20			
24.	2.30	0.0	2.30	N	24.982	1.60			
25.	2.50	0.0	2.50	N	25.982	1.250			
26.	2.20	0.0	2.20	N	26.982	1.80			
27.	2.00	0.0	2.00	N	27.982	1.60			
28.	2.30	0.2	2.50	N	28.982	1.80			
29.	2.20	0.1	2.30	N	29.982	1.30			
30.	0.40	0.0	0.40	N	30.982	0.30			
31.	0.80	0.0	0.80	N	31.982	0.60			
32.	1.0	0.0	1.00	N	32.982	0.80			
33.	1.8	0.0	1.80	N	33.982	1.43			
34.					78.				
35.					79.				
36.					80.				
37.					81.				
38.					82.				
39.					83.				
40.					84.				
41.					85.				
42.					86.				
43.					87.				
44.					88.				

EG&G ROCKY FLATS

Radiation Protection
Area or Equipment Drawing Showing Survey Points



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #:

Taken by

Signature

Employee #: [REDACTED]

Taken by

Signature

Employee #: [REDACTED]

Taken by

Signature

Employee #: [REDACTED]

Date: 11-29-94 Building: 886

Survey Description: Airlock of Doghouse

Time: 1455 Room: 101

Shift: Day

Diagram/Sketch Attached: yes no

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:					
Date Cal.:					
Cal. Due:					

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:					
Date Cal.:					
Cal. Due:					

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:				
Date Cal.:				
Cal. Due:				
BKGRD:				

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

Signature

Date: 11-30-94

RADIOLOGICAL OPERATIONS
Alpha Survey

RESULTS


Date: 11-29-94 Time: 1455 Building: 886 Room: Doghouse

	ALPHA			RESURVEY		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1	1000			6250		
2	1250			6250		
3	1000			6250		
4	1500			6250		
5	1000			6250		
6	1500			6250		
7	1500			6250		
8	1500			6250		
9	1000			6250		
10	1000			6250		
11	1000			6250		
12	1000			6250		
13	750			6250		
14	750			6250		
15	500			6250		
16	500			6250		
17						
18						
19						
20						
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Airlock to the Doghouse Rm# 101

Doghouse



(16) total Survey points

RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER:

96-881-6337

P/WRE

ROUTINE

R/WP

OTHER

✓ R-7-96

BUILDING/LOCATION

ROOM#:

886 / DOORHOUSE

101

DATE:

TIME:

10-7-96

1530

ITEM DESCRIPTION:

REMOVABLE SURVEY

OF AIRLOCK + DOORHOUSE RM 101

COMMENTS:

ALL SURVEYS TAKEN WITH

12-14 AIDS

Limits were exceeded on the
RWP Suspension Guide limits
however the area was already
posted as an H.C.A

STATUS:

RELEASABLE

NOT RELEASABLE

POSTED

NOT POSTED

WITHIN LIMITS

LIMITS EXCEEDED

Removable Contamination Counters

Mfg:	Eberline	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4	SAC-4
Serial #:				
Date Calib'd:				
Cal. due Date:				

Mfg:	Eberline	Eberline	Eberline	Eberline
Model:	BC-4	BC-4	BC-4	BC-4
Serial #:				
Date Calib'd:				
Cal. due Date:				

Total (Fixed + Removable) Survey Instruments

Mfg:	NE Electra	NE Electra	Bicron	Bicron
Model:	DP6	DP6	A-100	A-100
Serial #:				
Date Calib'd:				
Cal Due Date:				
Background:				
Efficiency:				

Mfg:	Ludlum	Ludlum	KODAK	KODAK
Model:	31	31	12-1A	12-1A
Serial #:			63480	63480
Date Calib'd:			1-84	1-84
Cal Due Date:			1-92	1-92
Background:			< 250	< 250
Efficiency:			N/A	N/A

RADIOLOGICAL OPERATIONS

Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: 10-10-94 Building: 086

Survey Description: _____

Time: 1030 Room: 101

Split table in Rm#101

Shift: Day

Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-94</u>	<u>6-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-93</u>	<u>4-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:	<u>61629</u>	<u>56127</u>		
Date Cal.:	<u>6-94</u>	<u>6-94</u>		
Cal. Due:	<u>6-95</u>	<u>12-94</u>		
BKGRD:	<u>50cpm</u>	<u>5250</u>		

COMMENTS:

STATUS:


- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 10-10-94

Area or Equipment Drawing Showing Survey Points



RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-10-94 Time: 1030 Building: 886 Room: 101 / spl. table

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1	<250	<250	0	<1894		3
2	<250	<250	15	<1894		0
3	<250	<250	45	<1894		63
4	<250	<250	6	<1894		18
5	<250	<250	66	<1894		27
6	<250	<250	3	<1894		0
7	<250	<250	9	<1894		12
8	<250	<250	21	<1894		21
9	<250	<250	15	<1894		9
10	<250	<250	12	<1894		6
11	<250	<250	3	<1894		12
12	<250	<250	15	<1894		0
13	<250	<250	69	<1894		30
14	<250	<250	6	<1894		0
15	<250	<250	30	<1894		0
16	<250	<250	18	<1894		0
17	<250	<250	12	<1894		0
18	<250	<250	21	<1894		6
19	<250	<250	12	<1894		0
20	<250	<250	27	<1894		0
21						
22						
23						
24						
25						
26						
27						
28						
29						
30						
31						
32						
33						
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						



RADIOLOGICAL OPERATIONS
 Alpha - Beta Survey

Control #: _____

Taken by _____
 Signature _____

Employee #: _____

Taken by _____
 Signature _____

Employee #: _____

Taken by *[Signature]*
 Signature _____

Employee #: [REDACTED]

Date: 10-10-94 Building: 886
 Time: 1315 Room: 101
 Shift: Days

Survey Description:
Smear Survey of top of Dog House
 Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-27-94</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:		<u>56191</u>			
Date Cal.:		<u>4-21-94</u>			
Cal. Due:		<u>10-94</u>			
BKGRD:		<u>2250</u>			

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposted

Radiological Operations Foreman

[Signature]
 Signature

Date: 10-10-94

RADIOLOGICAL OPERATIONS

Alpha-Beta Survey

RESULTS

Date: 10-10-94 Time: 1315 Building: 886 Room: 101

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1	<250	18	1		18
2	<250	15	2		3
3	<250	6	3		30
4	<250	12	4		21
5	<250	6	5		3
6	<250	9	6		0
7	<250	27	7		0
8	<250	9	8		18
9	<250	36	9		12
10	<250	12	10		0
11	<250	12	11		15
12	<250	33	12		100
13	<250	18	13		0
14	<250	6	14		42
15	<250	30	15		18
16	<250	15	16		0
17	<250	42	17		0
18	<250	12	18		21
19	<250	6	19		0
20	<250	9	20		0
21	<250	3	21		0
22	<250	12	22		3
23	<250	18	23		18
24	<250	27	24		0
25	<250	9	25		39
26	<250	6	26		0
27	<250	6	27		80
28	<250	24	28		0
29	<250	18	29		21
30	<250	3	30		9
31	<250	12	31		3
32	<250	6	32		6
33	<250	24	33		0
34	<250	27	34		0
35	<250	6	35		12
36	<250	15	36		9
37	<250	21	37		0
38	<250	21	38		9
39	<250	21	39		39
40	<250	33	40		0
41	<250	24	41		12
42	<250	21	42		0
43	<250	18	43		9
44	<250	21	44		18
45	<250	33	45		3

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey





RESULTS

Date: 10-10-99 Time: 1315 Building: 886 Room: 101


	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46	4250		24			0
47	4250		21			9
48	4250		33			24
49	4250		18			18
50	4250		27			0
51	4250		3			0
52	4250		12			15
53	4250		6			0
54	4250		3			12
55	4250		3			0
56	4250		9			15
57						
58						
59						
60						
61						
62						
63						
64						
65						
66						
67						
68						
69						
70						
71						
72						
73						
74						
75						
76						
77						
78						
79						
80						
81						
82						
83						
84						
85						
86						
87						
88						
89						
90						

✓

Radiological Operations
Area or Equipment Drawing Showing Survey Points



Radiological Operations
Area or Equipment Drawing Showing Survey Points



Top of Doc House

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey



Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by *[Signature]*
Signature

Employee #: [REDACTED]

Date: 10-10-94 Building: 886
Time: 1330 Room: 101
Shift: Days

Survey Description:
Smear of Mezzanine ^{Mezzanine} after plastic removed
Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-27-94</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:		<u>56191</u>		
Date Cal.:		<u>4-12-94</u>		
Cal. Due:		<u>10-94</u>		
BKGRD:		<u>1250</u>		

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 10-10-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-10-94 Time: 1330 Building: 886 Room: 101

ALPHA


BETA

	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			18
2			3
3			9
4			12
5			3
6			9
7			12
8			9
9			15
10			9
11			6
12			9
13			3
14			9
15			3
16			9
17	1600	15KD	
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			

	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			0
2			0
3			64
4			24
5			39
6			30
7			3
8			0
9			0
10			0
11			0
12			21
13			0
14			0
15			6
16			0
17			3
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			

✓

Radiological Operations
Area or Equipment Drawing Showing Survey Points



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey



Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by R. [Signature]
Signature

Employee #:

Date: 9-26-94 Building: 886
Time: 1430 Room: 101
Shift: DAYS

Survey Description:
Base Line 101
Diagram/Sketch Attached: yes _____ no

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>	<u>810</u>			
Date Cal.:	<u>10-5-93</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:	<u>110264</u>	<u>56071</u>		
Date Cal.:	<u>6-29-94</u>	<u>5-13-94</u>		
Cal. Due:	<u>6-95</u>	<u>11-94</u>		
BKGRD:	<u>75</u>	<u>2250</u>		

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposited

Radiological Operations Foreman

[Signature]
Signature

Date: 10-13-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-28-94 Time: 1430 Building: 886 Room: 101

ALPHA


BETA

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			0	1		<BK6
2			3	2		<BK6
3			12	3		18
4			24	4		6
5			27	5		<BK6
6			72	6		<BK6
7			12	7		<BK6
8			0	8		12
9			3	9		21
10			15	10		<BK6
11			21	11		9
12			21	12		<BK6
13			108	13		15
14			24	14		9
15			9	15		<BK6
16			21	16		<BK6
17			12	17		9
18			24	18		<BK6
19				19		
20				20		
21				21		
22				22		
23				23		
24				24		
25				25		
26				26		
27				27		
28				28		
29				29		
30				30		
31				31		
32				32		
33				33		
34				34		
35				35		
36				36		
37				37		
38				38		
39				39		
40				40		
41				41		
42				42		
43				43		
44				44		
45				45		

Table Left Side

Table Right Side

White Tank



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by _____ Employee #: _____
Signature

Taken by _____ Employee #: _____
Signature

Taken by *R. Handberg* Employee #: 
Signature

Date: 9-12-93 Building: 886
Time: 1425 Room: 101
Shift: DAYS

Survey Description:
Base line 101
Diagram/Sketch Attached: yes _____ no ✓

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>	<u>81</u>			
Date Cal.:	<u>10-5-93</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

- STATUS:
 Within Limits
 Limits Exceeded
 Posted
 Deposted

Radiological Operations Foreman

Carl [Signature]
Signature

Date: 9-14-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS


Date: 9-17-84 Time: 1425 Building: 886 Room: 101

	ALPHA			BETA		
	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (smear)	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (smear)
Floor East	1		9	1		<BKG
	2		9	2		15
	3		6	3		<BKG
	4		9	4		<BKG
	5		3	5		<BKG
	6		12	6		<BKG
House Wall	7		0	7		6
	8		0	8		<BKG
	9		9	9		<BKG
	10		9	10		<BKG
	11		57	11		<BKG
	12		6	12		<BKG
	13		18	13		15
	14		30	14		<BKG
	15		27	15		<BKG
	16		3	16		<BKG
Floor Bkg	17		15	17		<BKG
	18		18	18		3
	19		18	19		<BKG
	20		12	20		<BKG
	21			21		
	22			22		
	23			23		
	24			24		
	25			25		
	26			26		
27			27			
28			28			
29			29			
30			30			
31			31			
32			32			
33			33			
34			34			
35			35			
36			36			
37			37			
38			38			
39			39			
40			40			
41			41			
42			42			
43			43			
44			44			
45			45			

✓

RADIOLOGICAL MONITORING Control No. _____

Area or Equipment Drawing Showing Survey Points



x-x
Contamination
Boundary

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by *R. Anderson*
Signature

Employee #: [REDACTED]

Date: <u>9-14-94</u> Building: <u>886</u> Time: <u>1420</u> Room: <u>101</u> Shift: <u>DAY</u>	Survey Description: <p style="text-align: center; font-size: 1.2em;"><u>POST-JOB</u></p> Diagram/Sketch Attached: yes ___ no ___
--	---

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>	<u>810</u>			
Date Cal.:	<u>10-5-93</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

Ante Bell
Signature

Date: 9-14-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-14-94 Time: _____ Building: 886 Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1		18	1		0
2		3	2		42
3		9	3		0
4		9	4		0
5		12	5		0
6		0	6		0
7		18	7		0
8		12	8		0
9		9	9		0
10		12	10		18
11			11		
12			12		
13			13		
14			14		
15			15		
16			16		
17			17		
18			18		
19			19		
20			20		
21			21		
22			22		
23			23		
24			24		
25			25		
26			26		
27			27		
28			28		
29			29		
30			30		
31			31		
32			32		
33			33		
34			34		
35			35		
36			36		
37			37		
38			38		
39			39		
40			40		
41			41		
42			42		
43			43		
44			44		
45			45		

**RADIOLOGICAL OPERATIONS
Contamination Survey**

Taken by [Signature] Employee #: [Redacted]
Signature

Taken by _____ Employee #: _____
Signature

Taken by _____ Employee #: _____
Signature

Date: <u>8-19-94</u> Building: <u>875</u>	Survey Description: <u>875 Baseline Survey Cont (Fixed Contamination) / of every 5 smear pos</u> Diagram/Sketch Attached <input checked="" type="checkbox"/> yes <input type="checkbox"/> no
Time: <u>0800</u> Room#: <u>RLA</u>	
Shift: <u>Day</u>	

**INSTRUMENTATION USED
SMEAR COUNTERS**

Mfg.:	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>
Model:	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>
Serial#:	_____	_____	_____	_____	_____
Date. Cal.:	_____	_____	_____	_____	_____
Cal. Due.:	_____	_____	_____	_____	_____

Mfg.:	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>
Model:	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>	<u>SAC-4</u>
Serial#:	_____	_____	_____	_____	_____
Date. Cal.:	_____	_____	_____	_____	_____
Cal. Due.:	_____	_____	_____	_____	_____

SURVEY INSTRUMENTS

Mfg.:	<u>Ludlum</u>	<u>Ludlum</u>	_____	_____
Model:	<u>12-1A</u>	<u>31</u>	_____	_____
Serial#:	<u>56127</u>	<u>61645</u>	_____	_____
Date. Cal.:	<u>5-94</u>	<u>8-94</u>	_____	_____
Cal. Due.:	<u>11-94</u>	<u>2-95</u>	_____	_____
BKGRD:	<u><250</u>	<u>50 cpm</u>	_____	_____

COMMENTS

Status:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman:

[Signature] Date: 8-22-94
Signature

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (smear)	CPM Removable (Swipe)	CPM Direct	DPM/100cm ² Removable (smear)
1			1		
2			2		
3			3		
4			4		
5	<250		5	<1894	
6			6		
7			7		
8			8		
9			9		
10	<250		10	<1894	
11			11		
12			12		
13			13		
14			14		
15	<250		15	<1894	
16			16		
17			17		
18			18		
19			19		
20	<250		20	<1894	
21			21		
22			22		
23			23		
24			24		
25	<250		25	<1894	
26			26		
27			27		
28			28		
29			29		
30	<250		30	<1894	
31			31		
32			32		
33			33		
34			34		
35	<250		35	<1894	
36			36		
37			37		
38			38		
39			39		
40	<250		40	<1894	
41			41		
42			42		
43			43		
44			44		
45	<250		45	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
46						
47						
48						
49						
50		<250			<1894	
51						
52						
53						
54						
55		<250			<1894	
56						
57						
58						
59						
60		<250			<1894	
61						
62						
63						
64						
65		<250			<1894	
66						
67						
68						
69						
70		<250			<1894	
71						
72						
73						
74						
75		<250			<1894	
76						
77						
78						
79						
80		<250			<1894	
81						
82						
83						
84						
85		<250			<1894	
86						
87						
88						
89						
90		<250			<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
91			91		
92			92		
93			93		
94			94		
95	<250		95	<1894	
96			96		
97			97		
98			98		
99			99		
100	<250		100	<1894	
101			101		
102			102		
103			103		
104			104		
105	<250		105	<1894	
106			106		
107			107		
108			108		
109			109		
110	<250		110	<1894	
111			111		
112			112		
113			113		
114			114		
115	<250		115	<1894	
116			116		
117			117		
118			118		
119			119		
120	<250		120	<1894	
121			121		
122			122		
123			123		
124			124		
125	<250		125	<1894	
126			126		
127			127		
128			128		
129			129		
130	<250		130	<1894	
131			131		
132			132		
133			133		
134			134		
135	<250		135	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
136			136		
137			137		
138			138		
139			139		
140	<250		140	<1894	
141			141		
142			142		
143			143		
144			144		
145	<250		145	<1894	
146			146		
147			147		
148			148		
149			149		
150	<250		150	<1894	
151			151		
152			152		
153			153		
154			154		
155	<250		155	<1894	
156			156		
157			157		
158			158		
159			159		
160	<250		160	<1894	
161			161		
162			162		
163			163		
164			164		
165	<250		165	<1894	
166			166		
167			167		
168			168		
169			169		
170	<250		170	<1894	
171			171		
172			172		
173			173		
174			174		
175	<250		175	<1894	
176			176		
177			177		
178			178		
179			179		
180	<250		180	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
181			181		
182			182		
183			183		
184			184		
185	<250		185	<1894	
186			186		
187			187		
188			188		
189			189		
190	<250		190	<1894	
191			191		
192			192		
193			193		
194			194		
195	<250		195	<1894	
196			196		
197			197		
198			198		
199			199		
200	<250		200	<1894	
201			201		
202			202		
203			203		
204			204		
205	<250		205	<1894	
206			206		
207			207		
208			208		
209			209		
210	<250		210	<1894	
211			211		
212			212		
213			213		
214			214		
215	<250		215	<1894	
216			216		
217			217		
218			218		
219			219		
220	<250		220	<1894	
221			221		
222			222		
223			223		
224			224		
225	<250		225	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
226			226		
227			227		
228			228		
229			229		
230	<250		230	<1894	
231			231		
232			232		
233			233		
234			234		
235	<250		235	<1894	
236			236		
237			237		
238			238		
239			239		
240	<250		240	<1894	
241			241		
242			242		
243			243		
244			244		
245	<250		245	<1894	
246			246		
247			247		
248			248		
249			249		
250	<250		250	<1894	
251			251		
252			252		
253			253		
254			254		
255	<250		255	<1894	
256			256		
257			257		
258			258		
259			259		
260	<250		260	<1894	
261			261		
262			262		
263			263		
264			264		
265	<250		265	<1894	
266			266		
267			267		
268			268		
269			269		
270	<250		270	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
271			271		
272			272		
273			273		
274			274		
275	<250		275	<1894	
276			276		
277			277		
278			278		
279			279		
280	<250		280	<1894	
281			281		
282			282		
283			283		
284			284		
285	<250		285	<1894	
286			286		
287			287		
288			288		
289			289		
290	<250		290	<1894	
291			291		
292			292		
293			293		
294			294		
295	<250		295	<1894	
296			296		
297			297		
298			298		
299			299		
300	<250		300	<1894	
301			301		
302			302		
303			303		
304			304		
305	<250		305	<1894	
306			306		
307			307		
308			308		
309			309		
310	<250		310	<1894	
311			311		
312			312		
313			313		
314			314		
315	<250		315	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
316			316		
317			317		
318			318		
319			319		
320	<250		320	<1894	
321			321		
322			322		
323			323		
324			324		
325	<250		325	<1894	
326			326		
327			327		
328			328		
329			329		
330	<250		330	<1894	
331			331		
332			332		
333			333		
334			334		
335	<250		335	<1894	
336			336		
337			337		
338			338		
339			339		
340	<250		340	<1894	
341			341		
342			342		
343			343		
344			344		
345	<250		345	<1894	
346			346		
347			347		
348			348		
349			349		
350	<250		350	<1894	
351			351		
352			352		
353			353		
354			354		
355	<250		355	<1894	
356			356		
357			357		
358			358		
359			359		
360	<250		360	<1894	

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____


ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
361			361		
362			362		
363			363		
364			364		
365	<250		365	<1894	
366			366	<1894	
367			367		
368			368		
369			369		
370	<250		370	<1894	
371			371		
372			372		
373			373		
374			374		
375	<250		375	<1894	
376			376		
377			377		
378			378		
379			379		
380	<250		380	<1894	
381			381		
382			382		
383			383		
384			384		
385	<250		385	<1894	
386			386		
387			387		
388			388		
389			389		
390	<250		390	<1894	
391			391		
392			392		
393			393		
394			394		
395	<250		395	<1894	
396			396		
397			397		
398			398		
399			399		
400	<250		400	<1894	
401			401		
402			402		
403			403		
404			404		
405			405		

EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

101	120	121	140	141	160	161	180	181	200
102	119	122	139	142	159	162	179	182	199
103	118	123	138	143	158	163	178	183	198
104	117	124	137	144	157	164	177	184	197
105	116	125	136	145	156	165	176	185	196
106	115	126	135	146	155	164	175	186	195
107	114	127	134	147	159	167	174	187	194
108	113	128	133	148	157	168	173	188	193
109	112	129	132	149	152	169	172	189	192
110	111	130	131	150	151	170	171	190	191



EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

201	220	221	240	241	260	261	280	281	300
202	217	222	239	242	259	262	279	282	299
203	218	223	238	243	258	263	278	283	298
204	217	227	237	244	257	264	277	284	297
205	216	225	236	245	256	265	276	285	296
206	215	226	235	246	255	266	275	286	295
207	214	227	234	247	254	267	274	287	294
208	213	228	233	248	253	268	273	288	293
209	212	229	232	249	252	269	272	289	292
210	211	230	231	250	257	290	271	290	291




EG&G ROCKY FLATS

Control No. 875-1M


Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



Total Survey Points

Alpha - Beta Survey

Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by R. Houdashuk
Signature

Employee #: [REDACTED]

Date: 9-27-94 Building: 875

Survey Description: Base line,

Time: 1315 Room: AS Rep

Direct

Shift: Days

Diagram/Sketch Attached: yes no

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:					
Date Cal.:					
Cal. Due:	-				

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:					
Date Cal.:					
Cal. Due:					

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	Bicron	Bicron	
Model:	31	12-1A	A-100	A-100	
Serial#:	<u>110064</u>		<u>B766A</u>	<u>B385</u>	
Date Cal.:	<u>6-94</u>		<u>8-94</u>	<u>8-94</u>	
Cal. Due:	<u>12-94</u>		<u>2-95</u>	<u>2-95</u>	
BKGRD:	<u>75</u>		<u>0</u>	<u>0</u>	

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 9-27-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: AS Req

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM-24 DPM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM-24 DPM Direct	DPM/100cm2 Removable (smear)
1		46			<1894	
2						
3						
4						
5						
6						
7						
8		17			<1894	
9						
10						
11						
12						
13						
14						
15						
16		22			<1894	
17						
18						
19						
20						
21						
22						
23						
24		40			<1894	
25						
26						
27						
28						
29						
30						
31						
32		34			<1894	
33						
34						
35						
36						
37						
38						
39						
40		63			<1894	
41						
42						
43						
44						
45						

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Rep

	ALPHA			BETA		
	CPM Removable (Swipe)	DPM CPM-R₂₄ Direct	DPM/100cm ² Removable (Smear)	CPM Removable (Swipe)	DPM CPM-R₂₄ Direct	DPM/100cm ² Removable (Smear)
46						
47						
48		17			<1894	
49						
50						
51						
52						
53						
54						
55						
56		51			<1894	
57						
58						
59						
60						
61						
62						
63						
64		69			<1894	
65						
66						
67						
68						
69						
70						
71						
72		29			<1894	
73						
74						
75						
76						
77						
78						
79						
80		29			<1894	
81						
82						
83						
84						
85						
86						
87						
88		40			<1894	
89						
90						

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

	ALPHA			BETA		
	CFM Removable (Swipe)	DPM CFM ₂₅₄ Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	DPM CFM ₂₅₄ Direct	DPM/100cm ² Removable (Smear)
91						
92						
93						
94						
95						
96		29			<1894	
97						
98						
99						
100						
101						
102						
103						
104		6			<1894	
105						
106						
107						
108						
109						
110						
111						
112		51			<1894	
113						
114						
115						
116						
117						
118						
119						
120		34			<1894	
121						
122						
123						
124						
125						
126						
127						
128		17			<1894	
129						
130						
131						
132						
133						
134						
135						

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Rep

	ALPHA			BETA		
	CFM Removable (Swipe)	DPM CFM_{RD} Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	DPM CFM_{RD} Direct	DPM/100cm ² Removable (Smear)
136		46			<1894	
137						
138						
139						
140						
141						
142						
143						
144		23			<1894	
145						
146						
147						
148						
149						
150						
151						
152		40			<1894	
153						
154						
155						
156						
157						
158						
159						
160		63			<1894	
161						
162						
163						
164						
165						
166						
167						
168		34			<1894	
169						
170						
171						
172						
173						
174						
175						
176		34			<1894	
177						
178						
179						
180						

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

ALPHA			BETA		
CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (Smear)
181			181		
182			182		
183			183		
184	29		184	<1894	
185			185		
186			186		
187			187		
188			188		
189			189		
190			190		
191			191		
192	29		192	<1894	
193			193		
194			194		
195			195		
196			196		
197			197		
198			198		
199			199		
200	63		200	<1894	
201			201		
202			202		
203			203		
204			204		
205			205		
206			206		
207			207		
208	29		208	<1894	
209			209		
210			210		
211			211		
212			212		
213			213		
214			214		
215			215		
216	40		216	<1894	
217			217		
218			218		
219			219		
220			220		
221			221		
222			222		
223			223		
224	36		224	<1894	
225			225		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

ALPHA			BETA		
CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (Smear)
226			226		
227			227		
228			228		
229			229		
230			230		
231			231		
232	15		232	<1894	
233			233		
234			234		
235			235		
236			236		
237			237		
238			238		
239			239		
240	41		240	<1894	
241			241		
242			242		
243			243		
244			244		
245			245		
246			246		
247			247		
248	41		248	<1894	
249			249		
250			250		
251			251		
252			252		
253			253		
254			254		
255			255		
256	41		256	<1894	
257			257		
258			258		
259			259		
260			260		
261			261		
262			262		
263			263		
264	46		264	<1894	
265			265		
266			266		
267			267		
268			268		
269			269		
270			270		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
271						
272		56			<1894	
273						
274						
275						
276						
277						
278						
279						
280		41			<1894	
281						
282						
283		46			<1894	
284						
285						
286						
287						
288		36			<1894	
289						
290						
291						
292						
293						
294		56			<1894	
295						
296		41			<1894	
297						
298						
299						
300						
301						
302						
303						
304		56			<1894	
305						
306						
307						
308						
309						
310						
311						
312		26			<1894	
313						
314						
315						

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

ALPHA			BETA		
CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (Smear)
316			316		
317			317		
318			318		
319			319		
320	26		320	<1894	
321			321		
322			322		
323			323		
324			324		
325			325		
326			326		
327			327		
328	31		328	<1894	
329			329		
330			330		
331			331		
332			332		
333			333		
334			334		
335			335		
336	26		336	<1894	
337			337		
338			338		
339			339		
340			340		
341			341		
342			342		
343			343		
344	31		344	<1894	
345			345		
346			346		
347			347		
348			348		
349			349		
350			350		
351			351		
352	61		352	<1894	
353			353		
354			354		
355			355		
356			356		
357			357		
358			358		
359			359		
360	15		360	<1894	

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS


Date: 9-27-94 Time: 1315 Building: 875 Room: As Req

ALPHA			BETA		
CPM Removable (Swipe)	CPM DPM Direct	DPM/100cm ² Removable (Smear)	CPM Removable (Swipe)	CPM DPM Direct	DPM/100cm ² Removable (Smear)
361			361		
362			362		
363			363		
364			364		
365			365		
366			366		
367			367		
368	41		368	<1894	
369			369		
370			370		
371			371		
372			372		
373			373		
374			374		
375			375		
376	51		376	<1894	
377			377		
378			378		
379			379		
380			380		
381			381		
382			382		
383			383		
384	41		384	<1894	
385			385		
386			386		
387			387		
388			388		
389			389		
390			390		
391			391		
392	15		392	<1894	
393			393		
394			394		
395			395		
396			396		
397			397		
398			398		
399			399		
400	51		400	<1894	
401			401		
402			402		
403			403		
404			404		
405			405		

✓

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875




Total Survey Points

EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

II

101	120	121	140	141	160	161	180	181	200
102	119	122	139	142	159	162	179	182	199
103	118	123	138	143	158	163	178	193	198
104	117	124	137	144	157	164	177	194	197
105	116	125	136	145	156	165	176	185	196
106	115	126	135	146	155	166	175	184	195
107	114	127	134	147	154	167	174	187	194
108	113	128	133	148	153	168	173	188	193
109	112	129	132	149	152	169	172	189	192
110	111	130	131	150	151	170	171	190	191




EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

III



EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

201	220	221	240	241	260	261	280	281	300
202	219	222	239	242	259	262	279	282	299
203	218	223	238	243	258	263	278	283	298
204	217	224	237	244	257	264	277	284	297
205	216	225	236	245	256	265	276	285	296
206	215	226	235	246	255	266	275	286	295
207	214	227	234	247	254	267	274	287	294
208	213	228	233	248	253	268	273	288	293
209	212	229	232	249	252	269	272	289	292
210	211	230	281	250	267	290	271	290	291

IV



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [REDACTED]

Taken by _____
Signature

Employee #: _____

Taken by [Signature]
Signature

Employee #: [REDACTED]

Date: <u>10-7-94</u> Building: <u>875</u> Time: <u>1445</u> Room: <u>As Rep</u> Shift: <u>DAYS</u>	Survey Description: <u>Baseline on Walls</u> Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
--	---

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-27-94</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>11-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	Bicron		
Model:	31	12-1A	A-100		
Serial#:	<u>110264</u>	<u>56127</u>	<u>B766A</u>		
Date Cal.:	<u>6-29-94</u>	<u>5-23-94</u>	<u>8-2-94</u>		
Cal. Due:	<u>6-95</u>	<u>11-94</u>	<u>2-95</u>		
BKGRD:	<u>50</u>	<u>2250</u>	<u>1</u>		

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposted

Radiological Operations Foreman

[Signature]
Signature

Date: 10-10-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 0830 Building: 875 Room: as Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1	0		1		
2	0		2		
3	0		3		
4	5		4		
5	0		5		
6	5		6		
7	0		7		
8	5		8		
9	0		9		
10	0		10		
11	0		11		
12	0		12		
13	26		13		
14	5		14		
15	0		15		
16	5		16		
17	0		17		
18	0		18		
19	0		19		
20	5		20		
21	10		21		
22	5		22		
23	0		23		
24	0		24		
25	0		25		
26	5		26		
27	143		27		
28	5		28		
29	21		29		
30	0		30		
31	0		31		
32	5		32		
33	0		33		
34	0		34		
35	0		35		
36	0		36		
37	5		37		
38	10		38		
39	5		39		
40	5		40		
41	0		41		
42	0		42		
43	0		43		
44	0		44		
45	0		45		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 0830 Building: 875 Room: as Rec'd

	ALPHA			Resurvey BETA ¹⁰²⁴		
	CFM Removable (Swipe)	DPM CFM Direct		DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	DPM CFM Direct
46		31				
47		5				
48		0				
49		0				
50		5				
51		0				
52		92				
53		5				
54		0				
55		0				
56		5				
57		5				
58		0				
59		0				
60		0				
61		0				
62		21				
63		0				
64		5				
65		10				
66		256				
67		0				
68		0				
69		0				
70		0				
71		5				
72		5				
73		374			77	
74		0				
75		0				
76		5				
77		5				
78		10				
79		0				
80		0				
81		10				
82		158				
83		0				
84		5				
85		0				
86		0				
87		0				
88		0				
89		0				
90		0				

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 0830 Building: 875 Room: as Req'd

ALPHA			BETA		
CFM Removable (Swipe)	CFM DPM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
91			91		
92	5		92		
93	0		93		
94	16		94		
95	21		95		
96	4		96		
97	0		97		
98	0		98		
99	0		99		
100	0		100		
101	0		101		
102	0		102		
103	0		103		
104	0		104		
105	0		105		
106	0		106		
107	0		107		
108	0		108		
109	0		109		
110	0		110		
111	0		111		
112	0		112		
113	0		113		
114	0		114		
115	0		115		
116	0		116		
117	0		117		
118	0		118		
119	0		119		
120	0		120		
121	0		121		
122	0		122		
123	0		123		
124	0		124		
125	0		125		
126	0		126		
127	0		127		
128	0		128		
129	0		129		
130	0		130		
131	0		131		
132	0		132		
133	0		133		
134	0		134		
135	0		135		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 0830 Building: 825 Room: as Req'd

ALPHA			BETA		
CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
136	0		136		
137	0		137		
138	5		138		
139	5		139		
140	0		140		
141	10		141		
142	0		142		
143	0		143		
144	5		144		
145	5		145		
146	0		146		
147	0		147		
148	5		148		
149	0		149		
150	0		150		
151	0		151		
152	5		152		
153	5		153		
154	5		154		
155	0		155		
156	0		156		
157	10		157		
158	0		158		
159	5		159		
160	0		160		
161	0		161		
162	5		162		
163	0		163		
164	0		164		
165	5		165		
166	21		166		
167	0		167		
168	5		168		
169	0		169		
170	0		170		
171	5		171		
172	2		172		
173	0		173		
174	0		174		
175	0		175		
176	5		176		
177	0		177		
178	0		178		
179	21		179		
180	10		180		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 0830 Building: 875 Room: as Req'd

ALPHA			BETA		
CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
181	5		181		
182	0		182		
183	0		183		
184	5		184		
185	21		185		
186	56		186		
187	0		187		
188	5		188		
189	0		189		
190	0		190		
191	5		191		
192	5		192		
193	0		193		
194	0		194		
195	15		195		
196	0		196		
197	10		197		
198	0		198		
199	0		199		
200	5		200		
201	5		201		
202	0		202		
203	0		203		
204	5		204		
205	10		205		
206	0		206		
207	0		207		
208	5		208		
209	5		209		
210	5		210		
211			211		
212			212		
213			213		
214			214		
215			215		
216			216		
217			217		
218			218		
219			219		
220			220		
221			221		
222			222		
223			223		
224			224		
225			225		

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 1445 Building: 825 Room: As Rep

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (smear)
1	<250	0	1	<1894	12
2	<250	0	2	<1894	0
3	<250	0	3	<1894	3
4	<250	0	4	<1894	0
5	<250	3	5	<1894	9
6	<250	0	6	<1894	3
7	<250	3	7	<1894	0
8	<250	0	8	<1894	18
9	<250	3	9	<1894	15
10	<250	0	10	<1894	9
11	<250	0	11	<1894	0
12	<250	0	12	<1894	0
13	<250	3	13	<1894	0
14	<250	0	14	<1894	0
15	<250	0	15	<1894	9
16	<250	3	16	<1894	0
17	<250	0	17	<1894	21
18	<250	6	18	<1894	0
19	<250	0	19	<1894	15
20	<250	0	20	<1894	0
21	<250	9	21	<1894	0
22	<250	0	22	<1894	0
23	<250	0	23	<1894	0
24	<250	0	24	<1894	0
25	<250	0	25	<1894	0
26	<250	0	26	<1894	0
27	<250	3	27	<1894	9
28	<250	0	28	<1894	15
29	<250	0	29	<1894	0
30	<250	0	30	<1894	0
31	<250	6	31	<1894	21
32	<250	0	32	<1894	0
33	<250	0	33	<1894	0
34	<250	0	34	<1894	15
35	<250	3	35	<1894	0
36	<250	0	36	<1894	0
37	<250	3	37	<1894	0
38	<250	0	38	<1894	0
39	<250	6	39	<1894	0
40	<250	0	40	<1894	0
41	<250	3	41	<1894	51
42	<250	9	42	<1894	0
43	<250	0	43	<1894	0
44	<250	0	44	<1894	0
45	<250	0	45	<1894	0

✓

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-7-94 Time: 1445 Building: 875 Room: As Rep

ALPHA

BETA

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (Smear)
46	<250		6	46	<1894	0
47	<250		3	47	<1894	3
48	<250		0	48	<1894	0
49	<250		0	49	<1894	0
50	<250		0	50	<1894	42
51	<250		6	51	<1894	39
52	<250		3	52	<1894	0
53	<250		0	53	<1894	0
54	<250		0	54	<1894	9
55	<250		3	55	<1894	21
56	<250		0	56	<1894	0
57	<250		0	57	<1894	9
58	<250		0	58	<1894	0
59	<250		3	59	<1894	0
60	<250		0	60	<1894	0
61	<250		0	61	<1894	0
62	<250		0	62	<1894	0
63	<250		0	63	<1894	0
64	<250		0	64	<1894	0
65	<250		3	65	<1894	12
66	<250		0	66	<1894	0
67	<250		3	67	<1894	0
68	<250		0	68	<1894	0
69	<250		3	69	<1894	0
70	<250		0	70	<1894	0
71	<250		0	71	<1894	0
72	<250		0	72	<1894	0
73	<250		6	73	<1894	0
74	<250		0	74	<1894	15
75	<250		0	75	<1894	21
76	<250		6	76	<1894	0
77	<250		0	77	<1894	0
78	<250		3	78	<1894	0
79	<250		0	79	<1894	0
80	<250		0	80	<1894	3
81	<250		3	81	<1894	0
82	<250		0	82	<1894	12
83	<250		0	83	<1894	0
84	<250		3	84	<1894	0
85	<250		3	85	<1894	9
86	<250		6	86	<1894	3
87	<250		0	87	<1894	0
88	<250		0	88	<1894	0
89	<250		0	89	<1894	3
90	<250		0	90	<1894	0

Pt ↓

Tunnel →




RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS


Date: 10-7-94 Time: 1445 Building: 876 Room: AsReq

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm ² Removable (Smear)
Tunnel 91	<250	0	91	<1894	0
92	<250	0	92	<1894	3
93	<250	0	93	<1894	0
94	<250	0	94	<1894	0
95	<250	3	95	<1894	0
96	<250	0	96	<1894	0
97	<250	0	97	<1894	42
98	<250	6	98	<1894	0
99	<250	3	99	<1894	3
100	<250	6	100	<1894	24
101	<250	3	101	<1894	0
102	<250	0	102	<1894	0
103	<250	3	103	<1894	33
104	<250	3	104	<1894	30
105	<250	0	105	<1894	0
106	<250	3	106	<1894	0
107	<250	3	107	<1894	0
108	<250	3	108	<1894	9
109	<250	6	109	<1894	0
Upper Tunnel 110	<250	0	110	<1894	21
111	<250	0	111	<1894	0
112	<250	0	112	<1894	21
113	<250	0	113	<1894	6
114	<250	3	114	<1894	18
115	<250	3	115	<1894	0
116	<250	0	116	<1894	0
117	<250	0	117	<1894	0
118	<250	0	118	<1894	12
119	<250	0	119	<1894	0
120	<250	0	120	<1894	6
121	<250	0	121	<1894	0
122	<250	0	122	<1894	0
123	<250	0	123	<1894	0
124	<250	3	124	<1894	0
125	<250	3	125	<1894	0
126	<250	6	126	<1894	12
127	<250	3	127	<1894	6
128	<250	0	128	<1894	0
129	<250	0	129	<1894	3
130	<250	0	130	<1894	9
131	<250	3	131	<1894	6
132			132		
133			133		
134			134		
135			135		

**Radiological Operations
Area or Equipment Drawing Showing Survey Points**




Radiological Operations
Area or Equipment Drawing Showing Survey Points



West Wall Bldg # 825


U

Radiological Operations
Area or Equipment Drawing Showing Survey Points




South wall Bldg # 825

Radiological Operations
Area or Equipment Drawing Showing Survey Points




East Ball Bldg # 825

Radiological Operations
Area or Equipment Drawing Showing Survey Points



west well in the pit

Radiological Operations
Area or Equipment Drawing Showing Survey Points




South wall in the P.I.

13


13

Radiological Operations
Area or Equipment Drawing Showing Survey Points




East well in the pit

**Radiological Operations
Area or Equipment Drawing Showing Survey Points**




East Mill Tunnel (Lower)

**Radiological Operations
Area or Equipment Drawing Showing Survey Points**




West well funnel (lower)

Radiological Operations
Area or Equipment Drawing Showing Survey Points



South Wall Tunnel (upper)

Radiological Operations
Area or Equipment Drawing Showing Survey Points



North well funnel (upper)

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: 865-13M

Taken by James D. Williams
Signature

Employee #: [REDACTED]

Taken by Robert P. McClure
Signature

Employee #: [REDACTED]

Taken by _____
Signature

Employee #: _____

Date: <u>8-12-94</u> Building: <u>875</u>	Survey Description: <u>875 BASELINE</u>
Time: <u>1400</u> Room: <u>As Required</u>	<u>SURVEY</u>
Shift: <u>DAY</u>	Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>
Model:	<u>SAC - 4</u>				
Serial#:	<u>864</u>	<u>810</u>			
Date Cal.:	<u>10-5-93</u>	<u>6-1-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>	<u>Eberline</u>
Model:	<u>BC - 4</u>				
Serial#:	<u>874</u>	<u>868</u>			
Date Cal.:	<u>4-14-94</u>	<u>10-1-93</u>			
Cal. Due:	<u>4-95</u>	<u>10-94</u>			

SURVEY INSTRUMENTS

Mfg.:	<u>Ludlum</u>	<u>Ludlum</u>			
Model:	<u>31</u>	<u>12-1A</u>			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposited

Radiological Operations Foreman

Chris Bean
Signature

Date: 8-12-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: As REQUIRED

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1			6			27
2			3			0
3			3			3
4			6			51
5			3			36
6			3			24
7			3			0
8			0			0
9			0			0
10			6			15
11			3			0
12			3			15
13			0			24
14			3			12
15			0			0
16			3			6
17			6			15
18			0			0
19			6			0
20			0			0
21			3			9
22			0			0
23			3			6
24			6			0
25			9			30
26			3			18
27			3			0
28			3			27
29			0			15
30			6			6
31			9			9
32			0			0
33			9			0
34			0			0
35			3			30
36			0			9
37			6			48
38			0			0
39			12			33
40			0			0
41			0			0
42			6			9
43			0			0
44			3			0
45			3			0

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: As Required

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
46			3			6
47			9			18
48			0			0
49			9			30
50			3			0
51			0			0
52			0			30
53			0			39
54			3			0
55			0			0
56			3			0
57			0			3
58			0			0
59			0			0
60			3			24
61			0			10
62			0			0
63			0			6
64			0			0
65			3			3
66			9			9
67			0			0
68			6			0
69			0			30
70			0			15
71			0			0
72			3			6
73			0			0
74			3			0
75			0			12
76			0			0
77			0			6
78			0			0
79			9			0
80			3			0
81			6			9
82			0			15
83			3			0
84			3			21
85			9			0
86			0			6
87			12			0
88			0			0
89			0			3
90			3			0

RADIOLOGICAL OPERATIONS

Alpha-Beta Survey

RESULTS

Date: 8.12.94 Time: 1400 Building: 875 Room: as Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
91		0	91		0
92		0	92		0
93		0	93		3
94		0	94		0
95		0	95		9
96		0	96		15
97		0	97		0
98		0	98		0
99		0	99		6
100		0	100		0
101		0	101		0
102		0	102		0
103		0	103		24
104		0	104		0
105		0	105		0
106		0	106		0
107		0	107		0
108		0	108		6
109		0	109		0
110		0	110		21
111		0	111		0
112		0	112		0
113		0	113		33
114		0	114		0
115		0	115		18
116		0	116		0
117		0	117		3
118		0	118		0
119		0	119		0
120		12	120		0
121		0	121		0
122		0	122		30
123		0	123		0
124		0	124		0
125		0	125		0
126		0	126		6
127		0	127		0
128		0	128		0
129		0	129		0
130		0	130		9
131		0	131		15
132		0	132		0
133		0	133		0
134		0	134		24
135		0	135		0

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: As Required

ALPHA			BETA		
CPM Removable (Swipe)	CPM Direct	DPM/100cm2 Removable (Smear)	CPM Removable (Swipe)	CPM Direct	DPM/100cm2 Removable (Smear)
136		6	136		30
137		0	137		0
138		0	138		3
139		3	139		6
140		15	140		0
141		0	141		12
142		0	142		21
143		0	143		0
144		0	144		6
145		0	145		3
146		0	146		15
147		0	147		0
148		0	148		0
149		0	149		0
150		0	150		3
151		0	151		0
152		0	152		0
153		0	153		27
154		0	154		0
155		0	155		36
156		0	156		0
157		0	157		39
158		0	158		0
159		0	159		0
160		0	160		3
161		0	161		12
162		0	162		0
163		12	163		0
164		0	164		0
165		0	165		0
166		0	166		6
167		0	167		0
168		0	168		3
169		0	169		0
170		0	170		42
171		0	171		0
172		0	172		21
173		0	173		0
174		0	174		9
175		0	175		12
176		0	176		0
177		0	177		6
178		0	178		9
179		0	179		0
180		0	180		6

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: AS Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
181		3	181		12
182		3	182		0
183		3	183		0
184		6	184		0
185		6	185		51
186		0	186		27
187		12	187		0
188		3	188		0
189		3	189		3
190		3	190		6
191		3	191		0
192		6	192		0
193		6	193		0
194		0	194		3
195		0	195		0
196		3	196		6
197		6	197		3
198		0	198		21
199		15	199		36
200		0	200		0
201		0	201		12
202		9	202		0
203		3	203		0
204		9	204		18
205		0	205		12
206		0	206		0
207		0	207		0
208		6	208		21
209		27	209		24
210		0	210		0
211		0	211		0
212		0	212		3
213		0	213		6
214		0	214		0
215		0	215		27
216		0	216		0
217		0	217		30
218		0	218		12
219		0	219		0
220		0	220		9
221		0	221		6
222		0	222		24
223		0	223		0
224		0	224		6
225		6	225		15

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-97 Time: 1400 Building: 875 Room: As Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
226		0	226		30
227		0	227		36
228		0	228		0
229		3	229		18
230		0	230		27
231		0	231		0
232		0	232		0
233		9	233		0
234		0	234		3
235		3	235		6
236		3	236		0
237		12	237		0
238		0	238		0
239		0	239		18
240		6	240		0
241		12	241		6
242		0	242		0
243		9	243		0
244		3	244		9
245		0	245		3
246		0	246		21
247		0	247		0
248		12	248		6
249		0	249		6
250		0	250		0
251		6	251		15
252		0	252		0
253		9	253		6
254		3	254		0
255		0	255		0
256		0	256		3
257		0	257		3
258		3	258		42
259		6	259		0
260		0	260		39
261		0	261		0
262		0	262		27
263		3	263		6
264		15	264		0
265		0	265		0
266		3	266		3
267		6	267		0
268		0	268		9
269		0	269		12
270		0	270		37

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: AS Required


ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
361		0	361		0
362		3	362		0
363		3	363		0
364		3	364		48
365		6	365		9
366		0	366		9
367		9	367		0
368		3	368		0
369		3	369		12
370		6	370		0
371		9	371		0
372		9	372		6
373		3	373		9
374		6	374		12
375		0	375		9
376		3	376		0
377		9	377		0
378		3	378		3
379		3	379		21
380		0	380		0
381		0	381		6
382		0	382		0
383		0	383		30
384		0	384		27
385		6	385		0
386		0	386		12
387		3	387		0
388		3	388		9
389		12	389		0
390		9	390		6
391		0	391		0
392		6	392		12
393		0	393		3
394		3	394		0
395		3	395		9
396		3	396		0
397		3	397		6
398		0	398		0
399		0	399		0
400		3	400		27
401			401		
402			402		
403			403		
404			404		
405			405		

EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: AS Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
271		3	271		27
272		0	272		0
273		0	273		0
274		0	274		15
275		0	275		6
276		6	276		0
277		0	277		9
278		3	278		12
279		9	279		6
280		0	280		0
281		12	281		0
282		0	282		0
283		0	283		3
284		0	284		12
285		0	285		27
286		0	286		0
287		0	287		9
288		6	288		21
289		0	289		6
290		13	290		0
291		0	291		0
292		6	292		30
293		0	293		0
294		0	294		3
295		0	295		0
296		0	296		3
297		3	297		21
298		6	298		0
299		9	299		24
300		12	300		42
301		0	301		39
302		0	302		0
303		0	303		12
304		0	304		0
305		0	305		0
306		0	306		0
307		0	307		24
308		0	308		0
309		0	309		18
310		6	310		9
311		0	311		0
312		0	312		6
313		0	313		6
314		0	314		3
315		0	315		27

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 8-12-94 Time: 1400 Building: 875 Room: As Required



ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
316		6	316		0
317		6	317		12
318		3	318		12
319		0	319		9
320		3	320		27
321		0	321		0
322		9	322		0
323		0	323		15
324		0	324		9
325		3	325		0
326		6	326		0
327		3	327		6
328		0	328		6
329		3	329		12
330		0	330		18
331		0	331		24
332		0	332		30
333		3	333		24
334		6	334		9
335		12	335		0
336		0	336		3
337		3	337		6
338		6	338		6
339		0	339		12
340		0	340		9
341		3	341		9
342		3	342		3
343		0	343		3
344		6	344		0
345		6	345		0
346		3	346		0
347		0	347		0
348		0	348		15
349		3	349		9
350		6	350		6
351		0	351		15
352		0	352		0
353		9	353		0
354		3	354		3
355		0	355		0
356		3	356		3
357		0	357		6
358		0	358		9
359		6	359		12
360		3	360		9

EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



EG&G ROCKY FLATS

Control No. 875-1M

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875

201	220	221	240	241	260	261	280	281	300
202	217	222	239	242	259	262	279	282	299
203	218	223	238	243	258	263	278	283	298
204	217	224	237	244	257	264	277	284	297
205	216	225	236	245	256	265	276	285	296
206	215	226	235	246	255	266	275	286	295
207	214	227	234	247	254	267	274	287	294
208	213	228	233	248	253	268	273	288	293
209	212	229	232	249	252	269	272	289	292
210	211	230	231	250	257	270	271	290	291




EG&G ROCKY FLATS

Control No. 875-1M


Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 875



Total Survey Point

Alpha - Beta Survey

Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by *[Signature]*
Signature

Employee #: 

Date: <u>10-28-94</u> Building: <u>886</u>	Survey Description:
Time: <u>1410</u> Room: <u>108</u>	<u>Baseline of Floor in 108</u>
Shift: <u>DAYS</u>	Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-94</u>	<u>6-94</u>			
Cal. Due:	<u>10-94</u>	<u>10-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-93</u>	<u>4-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

[Signature]
Signature

Date: 10-31-94

RADIOLOGICAL OPERATIONS
Alpha Survey


RESULTS

Date: 10-28-94 Time: 1410 Building: 886 Room: 108

ALPHA			RESURVEY		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1		6	1		0
2		0	2		21
3		0	3		18
4		0	4		0
5		0	5		36
6		5	6		3
7		25	7		45
8		9	8		36
9		9	9		0
10		3	10		0
11		0	11		21
12		0	12		0
13		0	13		3
14		0	14		0
15		0	15		0
16		0	16		0
17		0	17		0
18		3	18		36
19		3	19		21
20		6	20		0
21		4	21		0
22		3	22		3
23		5	23		0
24		6	24		0
25		4	25		12
26		6	26		0
27		6	27		0
28		18	28		18
29		0	29		21
30		3	30		36
31		6	31		9
32		3	32		0
33		0	33		3
34			34		
35			35		
36			36		
37			37		
38			38		
39			39		
40			40		
41			41		
42			42		
43			43		
44			44		
45			45		

**Radiological Operations
Area or Equipment Drawing Showing Survey Points**

**ROOM 108 FLOOR SURVEY
BUILDING 886**



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [REDACTED]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: <u>10-28-94</u> Building: <u>886</u> Time: <u>1000</u> Room: <u>108</u> Shift: <u>Day</u>	Survey Description: <u>East + West Wall Survey Rm #108 Bldg 886</u> Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
---	--

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>842</u>	<u>810</u>			
Date Cal.:	<u>4-94</u>	<u>6-94</u>			
Cal. Due:	<u>~10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-93</u>	<u>4-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:					
Date Cal.:					
Cal. Due:					
BKGRD:					

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposited

Radiological Operations Foreman

[Signature]
Signature

Date: 10-31-94

RADIOLOGICAL OPERATIONS Alpha Survey

RESULTS

Date: 10-28-94 Time: 1000 Building: 886 Room: 108

	ALPHA			RESURVEY		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1			0			6
2			3			9
3			0			0
4			3			0
5			3			24
6			4			9
7			0			0
8			3			0
9			3			0
10			0			0
11			0			0
12			6			15
13			0			15
14			0			15
15			3			30
16			3			0
17			0			51
18			0			0
19			0			12
20			6			0
21			0			0
22			0			21
23			0			18
24			0			0
25			0			0
26			0			0
27			0			0
28			0			24
29			6			36
30			6			0
31			0			0
32			6			18
33			0			39
34			0			3
35			5			3
36			0			0
37			0			12
38			0			6
39			3			18
40			3			3
41			0			6
42			6			6
43			0			12
44			6			0
45			0			0

✓


RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: _____ Time: _____ Building: _____ Room: _____

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm ² Removable (Smear)
46		6	46		0
47		3	47		0
48			48		
49			49		
50			50		
51			51		
52			52		
53			53		
54			54		
55			55		
56			56		
57			57		
58			58		
59			59		
60			60		
61			61		
62			62		
63			63		
64			64		
65			65		
66			66		
67			67		
68			68		
69			69		
70			70		
71			71		
72			72		
73			73		
74			74		
75			75		
76			76		
77			77		
78			78		
79			79		
80			80		
81			81		
82			82		
83			83		
84			84		
85			85		
86			86		
87			87		
88			88		
89			89		
90			90		

Radiological Operations
Area or Equipment Drawing Showing Survey Points



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by _____
Signature *[Signature]*

Taken by _____
Signature *[Signature]*

Taken by *[Signature]*
Signature

Employee #: _____

Employee #: 

Employee #: _____

Date: <u>10-31-94</u> Building: <u>886</u> Time: <u>0945</u> Room: <u>108</u> Shift: <u>Days</u>	Survey Description: <u>Over head survey Rm 108</u> Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
--	---

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>1164</u>	<u>810</u>			
Date Cal.:	<u>10-7-94</u>	<u>6-1-94</u>			
Cal. Due:	<u>4-95</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-1-93</u>	<u>4-14-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum			
Model:	31	12-1A			
Serial#:		<u>56141</u>			
Date Cal.:		<u>10-24-94</u>			
Cal. Due:		<u>4-95</u>			
BKGRD:		<u>< 250</u>			

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposted

Radiological Operations Foreman
[Signature]
Signature

Date: 10-31-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS


Date: 11-31-94 Time: 0945 Building: 806 Room: 108

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			3			0
2			3			0
3			0			0
4			12			0
5			0			0
6			0			0
7			0			0
8			6			2
9			0			0
10			6			0
11			0			0
12			0			2
13			0			0
14			0			0
15			0			0
16			0			0
17			0			0
18			0			2
19			0			0
20			0			0
21			0			0
22			0			0
23			0			3
24			0			6
25			0			1
26			12			0
27			0			0
28			0			3
29			0			0
30			0			3
31			0			0
32			3			12
33			6			6
34						
35						
36						
37						
38						
39						
40						
41						
42						
43						
44						
45						

✓

Radiological Operations
Area or Equipment Drawing Showing Survey Points

ROOM 108 FLOOR SURVEY
BUILDING 886



RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Taken by R. Houdashel
Signature

Employee #: _____

Date: 10-28-94 Building: 880
Time: 1510 Room: Outside
Shift: Days

Survey Description: Outside of Bldg 880
Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED
SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:	842	810			
Date Cal.:	4-94	6-1-94			
Cal. Due:	- 10-94	12-94			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:	868	874			
Date Cal.:	10-93	4-94			
Cal. Due:	10-94	4-95			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	Bieron	Bieron	
Model:	31	12-1A	A-100	A-100	
Serial#:	110064		A564W	B766A	
Date Cal.:	6-94		6-10-94	6-94	
Cal. Due:	12-94		12-94	6-95	
BKGRD:	75		0	0	

COMMENTS:

- STATUS:
- Within Limits
 - Limits Exceeded
 - Posted
 - Deposted

*Within limits after resurvey of point 3
resurvey point is # 34*
Radiological Operations Foreman

Carl Bevan Date: 10-31-94
Signature

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 10-21-94 Time: 0930 Building: 880 Room: N/A

	ALPHA			BETA		
	CFM Removable (Swipe)	DPM CFM 2+ Direct		DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	DPM CFM 2+ Direct
1		rd 0 < 15 rd	0	1	< 1894	^{UN 11-11-94} 2+3
2		36	0	2	< 1894	0
3		692	6	3	< 1894	0
4		< 15	0	4	< 1894	9
5		< 15	0	5	< 1894	0
6		< 15	6	6	< 1894	3
7		< 15	0	7	< 1894	0
8		< 15	3	8	< 1894	0
9		< 15	0	9	< 1894	0
10		< 15	0	10	< 1894	27
11		31	6	11	< 1894	18
12		< 15	3	12	< 1894	15
13		31	0	13	< 1894	30
14		< 15	0	14	< 1894	0
15		51	6	15	< 1894	0
16		31	3	16	< 1894	0
17		< 15	0	17	< 1894	0
18		< 15	3	18	< 1894	9
19		20	3	19	< 1894	9
20		< 15	0	20	< 1894	21
21		< 15	0	21	< 1894	0
22		< 15	6	22	< 1894	15
23		< 15	3	23	< 1894	12
24		< 15	0	24	< 1894	0
25		< 15	3	25	< 1894	27
26		< 15	3	26	< 1894	0
27		< 15	0	27	< 1894	6
28		< 15	0	28	< 1894	6
29		20	3	29	< 1894	21
30		< 15	0	30	< 1894	15
31		< 15	3	31	< 1894	30
32		< 15	0	32	< 1894	0
33		< 15	3	33	< 1894	0
34		< 15	3	34	< 1894	6
35		< 15	3	35	< 1894	24
36		< 15	6	36	< 1894	0
37		< 15	3	37	< 1894	0
38		< 15	0	38	< 1894	12
39		51	3	39	< 1894	0
40		178	6	40	< 1894	0
41		32	0	41	< 1894	9
42		56	6	42	< 1894	0
43		99	3	43	< 1894	0
44		56	0	44	< 1894	6
45		56	6	45	< 1894	12

RADIOLOGICAL OPERATIONS

Alpha-Beta Survey

RESULTS


Date: 10-21-94 Time: 0930 Building: 880 Room: N/A

	ALPHA			BETA		
	CFM Removable (Swipe)	DPM CFM Direct ¹⁰⁻²⁷⁹⁴		DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct
46		89	3		<1894	6
47		80	0		<1894	0
48		70	0		<1894	18
49		112	0		<1894	0
50		108	0		<1894	18
51		80	3		<1894	12
52		133	0		<1894	0
53		80	0		<1894	15
54		61	3		<1894	18
55		23	0		<1894	39
56		80	0		<1894	0
57		117	0		<1894	51
58		No Access	0		<1894	18
59		No Access	0		<1894	30
60		No Access	0		<1894	21
61		28	0		<1894	0
62		42	0		<1894	15
63		56	0		<1894	0
64		80	0		<1894	12
65		70	0		<1894	15
66		47	0		<1894	0
67		<15	0		<1894	0
68		61	0		<1894	12
69		89	0		<1894	12
70		61	3		<1894	0
71		70	0		<1894	0
72		61	3		<1894	0
73		<15	3		<1894	39
74		<15	3		<1894	0
75		<15	9		<1894	0
76		42	3		<1894	0
77		28	0		<1894	3
78		56	0		<1894	12
79		19	0		<1894	0
80		46	0		<1894	0
81		<15	3		<1894	0
82		<15	0		<1894	33
83						
84		28	0		<1894	0
85						
86						
87						
88						
89						
90						

Survey
pt #3
0-2004

Radiological Operations
Area or Equipment Drawing Showing Survey Points

Page 2 of 2



Alpha - Beta Survey

EST

Taken by [Signature]
Signature

Control #:

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: 9-27-94 Building: 886/875

Survey Description: Baseline Soe

Time: 1100 Room: Tunnel

886/875 Tunnel

Shift: Day

Diagram/Sketch Attached: yes no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4	SAC - 4	SAC - 4	SAC - 4	SAC - 4
Serial#:	<u>864</u>	<u>810</u>			
Date Cal.:	<u>10-93</u>	<u>6-94</u>			
Cal. Due:	<u>10-94</u>	<u>12-94</u>			

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4	BC - 4	BC - 4	BC - 4	BC - 4
Serial#:	<u>868</u>	<u>874</u>			
Date Cal.:	<u>10-93</u>	<u>4-94</u>			
Cal. Due:	<u>10-94</u>	<u>4-95</u>			

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum		
Model:	31	12-1A		
Serial#:				
Date Cal.:				
Cal. Due:				
BKGRD:				

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposted

Radiological Operations Foreman

[Signature]
Signature

Date: 10-03-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1100 Building: 875 Room: funnel

	ALPHA			BETA		
	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			3			0
2			0			0
3			3			6
4			0			9
5			0			0
6			0			3
7			6			12
8			3			18
9			0			0
10			0			6
11			6			0
12			9			0
13			0			3
14			3			0
15			3			9
16			0			0
17			0			6
18			6			3
19			3			12
20			9			9
21			6			21
22			0			15
23			0			0
24			3			3
25			3			9
26			0			6
27			3			3
28			0			0
29			6			0
30			0			0
31			3			3
32			3			6
33			0			9
34			6			0
35			6			0
36			3			3
37			0			3
38			2			3
39			0			0
40			0			12
41			6			3
42			6			3
43			3			6
44			0			9
45			0			15

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9/28/94 Time: 1100 Building: 875 Room: as required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46		0	46		0
47		3	47		0
48		6	48		0
49		0	49		3
50		0	50		6
51		3	51		9
52		3	52		0
53		0	53		12
54		0	54		0
55		9	55		0
56		0	56		3
57		6	57		9
58		3	58		21
59		0	59		3
60		0	60		0
61		6	61		0
62		6	62		12
63		3	63		0
64		3	64		3
65		9	65		3
66		0	66		0
67		3	67		57
68		0	68		30
69		0	69		21
70		0	70		0
71		0	71		12
72		0	72		36
73		9	73		27
74		0	74		12
75		0	75		6
76		3	76		0
77		0	77		21
78		3	78		48
79		0	79		0
80		3	80		45
81		3	81		6
82		0	82		15
83		6	83		0
84		0	84		0
85		9	85		36
86		3	86		12
87		6	87		9
88		6	88		0
89		0	89		0
90		0	90		3

RADIOLOGICAL OPERATIONS Alpha-Beta Survey

RESULTS

Date: 9-27-94 Time: 1100 Building: 875 Room: as Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
91		9	91		12
92		3	92		18
93		12	93		39
94		12	94		0
95		6	95		15
96		3	96		36
97		12	97		0
98		9	98		24
99		6	99		0
100		3	100		0
101		0	101		12
102		0	102		9
103		6	103		3
104		2	104		6
105		9	105		0
106			106		
107			107		
108			108		
109			109		
110			110		
111			111		
112			112		
113			113		
114			114		
115			115		
116			116		
117			117		
118			118		
119			119		
120			120		
121			121		
122			122		
123			123		
124			124		
125			125		
126			126		
127			127		
128			128		
129			129		
130			130		
131			131		
132			132		
133			133		
134			134		
135			135		

Radiological Operations
Area or Equipment Drawing Showing Survey Points



1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16
17	18	19	20
21	22	23	24
25	26	27	28
29	30	31	32
33	34	35	36
37	38	39	40
41	42	43	44
45	46	47	48
49	50	51	52
53	54	55	56
57	58	59	60

61	62	63	64	65	66	67	68	69
70	71	72	73	74	75	76	77	78
79	80	81	82	83	84	85	86	87
88	89	90	91	92	93	94	95	96
97	98	99	100	101	102	103	104	105

underground portion
of tunnel

mezanine portion
of tunnel

**886/875 TUNNEL
BASELINE**

Alpha - Beta Survey

Control #: _____

Taken by *[Signature]*
Signature

Employee #: [REDACTED]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: <u>9-28-94</u> Building: <u>886/875</u> Time: <u>0900</u> Room: <u>Tunnel</u> Shift: <u>Day</u>	Survey Description: <u>Baseline Survey</u> <u>886/875 tunnel u.s. 100 Bicon</u> Diagram/Sketch Attached: yes <input checked="" type="checkbox"/> no <input type="checkbox"/>
---	--

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	Bicon	_____	_____
Model:	31	12-1A	A+100	_____	_____
Serial#:	_____	_____	8766A	_____	_____
Date Cal.:	_____	_____	8-94	_____	_____
Cal. Due:	_____	_____	2-95	_____	_____
BKGAD:	_____	_____	0	_____	_____

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 10-03-94

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-28-94 Time: 0900 Building: 875 Room: CS Required

ALPHA			BETA		
CFM Removable (Swipe)	DPM CFM Direct	DPM/100cm2 Removable (smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (smear)
1			1		
2			2		
3			3		
4			4		
5	29		5		
6			6		
7			7		
8			8		
9			9		
10	34		10		
11			11		
12			12		
13			13		
14			14		
15	10		15		
16			16		
17			17		
18			18		
19			19		
20	36		20		
21			21		
22			22		
23			23		
24			24		
25	41		25		
26			26		
27			27		
28			28		
29			29		
30	21		30		
31			31		
32			32		
33			33		
34	15 ⁹⁻²⁸⁻⁹⁴		34		
35	15		35		
36			36		
37			37		
38			38		
39			39		
40	31		40		
41			41		
42			42		
43			43		
44			44		
45	46		45		

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 9-28-99 Time: 0900 Building: 875 Room: as Required

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
46			46		
47			47		
48			48		
49			49		
50	46		50		
51			51		
52			52		
53			53		
54			54		
55	46		55		
56			56		
57			57		
58			58		
59			59		
60	41		60		
61			61		
62			62		
63			63		
64			64		
65	77		65		
66			66		
67			67		
68			68		
69			69		
70	31		70		
71			71		
72			72		
73			73		
74			74		
75	51		75		
76			76		
77			77		
78			78		
79			79		
80	26		80		
81			81		
82			82		
83			83		
84			84		
85	31		85		
86			86		
87			87		
88			88		
89			89		
90	67		90		

RADIOLOGICAL OPERATIONS
Alpha-Beta Survey

RESULTS

Date: 4-28-94 Time: 0900 Building: 875 Room: as Recd

ALPHA			BETA		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
91			91		
92			92		
93			93		
94			94		
95	21		95		
96			96		
97			97		
98			98		
99			99		
100	31		100		
101			101		
102			102		
103			103		
104			104		
105	26		105		
106			106		
107			107		
108			108		
109			109		
110			110		
111			111		
112			112		
113			113		
114			114		
115			115		
116			116		
117			117		
118			118		
119			119		
120			120		
121			121		
122			122		
123			123		
124			124		
125			125		
126			126		
127			127		
128			128		
129			129		
130			130		
131			131		
132			132		
133			133		
134			134		
135			135		

Radiological Operations
Area or Equipment Drawing Showing Survey Points



1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16
17	18	19	20
21	22	23	24
25	26	27	28
29	30	31	32
33	34	35	36
37	38	39	40
41	42	43	44
45	46	47	48
49	50	51	52
53	54	55	56
57	58	59	60

underground portion
of tunnel

61	62	63	64	65	66	67	68	69
70	71	72	73	74	75	76	77	78
79	80	81	82	83	84	85	86	87
88	89	90	91	92	93	94	95	96
97	98	99	100	101	102	103	104	105

mezanine portion
of tunnel

**886/875 TUNNEL
BASELINE**

RADIOLOGICAL OPERATIONS
Alpha - Beta Survey

Control #: _____

Taken by [Signature]
Signature

Employee #: [Redacted]

Taken by _____
Signature

Employee #: _____

Taken by _____
Signature

Employee #: _____

Date: 10-26-94 Building: 886

Survey Description: _____

Time: 1400 Room: 102

Overhead Survey Rm# 102

Shift: Day

Diagram/Sketch Attached: yes X no _____

INSTRUMENTATION USED

SMEAR COUNTERS

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	SAC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

Mfg.:	Eberline	Eberline	Eberline	Eberline	Eberline
Model:	BC - 4				
Serial#:	_____	_____	_____	_____	_____
Date Cal.:	_____	_____	_____	_____	_____
Cal. Due:	_____	_____	_____	_____	_____

SURVEY INSTRUMENTS

Mfg.:	Ludlum	Ludlum	_____	_____
Model:	31	12-1A	_____	_____
Serial#:	_____	62753	_____	_____
Date Cal.:	_____	6-94	_____	_____
Cal. Due:	_____	12-94	_____	_____
BKGRD:	_____	1250	_____	_____

COMMENTS:

STATUS:

- Within Limits
- Limits Exceeded
- Posted
- Deposed

Radiological Operations Foreman

[Signature]
Signature

Date: 10-27-94

RADIOLOGICAL OPERATIONS
Alpha Survey


RESULTS

Date: 10-26-94 Time: 1400 Building: 886 Room: 102

ALPHA			RESURVEY		
CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)	CFM Removable (Swipe)	CFM Direct	DPM/100cm2 Removable (Smear)
1	<250		1		
2	<250		2		
3	<250		3		
4	<250		4		
5	<250		5		
6	<250		6		
7	<250		7		
8	<250		8		
9	<250		9		
10	<250		10		
11	<250		11		
12	<250		12		
13	<250		13		
14	<250		14		
15	<250		15		
16	<250		16		
17	<250		17		
18	<250		18		
19	<250		19		
20	<250		20		
21	<250		21		
22	<250		22		
23	<250		23		
24	<250		24		
25	<250		25		
26	<250		26		
27			27		
28			28		
29			29		
30			30		
31			31		
32			32		
33			33		
34			34		
35			35		
36			36		
37			37		
38			38		
39			39		
40			40		
41			41		
42			42		
43			43		
44			44		
45			45		

Radiological Operations
Area or Equipment Drawing Showing Survey Points

ROOM# 102 BUILDING 886



**RADIATION PROTECTION
Contamination Survey**

Taken by: _____
 Taken by: TA (BROWN)
 Taken by: KL Pearson

Emply# _____
 Emply# _____
 Emply# _____

Date: 7-14-94 Building: 886
 Time: 0945 Room #: 102
 Shift: Days

Survey Description: Contamination
Survey room 102 Building 886
Alpha + Beta
Floor Smears (Shelves + Items
in room swipe Alpha only)

**Instrumentation Used
SMEAR COUNTERS**

Mfg:	1. <u>Eberline</u>	2. <u>Eberline</u>	3. <u>Eberline</u>	4. <u>Eberline</u>	5. <u>Eberli</u>
Model:	1. <u>SAC - 4</u>	2. <u>SAC - 4</u>	3. <u>SAC - 4</u>	4. <u>SAC - 4</u>	5. <u>SAC -</u>
Serial #:	1. <u>864</u>	2. <u>868</u>	3. _____	4. _____	5. _____
Date Per. CK:	1. <u>7-14-94</u>	2. <u>7-14-94</u>	3. _____	4. _____	5. _____
Date Calib'd:	1. <u>10-5-93</u>	2. <u>10-1-93</u>	3. _____	4. _____	5. _____
Cal. Due Date:	1. <u>10-94</u>	2. <u>10-94</u>	3. _____	4. _____	5. _____

Mfg:	6. <u>Eberline</u>	7. <u>Eberline</u>	8. <u>Eberline</u>	9. <u>Eberline</u>	10. <u>Eberli</u>
Model:	6. <u>SAC - 4</u>	7. <u>SAC - 4</u>	8. <u>SAC - 4</u>	9. <u>SAC - 4</u>	10. <u>SAC -</u>
Serial #:	6. _____	7. _____	8. _____	9. _____	10. _____
Date Per. CK:	6. _____	7. _____	8. _____	9. _____	10. _____
Date Calib'd:	6. _____	7. _____	8. _____	9. _____	10. _____
Cal. Due Date:	6. _____	7. _____	8. _____	9. _____	10. _____

OTHER INSTRUMENTS

Mfg:	1. <u>Ludlum</u>	2. <u>Ludlum</u>	3. <u>Ludlum</u>	4. <u>Ludlum</u>	5. <u>Ludlum</u>
Model:	1. <u>12 - 1A</u>	2. <u>12 - 1A</u>	3. <u>12 - 1A</u>	4. <u>12 - 1A</u>	5. <u>12 - 1A</u>
Serial #:	1. _____	2. _____	3. _____	4. _____	5. _____
Date Per. CK:	1. _____	2. _____	3. _____	4. _____	5. _____
Date Calib'd:	1. _____	2. _____	3. _____	4. _____	5. _____
Cal. Due Date:	1. _____	2. _____	3. _____	4. _____	5. _____

COMMENTS

Smears 1-40 of Floor counted for Alpha + Beta
Swipes 41-42 of carts, Swipes 43-45 of ladders, 46-52 of overhead
lights, Swipes 53-54 of tables, 55 chair, 56 Welder, 57-90 swipes of
blue shelves

Status: Within Limits
 Limits Exceeded
 Posted
 Deposited

Radiological Operations Foreman
Curtis Bean 7-14-94
 Signature Date

Contamination Survey

RESULTS

Date: 7-14-94 Time: 0945 Building: 556 Room: 102

A/Fa
~~Initial~~

UB

Beta
~~Resurvey~~

~~CPM~~

CPM
Removable
(Swipe)

CPM
Direct

DPM/100cm²
Removable
(Smear)

CPM
Removable
(Swipe)


CPM
Direct

DPM/100cm²
Removable
(Smear)

46.	1250			46.		
47.	1250			47.		
48.	1250			48.		
49.	1250			49.		
50.	1250			50.		
51.	2250			51.		
52.	1250			52.		
53.	1250			53.		
54.	1250			54.		
55.	1250			55.		
56.	1250			56.		
57.	1250			57.		
58.	2250			58.		
59.	2250			59.		
60.	1250			60.		
61.	1250			61.		
62.	2250			62.		
63.	2250			63.		
64.	1250			64.		
65.	2250			65.		
66.	1250			66.		
67.	1250			67.		
68.	1250			68.		
69.	1250			69.		
70.	1250			70.		
71.	1250			71.		
72.	1250			72.		
73.	2250			73.		
74.	1250			74.		
75.	1250			75.		
76.	1250			76.		
77.	1250			77.		
78.	1250			78.		
79.	1250			79.		
80.	1250			80.		
81.	1250			81.		
82.	1250			82.		
83.	1250			83.		
84.	1250			84.		
85.	1250			85.		
86.	1250			86.		
87.	1250			87.		
88.	2250			88.		
89.	1250			89.		
90.	1250			90.		

Radiation Protection
Area or Equipment Drawing Showing Survey Points

Building 886



ROOM 102

Total Survey Points

APPENDIX B

CHEMICAL HAZARDS CHARACTERIZATION RESULTS



RIN # 98D0452

Sampling Record November, 20, 1997

Project: 886 Cluster RCLP

Building: 886

Room (if applicable):

Area is classified as (circle as appropriate): Affected Unaffected
 Analysis (circle as appropriate): Asbestos PCB Swipe PCB media Lead/Metals

Room

Rm 111-7

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
886-971119-MS-001	Condensate tank/mud+canvas/3'E of W wall, 2'S of W door, 2' above floor	
886-971119-MS-002	Condensate tank/mud+canvas/2'E of W wall, 2'S of W door, 3' above floor	
886-971119-MS-003	Condensate tank/mud+canvas/3'E of W wall, 4'S of W door, 3' above floor	
886-971119-MS-004	Block wall/mortar, skim 1" ^{E of S door} South wall, 5.5' above floor	
886-971119-MS-005	Chiller return elbow/mud+canvas fit/9'E of W wall, 2.5' N of S wall, 7' above floor	
886-971119-MS-006	Chiller return valve/mud+canvas/15'E of W wall, 2.5' N of S wall, 6.5' above floor	
886-971119-MS-007	Chiller supply elbow/mud+canvas/2' W of E wall, 3.5' N of S wall, 3' above floor	
886-971119-MS-008	steam supply straight / block / 13.5' E of W wall, 2' N of S wall, 6' above floor	
886-971119-MS-009	steam supply tee / mud+canvas / 13.5' E of W wall, 2' N of S wall, 4.5' above floor	
886-971119-MS-010	steam supply straight / block / 14' E of W wall, 7' N of S wall, 6' above floor	
886-971119-MS-011	steam supply straight / block / 3' E of W wall, 6' N of S wall, 8.5' above floor	
Rm 106 886-971119-MS-012	^{willow} Floor tile Room 106 / 6.5' E of W wall, 5.5' N of S wall, Floor	
Rm 106 886-971119-MS-013	^{carpet mastic} DUCT / WALL PENETRATION FILLER 2.5' E of W wall, S wall, 9' above floor	
Rm 107 886-971119-MS-014	Black 4" Cove base / 5' W of E wall, 1.5' N of S wall, 2" above floor	
Rm 107 886-971119-MS-015	Ceiling tile, ^{longitudinal grooves, pits + pin holes} 13' W of E wall, 6' N of S wall, Ceiling	
Rm 107 886-971119-MS-016	9" brown floor tile, 10' W of E wall, 6' N of S wall, floor	
Rm 107 886-971119-MS-017	Concrete Wall, 3' W of E wall, 5' above floor, South Wall	
	# 11/20/97	

Evaluated/Sampled by: *Phill Solomon*
 Date: 11/20/97

Reviewed by: *M. J. [Signature]* CAI
 Date: 11/25/97

RIN# 98D0452

Sampling Record Nov 20, 1997

Project: 886 Cluster RCLP

Building: 886

Room (if applicable):

Area is classified as (circle as appropriate): Affected

Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe

PCB media

Lead/Metals

Room	Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
Rm 115	886-971119-MS-018	Mortar/wall surfacing material, 2.5' S of N wall, 1' W wall, 5' above floor	
	886-971119-MS-019	Linoleum floor (sheet vinyl), 3' S of N wall, 0.5' W of E wall, floor	
	886-971119-MS-020	Greycove base, 3' S of N wall, E wall, 2" above floor	
	886-971119-MS-021	Ceiling tile, light tan, rectangular grooves, 1' S of N wall, 2' W of E wall, ceiling	
REAL	886-971119-MS-022	Ceiling tile, light tan, rectangular grooves, 0.5' S of N wall, 4.5' W of E wall, ceiling	
DUPLICATE	886-971119-MS-023	Ceiling tile, light tan, rectangular grooves, 0.5' S of N wall, 4.5' W of E wall, ceiling	
Rm 110	886-971119-MS-024	Domestic water elbow med + canvas NW corner of Room 6.5' above floor	
Rm 110	886-971119-MS-025	Floor tile 9" TAN/white flecks, 1' N of S wall, 3' E of W wall, on floor	

Evaluated/Sampled by:

Abbi Solomon

Date:

11/20/97

Reviewed by:

M. J. [Signature] CAI

Date:

11/25/97

Sampling Record November 21, 1997

Project: 886 Cluster RCLP

Building: 886

Room (if applicable):

Area is classified as (circle as appropriate): Affected Unaffected
 Analysis (circle as appropriate): Asbestos PCB Swipe PCB media Lead/Metals

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
Rm 113 Rm 116 886-971119-MS-026	9" floor tile beige with brown streaks / 4.5' W of E wall, 0.5' N of S wall, floor	
Rm 116 886-971119-MS-027	Rm 116 floor tile / carpet 8' W of E wall, 4' N of S wall, floor	
Rm 116 886-971119-MS-028	WALL PLASTER / 2' N of S wall, W wall, 4.5' above floor	
Rm 116 886-971119-MS-029	Duplicate of 886-971119-MS-028	
Rm 119 886-971119-MS-030	floor tile, 9" green tan checkerboard / 0.5' W of E wall, 0.5' S of N wall, floor	
886-971121-MS-031	Mortar/wall surfacing material / W wall, 4' S of E wall, 5' above floor	
886-971121-MS-032	Wall Plaster 1.5' E of W wall, N wall, 4' above floor	
Rm 123 886-971121-MS-033	9" floor tile red and tan checkerboard / 6.5' E of W wall, 0.5' N of S wall, floor	
886-971121-MS-034	Ceiling tile wide shallow kt. grooves / 6' W of E wall, 2' S of N wall, ceiling	
886-971121-MS-035	Ceiling tile latitudinal mastic P.H. / 2' W of E wall, 2' S of N wall, ceiling	
? Rm 129 886-971121-MS-036	Ceiling tile lat. room holes, etc. P.H. / 2' N of S wall, 4' W of E wall ceiling	
Rm 129 886-971121-MS-037	floor tile - unknown style / 0.5' W of E wall, 0.5' N of S wall, floor	
Rm 129 886-971121-MS-038	floor tile - unknown style / 0.5' E of W wall, 0.5' N of S wall, floor	
Rm 131 886-971121-MS-039	ceiling tile mastic pattern Mortar/wall surfacing material, 3' N of S wall, W wall, 3' above floor	
MAIN Entrance 886-971121-MS-040	Wall Plaster 6' W of E wall, N wall, 5.5' above floor	HS 11/21/97
886-971121-MS-041	Dry wall 3' E of W wall, N wall, 6' above floor	
886-971121-MS-042	Dry Wall 1' E of W wall, N wall, 8' above floor	
886-971121-MS-043	Dry Wall 1' W of E wall, N wall, 8' above floor	
130 886-971121-MS-044	Wall Plaster ^{HS 11/21/97} Dry Wall, 5' N of S wall, E wall, 5' above floor	
Rm 131 886-971121-MS-040	Dry wall, tape and joint compound, NE corner of room, 3.5' above floor	

Evaluated/Sampled by:

Date:

Abji Salou
11/21/97

Reviewed by:

Date:

M. Salou
11/25/97

Sampling Record *SAMPLES FROM Nov 24, 1997*

Project: 886 Cluster RCLP

Building: *886*

Room (if applicable):

Area is classified as (circle as appropriate): Affected Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe PCB media Lead/Metals

Rm 128
Rm 125
Rm 127
Rm 118
Rm 120
Rm 117
Rm 114
Rm 117
Rm 112
Rm 112
Rm 126

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
886-971121-MS-046	Draywall, tape, and Joint compound, SE corner of room, 4' above floor	
886-971121-MS-047	Wall Plaster, 3 feet S of N wall, E wall, 5' above floor	
886-971121-MS-048	Cinder block/mortar/skim 5' S of N wall, West wall, 5' above floor	
886-971121-MS-049	Goose base, 4" light brown / 6.5' E of W wall, N wall, 2" above floor	
886-971121-MS-050	Wall Plaster / 4.5' S of N wall / E wall / 6' above floor	
886-971121-MS-051	Goose base, 4" Dark brown / 4.5' E of W wall, S wall, 2" above floor	
886-971121-MS-052	Ceiling tile wide lat grooves, P.H. / 10' W of E wall, 6.5' N of S wall, ceiling	
886-971121-MS-053	Cinder block, mortar, surfacing material / 6' N of E wall, S wall, 6' above floor	
886-971121-MS-054	Duplicate of 886-971121-MS-053 / 6' N of E wall, S wall, 6' above floor	
886-971121-MS-055	floor tile 9" gray with black / 10' W of E wall, 9' N of S wall, floor	
886-971121-MS-056	Wall Plaster / 8' N of S wall, E wall, 5' above floor	
886-971121-MS-057	floor tile 9" light brown + beige checkerboard / 6' W of E wall, S wall (at door), floor	
886-971121-MS-058	floor tile 9" gray + blue-gray checker / 4' S of N wall, 1' W of E wall, floor	
886-971121-MS-059	Wall Plaster / 14' S of N wall, E wall, 5' above floor	
886-971121-MS-060	sheet vinyl w/ floor tile / half way between doors to 112, 113, 0.5' E of W wall, floor	
886-971121-MS-061	Cinder block, mortar, surfacing material / 3.5' E of Rm 116 door, S wall, 5' above floor	
886-971121-MS-062	Cinder block, mortar, surfacing material / 2' N of Rm 127 door, E wall, 5' above floor	
886-971121-MS-063	Cinder block, mortar, surfacing material / 1' S of Rm 118 door, E wall, 6' above floor	
	<i>11/24/97</i>	

Evaluated/Sampled by: *[Signature]*

Date: *11/24/97*

Reviewed by: *[Signature]*

Date: *11/25/97*

Sampling Record *SAMPLES COLLECTED OUTSIDE OF BUILDING 886 ON Nov 25, 1997*

Project: 886 Cluster RCLP

Building: 886

Room (if applicable):


Area is classified as (circle as appropriate): Affected

Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe

PCB media

Lead/Metals

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
886-971124-MS-064	T.S.I. on duct/control on HVAC / 30'S of Rm 140 S wall, 4.5' N of W outside wall, 10' above ground	
886-971124-MS-065	T.S.I. on duct/control on HVAC / 11'S of Rm 140 S wall, 5' W of W outside wall, 11' above ground	
886-971124-MS-066	T.S.I. on duct/control on HVAC / 4'S of Rm 140 S wall, 4.5 W of W outside wall, 10' above ground	
886-971124-MS-067	Texture on concrete / 12.5' N of SW corner of building (Rm 101), 1.5' above ground	
886-971124-MS-068	Texture on concrete / 7' E of SW corner of building (Rm 101), 3.5' above ground	
886-971124-MS-069	Texture on concrete / 19' N of SE corner of building (Rm 101), 5' above ground	
886-971124-MS-070	Texture on outside cinder block / 12' N of Rm 140 N wall, W wall, 5' above ground	
886-971124-MS-071	Texture on outside cinder block / 27' N of SW corner of building (Rm 101) S' W of W wall, 5' above ground	
886-971124-MS-072	Texture on outside cinder block / 1' N of BW 886 Door 3 (Rm 112), E wall, 4' above ground	
886-971124-MS-073	Duplicate of 886-971124-MS-072	
	→ These 4 samples: Beige over green ^{texture MS 11/25/97} in cinder block	
	→ These 3 samples: Beige over white texture over concrete	
 11/25/97		

OUTSIDE OF 886 (OUTSIDE WALLS)

Evaluated/Sampled by: *[Signature]*

Date:

11/25/97

Reviewed by: *[Signature]*

Date:

11/25/97

Project: 886 Cluster RCLP
 Building: 888 Guard Shack
 Room (if applicable):

Area is classified as (circle as appropriate): Affected
 Analysis (circle as appropriate): Asbestos PCB Swipe

~~MS~~ 12/8/97
~~Unaffected~~
 PCB media Lead/Metals

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
886-971124-MS-026	Drywall tape and joint compound; from SW corner main area (west wall) 5' from floor	
886-971124-MS-027	Drywall tape and joint compound; from N edge of partition wall 5' from floor	
886-971124-MS-028	Drywall tape and joint compound; from SW corner of restroom wall 5' from floor	
MS 12/9/97		

Evaluated/Sampled by: M Schlaterbusch
 Date: 12/8/97


Reviewed by: Krist Kelly
 Date: 12/8/97

signed *[Signature]*
Hopi Salomon 11/25/97
M. Salomon

BUILDING 886 RCLP Asbestos Sampling Locations

Not to Scale

= SAMPLE LOCATIONS THAT CORRESPOND TO THE last 3 digits of the sample number.
(886-971121-MS---, 886-971124-MS---)




BUILDING 886 RCLP



Not to scale

BUILDING 886 Asbestos Sampling Location

⊕ = Sample locations that correspond with last three digits of the sample number
(886-971121-MS-...)



Building 886 RLCP

Signed *Hopi Selamon* Hopi Selamon (paperwork guy) 11/25/97

M. Schlotterbusch - M Schlotterbusch CAI 11/25/97

Asbestos Sample Locations
in CA in Buildings 886

Ⓝ = sample locations that correspond to the last 3 digits of the Sample #

(886-971124-MS- - -)


SAMPLED ON Dec 2, 1997

Building 886 RLCP

3

Note: These core samples (asbestos) were collected at the same locations as TCLP metal core samples

Asbestos #	TCLP #
074	98A045-007=004
075	98A045-008,004



SAMPLED 12/2/97

recorded by
Philip Salton 12/2/97
Reviewed by [Signature] 12/15/97

D4

A

48'-0"

TUNNEL TO BLDG. 875

CONC. CURB

0

5

141

101

102

108

074

075

103

104

107

109

106

113

115


110

112

114

Asbestos sample locations on outside of Bld. 886
 Sampled 11/25/97

⊕ = sample locations that correspond to the last three digits of the sample number (886-971124-MS-...)



Samplers - *John Schuman* (paperwork) 11/25/97
 A.I. - *Mike Schuman* (sample acquisition) 11/25/97
 HSS - *B. Somers* 11-25-97
 Wood HL + E. Kelly 11-25-97


Buildings 886 RLCF

BUILDING 886 - FIRST FLOOR PLAN

MASTER DRAWING
 MAINTAIN AS-BUILT PER CODE 6.6.2

Asbestos Sample Locations - Building 888 12/8/97

Sample Location - Schematic



Illustrated by: M Schluterbusch
Date: 12/8/97
Reviewed by: *[Signature]*
Date: 12/9/97

Rocky Flats Environmental Technology Site

Golden CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

RFP F 3791.32 (7/95)
Formerly P 530

RIN 78D0452

Name of Originator: Mike Schlatterbusch Title: CAI Bldg/Ext: 78DJ/4215 Date: Nov 20, 1997 Page 1 of 3

SAMPLE NUMBER Bldg/Y/M/D/P/#/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/ TIME/	MEDIA	Personal Area Bulk		REMARKS	Lab Number
					P	A		
886-971119-MS-001	Asbestos/PLM		1000		B		Archive for Point Count	
002								
003								
004								
005								
006								
007								
008								
009								
010			1000					
011			1455					
012			1455					
886-971119-MS-016	Asbestos/PLM		1455		B		Archive for Point Count	

Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
Neil [Signature]	April [Signature]	0830 11/20/97	April [Signature]	April [Signature]	1155 11/21/97
John [Signature]	K. [Signature]	1505 11/21/97			

Report and Billing Instruction

Kaiser-Hill Verbal To: _____
 RMRS Fax To: 966-4046
 SSOC Report To: 966-6538
 DynCorp Bill To: _____
 WSI P.O.#/Release: MEHMA
 Lab: Reservoir

Analysis Request

Industrial Hygiene Sample
 Standard Service
 Asbestos Samples 24 Rush 2 Rush Other

Seal# (Release #) KIN 10D0452
 Condition of Seal: Broken Unbroken

Signature: [Signature]
 Comments: Row Sealed Bags
 Signed off Per Bag #11

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

RIN 78D0452

Safety and Hygiene Chain of Custody Record and Analysis Request

Golden 80402-0464

ENVIRONMENTAL TECHNOLOGY SITE

Name of Originator: Mike Schlotterbach Title: CAI Bldg/Ext: T1305/4315 Date: Nov 30, 1997 Page 2 of 2

SAMPLE NUMBER Bldg/Y/M/D/P/#/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	Personal Area Bulk		REMARKS	Lab Number
					A	B		
886-971119-MS-017 018	Asbestos/PLM		1455		B		Archives for Point Count	
019			1520					
020			1520					
021			1520					
022			1520					
023			1520					
024			1600					
886-971119-MS-025	Asbestos/PLM		1604		B		Archives for Point Count	
# 11/20/97								
Relinquished by <u>M. Schlotterbach</u>	Received by <u>M. Schlotterbach</u>	Time/Date 11/20/97 0030	Relinquished by <u>M. Schlotterbach</u>	Received by <u>M. Schlotterbach</u>	Time/Date 11/20/97			
Relinquished by <u>M. Schlotterbach</u>	Received by <u>K. P. ...</u>	Time/Date 11/20/97	Relinquished by <u>M. Schlotterbach</u>	Received by <u>K. P. ...</u>	Time/Date 11/20/97			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			

Report and Billing Instruction

Kaiser-Hill Verbal To: 966-4046

RMRS Fax To: 966-6538

SSOC Report To: _____

DynCorp Bill To: _____

WSI P.O.#/Release: ME944A

Lab: Lab 2500

Analysis Request

Industrial Hygiene Sample

Standard Service Rush Other

Asbestos Samples 24 2 Other

Rush Standard Service

Seal# (Release #) KIN 18DC452

Condition of Seal: Broken Unbroken

Signature: _____

Comments: Rec'd sealed bags signed off per bags

Rocky Flats Environmental Technology Center

Golden CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

RFP F 3791 (7/95)
Formerly F 330

KIN 92D 0452

Name of Originator: Mike Schluter, bush Title: CHAI Bldg/Ext: T130J/4215 Date: Nov 21, 1997 Page 1 of 7

SAMPLE NUMBER Bldg/Y/M/D/P#S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA		P Personal A Area B Bulk		REMARKS	Lab Number
886-971119-MS-026 -027 -028 -029	PLM/Asbestos		0858 0915 0915			B	Archive for Point Count		
886-971121-MS-031 -032 -033 -034 -035 -036 -037 -038 -039 -040			0940 0940 1020 1020 1020 1055 1055 1120 1120 1120			B	Archive for Point Count		
886-971121-MS-041			1115			B	Archive for Point Count		

Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
<i>[Signature]</i>	<i>[Signature]</i>	11/21/97	<i>[Signature]</i>	<i>[Signature]</i>	11/21/97
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date

Report and Billing Instruction

Verbal To: (fax) 416-4046 - Hopi Sciences
 Fax To: 966 6538 - Mike
 Report To:
 Bill To: MEQUINA
 P.O.#/Release: 10/21/97
 Lab:

Analysis Request

Industrial Hygiene Sample
 Standard Service
 Rush
 Other

Asbestos Samples
 24
 2
 Other
 Rush

Seal# (Release #) KIN 97D 0452
 Condition of Seal: Broken Unbroken
 Signature: *[Signature]*
 Comments: Record sealed bags signed by COC per bag #10

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

Safety and Hygiene Chain of Custody Record and Analysis Request

WIN 98D 0452

Name of Originator: Mike Schlotterbusch Title: CAI Bldg/Ext: T1305/4A15 Date: Nov 21, 1997 Page 2 of 2

SAMPLE NUMBER Bldg/Y/M/D/P#/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P		REMARKS	Lab Number
					A	B		
886-971121-MS-043	PLM/Asbestos		1145		B		Acrylic for point count	
-044			1145					
886-971121-MS-045			1202					
			1202					
11/21/97								
Relinquished by <i>M. Schlotterbusch</i>	Received by <i>J. [unclear]</i>	Time/Date 1433 11/21/97	Relinquished by <i>[unclear]</i>	Received by <i>R. [unclear]</i>	Time/Date 1505 11/21/97			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			

Report and Billing Instruction

Kaiser-Hill Verbal To: Mike Schlotterbusch 866-6588

RMRS Fax To: How Schlotterbusch 866-6446

SSOC Report To: [unclear]

DynCorp Bill To: [unclear]

WSI P.O.#/Release: ME944A

Lab: K&E J011

Analysis Request

Industrial Hygiene Sample

Standard Service

Standard Service

24 Rush

2 Rush

Other

Asbestos Samples

Asbestos Samples

Other

Seal# (Release #) WIN 98D 0452

Condition of Seal: Broken Unbroken

Signature: [unclear]

Comments: [unclear]

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

Rocky Flats Environmental Technology Site

Golden, CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

RIN 9800452

Name of Originator: Mika Schuchbauer Title: CAI Bldg/Ext: 7305/4215 Date: Apr 24, 1997 Page 1 of 2

SAMPLE NUMBER Bldg/Y/M/D/P/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P		REMARKS	Lab Number
					A	B		
886-971121-MS-046	PLM/Asbestos		0900			B	Archive for Paint Count	
047			0912					
048			0923					
049			0955					
050			1000					
051			1010					
052			1102					
053			1045					
054			1045					
055			1055					
056			1051					
057			1027					
058			1110					
059			1114					
060			1131					
886-971121-MS-061	PLM/Asbestos		1141			B	Archive for Paint Count	

Relinquished by	Time/Date	Relinquished by	Time/Date	Received by	Time/Date
<i>M. Schuchbauer</i>	16:00 11/25/97				
Relinquished by	Time/Date	Relinquished by	Time/Date	Received by	Time/Date
Relinquished by	Time/Date	Relinquished by	Time/Date	Received by	Time/Date

Report and Billing Instruction

Kaiser-Hill Verbat To: Mike Schuchbauer 916-4011

RMRS Fax To: Mike Schuchbauer 916-4011

SSOC Report To: K-H

DynCorp Bill To: K-H

WSI P.O.#/Release: ME 944A

Lab: Reserv

Analysis Request

Industrial Hygiene Sample

Standard Service

Asbestos Samples

Standard Service

24 Rush

2 Rush

Other: 3 days

Seal# (Release #) RIN 9800452

Condition of Seal: Broken Unbroken

Signature: _____

Comments: _____

SIN 98D0452

Rocky Flats Environmental Technology Site

Golden, CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

Name of Originator: Hwy 1 Station Title: CAI

Bldg/Ext: T130J/4215

Date: Nov 25 1997

Page 1 of

SAMPLE NUMBER Bldg/Y/M/D/P#/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P Personal A Area B Bulk	REMARKS	Lab Number
886-971124-MS-064	<u>PM/A/Asbestos</u>		<u>0851</u>		<u>B</u>	<u>Asbestos for Print Count</u>	
-065			<u>0845</u>				
-066			<u>0835</u>				
-067			<u>0906</u>				
-068			<u>0920</u>				
-069			<u>0935</u>				
-070			<u>1013</u>				
-071			<u>1002</u>				
-072			<u>0945</u>				
886-971124-MS-073	<u>PM/A/Asbestos</u>		<u>0950</u>		<u>B</u>	<u>Asbestos for Print Count</u>	

AS 11/25/97

Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
<u>MA [Signature]</u>	<u>Bud D. [Signature]</u>	<u>1600 11/25/97</u>			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date

Report and Billing Instruction

Kaiser-Hill Verbal To: Hwy 1 Station 916-4046

RMRS Fax To: M. Seibert 916-6533

SSOC Report To: K-H

DynCorp Bill To: K-H

WSI P.O.#/Release: ME94AA

Lab: [Signature]

Analysis Request

Industrial Hygiene Sample

Standard Service

Rush

Asbestos Samples

Standard Service

Rush

Other: [Signature]

Seal# (Release #): RIN 9706452

Condition of Seal: Broken Unbroken

Signature: _____

Comments: _____

RW 98A 0453

Name of Originator: <u>Earl</u>		Title: <u>HSS</u>		Bldg/Ext: <u>TR/A</u> / <u>5356</u>		Date: <u>11-25-97</u>		Page <u>1</u> of <u>1</u>	
SAMPLE NUMBER Bldg/Y/M/D/P/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P A B	Personal Area Bulk	REMARKS	Lab Number	
886-971121-82-01	asbestos PCM	416.4	1230	MCF	A	0.3 um 15 min Millipore			
886-971121-82-02		blank	0700		P	0.3 um 15 min Millipore			
886-971124-82-01		345.7	1205		P	0.3 um 37 min Millipore			
886-971124-82-02		blank	0700		P	0.3 um 37 min Millipore			
11-25-97									
85									
Relinquished by <u>Paul D. Schaefer</u>	Received by <u>M. Schaefer</u>	Time/Date <u>15:25 11/25/97</u>	Relinquished by <u>M. Schaefer</u>	Received by <u>Paul D. Schaefer</u>	Time/Date <u>15:00 11/25/97</u>				
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date				
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date				
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date				

Report and Billing Instruction

Kaiser-Hill Verbal To: Tax 6538

RMRS Fax To: E. Schaefer 6533

SSOC Report To: R-H

DynCorp Bill To: R-H

WSI P.O.#/Release: ME 59 4A

Lab: Schaefer

Analysis Request

Industrial Hygiene Sample Rush Other

Asbestos Samples 24 Rush 2 Rush Other

Seal# (Release #) _____

Condition of Seal: Broken Unbroken

Signature: RW

Comments: 98A 0453

NVLAQ LAB NO. 1898

ASBESTOS - TEM, PCM, PLM, SEM
METALS - AA, FLAME/FURNACE
AIRBORNE PARTICULATES
SPECIAL PARTICLE ANALYSIS

AIHA LAB I.D. 10768

RESERVOIRS ENVIRONMENTAL

SERVICES, INC.

Fax Transmittal

RES Job: 47049

To: Mike S. Tom &

Company: Kaiser

Fax Number: 906-4046/6538 + 3400

From: Pj

Date: 11/24

Number of Pages: _____ (excluding cover sheet)



Message:

Refer w/ RIN #

Please call (303) 830-1986 or 800-678-7374 if transmission is incomplete.

RESERVOIRS ENVIRONMENTAL SERVICES, INC.
 NVLAP Accredited Laboratory #1896

Page 2 of 3

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47649-1

Client: Kaiser-Hill Company, LLC

Client Project: RIN 98D00452

Date Samples Received: November 21, 1997

Analysis Type: PLM Short Report, Bulk

Turnaround: 2 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)										Non-Fibrous Components (%)						
				BY LAYER	Visual Estimate (%)	C	G	S	H	W	T	O	E	L	A	N	J	L	L	C	E	R
886-971119-MS-006	EM 318279	A White fibrous woven material with white paint	8	ND		70	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	30
		B White fibrous plaster	92	15	Chrysotile Amosite	0	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-007	EM 318280	A White fibrous woven material with white paint	8	ND		70	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	30
		B White fibrous plaster	92	15	Chrysotile Amosite	TR	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-008	EM 318281	A White fibrous woven material w/white paint & tan fibrous material	7	ND		50	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	50
		B White fibrous plaster	93	15	Chrysotile Amosite	15	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-009	EM 318282	A White fibrous woven material with white paint	6	ND		70	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	30
		B White fibrous plaster	94	15	Chrysotile Amosite	TR	0	30	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-010	EM 318283	A White fibrous woven material with white paint	5	ND		80	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	20
		B Grey fibrous plaster	95	20	Amosite		0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

ND = None Detected
 TR = Trace, < 1% Visual Estimate
 CELL = Cellulose
 ORG = Organic
 Trans-Act = Tremolite-Actinolite
 WOLL = Wollastonite
 BRUC = Brucite
 GYP = Gypsum
 SYNTH = Synthetic
 Data QA

RESERVOIRS ENVIRONMENTAL SERVICES, INC.

NVLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47646-1
 Client: Kaiser-Hill Company, LLC
 Client Project: RIN98D0452, ME94AA
 Date Samples Received: November 21, 1997
 Analysis Type: PLM Short Report, Bulk
 Turnaround: 24 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)					Non-Fibrous Components (%)		
				BY LAYER	Visual Estimate (%)	C	E	L	L	S		H	
886-971119-MS-024	EM 318249	A White fibrous woven material w/white paint	4	ND	ND	90	0	0	0	0	0	0	10
		B White fibrous plaster	96	21	0	40	0	0	0	0	0	0	39
886-971119-MS-025	EM 318250	A Black tar	5	5	0	0	0	0	0	0	0	0	95
		B Tan tile	95	4	0	0	0	0	0	0	0	0	96

ND = Nons Detected
 TR = Trace, < 1% Visual Estimate
 CELL = Cellulose
 Trem-Act = Tremolite-Actinolite

WOLL = Wollastonite
 BRUC = Brucite

GYP = Gypsum
 SYNTH = Synthetic

Date CA

Rocky Flats Environmental Technology Site

Golden, CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

Name of Originator: Mike Schuster, Title: CAT

Bldg/Ext: T130 J/4215 Date: Nov 20, 1997 Page 2 of 2

RFP # 3701-32 (7/86)
Formerly RF-47530

BIN 98D045A

476A6

SAMPLE NUMBER Bldg/Y/MD/P/S#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P		REMARKS	Lab Number
					A	B		
886-971119-MS-017 018	Asbestos/PLM		1455		B		Archive for Point Count	
019			1520					
020			1520					
021			1520					
022			1520					
023			1520					
024			1600					
886-971119-MS-025	Asbestos/PLM		1604		B		Archive for Point Count	
11/20/97								
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			
<i>[Signature]</i>	<i>[Signature]</i>	11/20/97	<i>[Signature]</i>	<i>[Signature]</i>	11/21/97			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			
<i>[Signature]</i>	<i>[Signature]</i>	11/21/97	<i>[Signature]</i>	<i>[Signature]</i>	11/21/97			
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date			

Report and Billing Instruction

Kaiser-Hill: Verbal To: 966-4046

RMRS: Fax To: 966-6538

SSOC: Report To:

DynCorp: Bill To:

WSI: P.O.#/Release: KE94MA

Lab: Resvoir

Analysis Request

Industrial Hygiene Sample

Standard Service

Rush

Other

Asbestos Samples

2d

2d

Rush

Other

Seal# (Release #) RIN 98D0452

Condition of Seal: Broken Unbroken

Signature: *[Signature]*

Comments: Rev'd sealed bags
Signed off per bags

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

47641

Reentry-Phase-Environmental-Technology-Site

Golden, CO 80402-0464
Safety and Hygiene Chain of Custody Record and Analysis Request

RFP F 3781.22 (7/85)
Formerly RF-47830

RIN 98D 0452 Bldg/Ext: T130J/4215 Date: Nov 21, 1997 Page 2 of

Name of Originator: Mike Schlotzbecher Title: CAI	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA		REMARKS	Lab Number
				P A B	Personal Area Bulk		
886-971121-MS-042 -043 -044 826-971121-MS-045	Plum Asbestos		1145 1145 1202 1202		B	Archive for Point Count	
11/21/97							
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97	Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97	Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97	Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97
Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97	Relinquished by: <i>[Signature]</i>	Received by: <i>[Signature]</i>	Time/Date: 11/21/97	Time/Date: 11/21/97

Seal# (release #) RIN 98D 0452
 Condition of Seal: Broken Unbroken
 Signature: _____
 Comments: *[Handwritten]*
 signed cert of rep 11/21/97

Report and Billing Instruction

Kaiser-Hill Verbal To: *[Handwritten]*
 FMRS Fax To: *[Handwritten]*
 SSOCC Report To: *[Handwritten]*
 DynCorp Bill To: *[Handwritten]*
 WSI P.O.#/Release: ME94AA
 Lab: *[Handwritten]*

Industrial Hygiene Sample
 Standard Service Asbestos Samples
 Rush 2 Rush
 2 Rush

Analysis Request
 Industrial Hygiene Sample
 Asbestos Samples
 2 Rush

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

RESERVOIRS ENVIRONMENTAL SERVICES, INC.
 NVLAP Accredited Laboratory #1896

Page 3 of 3

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47648-1
 Client: Kaiser-Hill Company, LLC
 Client Project: RIN98D0452,
 Date Samples Received: November 21, 1997
 Analysis Type: PLM Short Report, Bulk
 Turnaround: 24 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Fibrous Components (%)											
				BY LAYER	Visual Estimate	Non-Asbestos Fibrous Components (%)					Non-Fibrous Components (%)						
Label				Mineral		C	G	S	H	A	O	L	L	C	E	R	
886-971119-MS-038	EM 318267	A Black tar	5		ND	0	0	0	0	0	0	0	0	0	0	0	
		B Tan resin	15		ND	2	0	0	0	0	0	0	0	0	0	0	0
		C Tan/brown tile	80	Chrysotile	8	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-039	EM 318268	A Multicolored paint	15		ND	0	0	0	0	0	0	0	0	0	0	0	
		B Gray granular plaster	85		ND	0	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-040	EM 318269	A Multicolored paint	5		ND	0	0	0	0	0	0	0	0	0	0	0	
		B White plaster	7		ND	1	0	0	0	0	0	0	0	0	0	0	0
		C Tan fibrous material	18		ND	97	0	0	0	0	0	0	0	0	0	0	0
		D White fibrous plaster	70		ND	10	0	0	0	0	0	0	0	0	0	0	0
886-971119-MS-041	EM 318270	A White paint w/white plaster (mud)	7-10		ND	0	0	0	0	0	0	0	0	0	0	0	
		B Tan fibrous material	28		ND	95	0	0	0	0	0	0	0	0	0	0	0
		C White plaster (drywall)	65		ND	5	0	0	0	0	0	0	0	0	0	0	0

ND = None Detected
 TR = Traces, < 1% Visual Estimate
 ORG = Organic
 CELL = Cellulose
 Trem-Act = Tremolite-Actinolite
 WOLL = Wollastonite
 BRUC = Brucite
 GYP = Gypsum
 SYNTH = Synthetic
 DAB OA

NVLAQ LAB NO. 1896

ASBESTOS - TEM, PCM, PLM, SEM
METALS - AA, FLAME/FURNACE
AIRBORNE PARTICULATES
SPECIAL PARTICLE ANALYSIS

IHA LAB I.D. 10768

RESERVOIRS ENVIRONMENTAL

SERVICES, INC.

Fax Transmittal

RES Job: 47729

To: Tom S., Hopi + Mike S.

Company: Kaiser

Fax Number: 916-3400-4046-6538

From: PJ

Date: 12/2

Number of Pages: 5 (excluding cover sheet)



Message:

Please call (303) 830-1986 or 800-678-7374 if transmission is incomplete.

Golden, CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

47729

Formally RIF-47830

RAIN 98D0452

Name of Originator: Mike Schlinker, Title: CAT Bldg/Ext: 7303/215 Date: Apr 24, 1997 Page 1 of 2

SAMPLE NUMBER Bldg/Y/M/D/P/PS#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P		REMARKS	Lab. # Number
					A	B		
886-971121-MS-046	PLM/Asbestos		0900		B	Archive for Point Count		
047			0919					
048			1023					
049			0955					
050			1000					
051			1010					
052			1102					
053			1045					
054			1045					
055			1055					
056			1051					
057			1087					
058			1110					
059			1114					
060			1131					
886-971121-MS-061	PLM/Asbestos		1141		B	Archive for Point Count		
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date	Time/Date	Time/Date	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date	Time/Date	Time/Date	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date	Time/Date	Time/Date	Time/Date
Relinquished by	Received by	Time/Date	Relinquished by	Received by	Time/Date	Time/Date	Time/Date	Time/Date

Report and Billing Instructions:

Kaiser-Hill Verbal To: Mike Schlinker 303-4054

RMRS Fax To: Mike Schlinker 303-4054

SSOC Report To: KS-H

DynCorp Bill To: KS-H

WSI P.O.#/Release: ME94A1

Lab: Res-env

Analysis Request:

Industrial Hygiene Sample

Standard Service Rush

Asbestos Samples 24 2 Other 3-5 days

Sea# (Release #) RIN 98D0452

Condition of Seal: Broken Unbroken

Signature: _____

Comments: _____

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

NVLAQ LAB NO. 1896

ASBESTOS - TEM, PCM, PLM, SEM
METALS - AA, FLAME/FURNACE
AIRBORNE PARTICULATES
SPECIAL PARTICLE ANALYSIS

AIHA LAB I.D. 10768

RESERVOIRS ENVIRONMENTAL SERVICES, INC.

Fax Transmittal

RES Job: 47732

To: Tom, Hopi + Mike S.

Company: Kaiser Hill

Fax Number: 916-3400, 4046, 6538

From: Pey

Date: 12/1

Number of Pages: 3 (excluding cover sheet)



Message:

Please call (303) 830-1986 or 800-678-7374 if transmission is incomplete.

RESERVOIRS ENVIRONMENTAL SERVICES, INC.
 NVLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number:

Client:

Date Samples Received:

Analysis Type:

Turnaround:

RES 47732-1

Kaiser-Hill Company, LLC

98D0452, MEB4AA

November 25, 1997

PLM Short Report, Bulk

3-5 Day

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Fibrous Components (%)															
				BY LAYER	Visual Estimate (%)	Non-Asbestos Fibrous Components (%)					Non-Fibrous Components (%)										
Layer				Mineral		C	G	S	H	W	T	O	E	L	A	N	I	L	C	H	R
886-971124-MS-069	EM 318906	A	30	Gray granular plaster	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		B	70	Multicolored resinous paint	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971124-MS-070	EM 318907	A	35	Gray granular plaster	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		B	65	Gray plaster w/tan/white paint	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971124-MS-071	EM 318908	A	40	Gray granular plaster	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		B	60	Green plaster w/tan & white paint	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971124-MS-072	EM 318909	A	25	Gray granular plaster	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		B	75	Green plaster w/tan & white paint	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
886-971124-MS-073	EM 318910	A	30	Gray granular plaster	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		B	70	Green plaster w/tan & white paint	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

ND = None Detected
 TR = Trace, < 1% Visual Estimate
 CELL = Cellulose
 ORG = Organic
 Trem-Act = Tremolite-Actinolite
 WOLL = Wollastonite
 BRUC = Brucite
 GYP = Gypsum
 SYNTH = Synthetic
 Data QA

Rocky Flare Environmental Technology Inc

Golden, CO 80402-0464

Safety and Hygiene Chain of Custody Record and Analysis Request

49132

RF-47630

98D0452

Name of Originator: Hop 1 Salgrem Title: CA I Bldg/Ext: T 1301/4015 Date: Nov 25, 1997 Page 1 of 1

SAMPLE NUMBER Bldg/MD/P/RS#	ANALYZE FOR	VOLUME liters	SAMPLE TIME/	MEDIA	P Personal		REMARKS	Lab Number
					A Area	B Bulk		
886-971124-MS-064	PM/Asbestos		0851		B		Asbestos for Paint Cont	
-065			0845					
-066			0835					
-067			0906					
-068			0920					
-069			0935					
-070			1013					
-071			1002					
-072			0945					
886-971124-MS-073	PM/Asbestos		0950		B		Asbestos for Paint Cont	

Relinquished by	Time/Date	Relinquished by	Time/Date	Received by	Time/Date
<i>[Signature]</i>	16:00 11/25/97	<i>[Signature]</i>	17:00 11-25-97		

Report and Billing Instruction Kaiser-Hill <input type="checkbox"/> Verbal To: <u>Hop 1 Salgrem 966-4016</u> RMRS <input checked="" type="checkbox"/> Fax To: <u>M. S. Kalkbush 866-6538</u> SSOC <input type="checkbox"/> Report To: <u>K-H</u> DynCorp <input type="checkbox"/> Bill To: <u>S-H</u> WSI <input type="checkbox"/> P.O.#/Release: <u>ME94AA</u> Lab: <u>Rosario</u>	Analysis Request <input type="checkbox"/> Standard Service <input type="checkbox"/> Industrial Hygiene Sample <input type="checkbox"/> Rush <input checked="" type="checkbox"/> Asbestos Samples <input type="checkbox"/> Standard Service <input type="checkbox"/> Rush <input type="checkbox"/> Other: <u>3-5 days</u>	Seal # (Release #) <u>98D 0452</u> Condition of Seal: <input type="checkbox"/> Broken <input type="checkbox"/> Unbroken Signature: _____ Comments: _____
---	---	---

White - Return to Originator Yellow - Lab Copy Green - Sample Custodian Blue - Originator

RESERVOIRS ENVIRONMENTAL SERVICES, INC.
 NVLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47964-1

Client: Kaiser-Hill Company, LLC

Client Project: RIN 98DO452

Date Samples Received: December 08, 1997

Analysis Type: PLM Short Report, Bulk

Turnaround: 24 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT BY LAYER Mineral	Non-Asbestos Fibrous Components (%)										Non-Fibrous Components (%)			
					C	G	L	E	L	A	S	T	R	S		H	W	T
886-971124-MS-074	EM 320266	A Multicolored paint w/trace gray plaster	3	Chrysotile	0	0	0	0	0	0	0	0	0	0	0	0	0	100
		B Gray granular plaster	97		0	0	0	0	0	0	0	0	0	0	0	0	0	100
886-971124-MS-075	EM 320267	A Gray granular plaster w/gray paint	100		0	0	0	0	0	0	0	0	0	0	0	0	0	100

ND = None Detected

TR = Trace, < 1% Visual Estimate

CELL = Cellulose

ORG = Organic

Tram-Act = Tremolite-Actinolite

WOLL = Wollastonite

BRUC = Brucite

GYP = Gypsum

SYNTH = Synthetic

Analyst: PDI

Date: 01/09/98

PROPERTY/WASTE RELEASE EVALUATION

PRE Number: 971119-T130B-002

Charge Number: ME92AARC

EXTENDED: EXPIRES:

PART I

SENDER/CUSTODIAN

Description of Property/Waste To Be Released/Transferred:

One hundred (100) bulk asbestos and air samples for asbestos analysis. See attached chain of custody for identification and attached contamination survey results.

Property's Current Location:

Building 886.

Property's Destination:

Reservoirs Environmental Services, 1827 Grant Street, Denver, CO 80203.

Property's New Recipient/Custodian:

Reservoirs Environmental Services.

Property History/Process Knowledge:

These one hundred bulk asbestos and air samples listed above were generated for asbestos characterization on the 886 cluster.

Has the specified property/waste ever been in an RMMA or contacted DOE controlled radioactive materials?

Unknown.

COPY

ACKNOWLEDGEMENT:

By signing below, the sender/custodian verifies the information above to be true and correct.

- (1) Samples shall be shipped in accordance with 49 CFR (DOT) requirements.
- (2) The receiving laboratory holds the necessary NRC/State license for the radionuclides being shipped; said license shall be formally documented, retrievable and traceable to each sample shipped.
- (3) Paragon Analytic is licensed to handle nuclear material under Colorado Department of Public Health and Environment Nuclear Material License #847-02, Expiration 11/20/97. See attached letter for confirmation/renewal.

Date: 11/20/97 Ext: 6047 Pager: N/A

PART II

RADIOLOGICAL ENGINEERING

Radiological Survey for removable and total contamination on the exterior of the package:

- 1. Alpha
- 2. Beta/gamma

Radiological Survey for dose rate on the exterior of the package:

- 1. Gamma

SPECIFIC REQUIREMENTS AND/OR COMMENTS: The Radiological Control Technician (RCT) shall perform contamination surveys on the area where samples were taken. Surveys will be performed on shipping container (package) surfaces per 49 CFR protocols. Results of radiation level on contact shall be less than .5 millirem/hour (total). This evaluation does not constitute an unrestricted release of the specified bulk asbestos and air samples from the Department of Energy radiological controls, i.e. the specified building material samples are only being provided with authorization for transport in accordance with Department of Transportation 49 CFR requirements. The Sender/Custodian shall provide a copy of the completed contamination surveys for approval.

Date: 11/20/97 Ext: 8148 Pager: 3927

APPROVAL FOR TRANSFER/SHIPMENT

The property samples specified above may be transferred to the destination indicated in Part 1 of this Release Evaluation.

Date: 11/21/97 Ext: 8451 Page: 5888


RADIOLOGICAL DOSE SURVEY FORM

LOG NUMBER: PRE# 971119-T130B-002

	GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴		GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴
1	<0.5				N/A	39					N/A
2	<0.5				N/A	40					N/A
3					N/A	41					N/A
4					N/A	42					N/A
5					N/A	43					N/A
6					N/A	44					N/A
7					N/A	45					N/A
8					N/A	46					N/A
9					N/A	47					N/A
10					N/A	48					N/A
11					N/A	49					N/A
12					N/A	50					N/A
13					N/A	51					N/A
14					N/A	52					N/A
15					N/A	53					N/A
16					N/A	54					N/A
17					N/A	55					N/A
18					N/A	56					N/A
19					N/A	57					N/A
20					N/A	58					N/A
21					N/A	59					N/A
22					N/A	60					N/A
23					N/A	61					N/A
24					N/A	62					N/A
25					N/A	63					N/A
26					N/A	64					N/A
27					N/A	65					N/A
28					N/A	66					N/A
29					N/A	67					N/A
30					N/A	68					N/A
31					N/A	69					N/A
32					N/A	70					N/A
33					N/A	71					N/A
34					N/A	72					N/A
35					N/A	73					N/A
36					N/A	74					N/A
37					N/A	75					N/A
38					N/A	76					N/A

3 of 3

Room 115
22
23
21
19
20



BUILDING 886--FIRST FLOOR PLAN
SCALE: 1"=10'-0"

MASTER DRAWING
MAINTAIN AS-BUILT PER CODE 6.6.2
OF CODES AND STANDARDS FOR THE CITY OF NEW YORK

11/11/11

RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: Special - Pre-Job

P/WRE _____ ROUTINE _____

R.W.P. 88-97-5261 OTHER X

BUILDING/LOCATION ROOM#: 111

886

DATE: 11-19-97 TIME: 12:00

ITEM DESCRIPTION: Pre-Job

COMMENTS: Pre
See map on page 3

Mfg:		Removable Contamination Counters	
Model:	Serial #:	Eberline	Eberline
SAC-4	984	SAC-4	SAC-4
9-18-97	1158	BC-4	BC-4
3-18-98	9-17-97	BC 763	BC-4
	3-17-98	10-6-97	BC 869
		4-6-98	9-29-97
			3-29-98

Mfg:		Total (Fixed + Removable) Survey Instruments	
Model:	Serial #:	NE Electra	Bicron
DP6	1277	NE Electra	Bicron
5-28-97		DP6	A-100
11-28-97			
0.0 P 513			
0.22-87-6-22-97			

Mfg:		Total (Fixed + Removable) Survey Instruments	
Model:	Serial #:	NE Electra	Bicron
Ludlum	31	NE Electra	Bicron
31		DP6	A-100

STATUS: _____ RELEASABLE _____ NOT RELEASABLE


_____ POSTED _____ NOT POSTED

✓ _____ WITHIN LIMITS _____ LIMITS EXCEEDED

	886-971119-MS-001	CONDENSATE TANK	MUD + CANVAS
①			
②			
③			
④	886-971119-MS-004	Block WALL	Mortar, Skim
⑤	886-971119-MS-005	Chiller Return Elbow	MUD fitt
⑥	006	Chiller Return straight VALVE 1/2" x 1/2"	Block MUD 1/4" x 1/4"
⑦	007	Chiller Supply Elbow	MUD
⑧	886-971119-MS-008	Steam Supply straight	Block
⑨	009	steam supply Tee	MUD
⑩	010	STEAM SUPPLY straight	Block
⑪	886-971119-MS-011	STEAM SUPPLY STRAIGHT	Block



BUILDING 886 RLCP SAMPLING LOCATIONS
 Asbestos SAMPLING - Nov 19, 1997 Room 111
 NOT TO SCALE



RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: **PRE # 97119-T/30B-002**

P.W.R.E. ROUTINE _____
 R.W.P. OTHER _____

BUILDING/LOCATION: **ROOM#: 886**

DATE: **11-21-97** TIME: **9:30**

ITEM DESCRIPTION: **The bag with tubes of asbestos.**

COMMENTS: **outer bag is sealed with "custody seal". contents inside of bag not surveyed**

STATUS: RELEASABLE _____ NOT RELEASABLE
 POSTED _____ NOT POSTED
 WITHIN LIMITS _____ LIMITS EXCEEDED

Removable Contamination Counters	
Mfg:	Eberline
Model:	SAC-4
Serial #:	1158
Date Calib'd:	9-17-97
Cal. due Date:	3-17-98
Mfg:	Eberline
Model:	BC-4
Serial #:	BC 763
Date Calib'd:	10-6-97
Cal. due Date:	4-6-98

Total (Fixed + Removable) Survey Instruments			
Mfg:	NE Electra	NE Electra	Bicron
Model:	DP6	DP6	A-100
Serial #:	1277		
Date Calib'd:	5-28-97		
Cal Due Date:	11-28-97		
Background:	0.20 B526		
Efficiency:	0.22.870.528.57		

Mfg:	Ludlum	Ludlum	Eberline
Model:	31	31	RO 20
Serial #:			191
Date Calib'd:			7-16-97
Cal Due Date:			1-16-98
Background:			< 0.5
Efficiency:			N/A





Sampling Record

Project: 886 Cluster RCLP

Building: *Entire CLUSTER*

Room (if applicable): *N.A.*


Area is classified as (circle as appropriate): Affected

Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe

PCB media

Lead/Metals

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
<i>All Building 886 RCLP</i>	<i>samples collected between Nov 11, Dec 8, 1997 were collected using decontaminated sampling equipment in accordance with section 4.5 of the RCLP. This was verified to me (Hopi Solomon) by MATT DESSI and Mike Schluterbush of SFG</i>	<i>collected</i>
		

Signed
Evaluated/Sampled by:

Hopi Solomon
12/10/97

Date:

Reviewed by:

Date:

PCB samples collected Nov 11, 1997

Project: 886 Cluster RCLP

Building: 886

Room (if applicable): 111

Area is classified as (circle as appropriate): Affected

Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe

PCB media

Lead/Metals

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
886-971119-MD-001	Red Paint, 1.5 ft N of door 264; Some white undercoat and concrete	
886-971119-MD-002	Duplicate of -001	
886-971119-MD-003	Sprinkler system 6" Pipe, 6 ft South of door D-264 5 feet up from floor	
886-971119-MD-004	Gray Floor Paint 4' West of JB 886 Electrical Box	
886-971119-MD-005	Gasket material from vibration damper Sample in plastic bag, would not fit in jar	
		(initials) 12/4/97

Evaluated/Sampled by:

M. Dessi / P. Valentini

Date: 11/20/97

Reviewed by:

[Signature]

Date:

12/10/97

Note: Problems with the COC with respect to following proper APD protocol on bottle and event numbering are noted. This does not affect sample integrity.

[Signature] 12/10/97

[Signature]

SAMPLERS (Signature) M.H.D.

REPORT IDENTIFICATION NUMBER (RIN) 98A0450

LAB/LOCATION: Paragon Analytix

RFETS CONTRACTOR SEC

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER N/A

Preservation	Analysis
Coated to 4°C	
NaOH	
HNO3	
H2SO4	
H2O	

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX
11/20/97	1000	001	001	886-97119-MD001		Jar	Paint
11/20/97	1000	001	002	886-97119-MD002		Jar	Paint
11/20/97	1000	001	003	886-97119-MD003		Jar	Paint
11/20/97	1000	001	004	886-97119-MD004		Jar	Paint
11/20/97	1000	001	005	886-97119-MD005		Bag	Gasket

Relinquished By	Date	Time	Received By/Organization	Date	Time
<i>[Signature]</i>	11/21/97	1625	<i>[Signature]</i>	11/21/97	1625

REMARKS: Faxed results by C.A.B. 12/2 (Tues) Ok. per Pat Preece

Charge # Project Bldg 886-RLCR

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill

Aroclors
Method SW8081
Method Blank

Lab Name: Paragon Analytica, Inc.
 Work Order Number: 8711247
 Client Name: Kaiser-Hill Co., L.L.C.
 Client Project ID: 88A0460

Reported on: Tuesday, December 02, 1997

Field ID: LAB00
 Lab ID: PCB-OR01112497MB

Sample Matrix: Solid
 % Moisture: N/A
 Cleanup Method: SW8605
 Report Basis: NA

Date Collected: 24-Nov-97
 Date Extracted: 24-Nov-97
 Date Analyzed: 26-Nov-97
 Prep Batch: 148166

Sample Aliquot: 2
 Final Volume: 10
 Dilution: 1

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12874-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-18-6	AROCHLOR-1232	350	ug/kg	350	U	
83489-21-8	AROCHLOR-1242	350	ug/kg	350	U	
12878-20-8	AROCHLOR-1248	350	ug/kg	350	U	
11087-88-1	AROCHLOR-1254	350	ug/kg	350	U	
11096-82-9	AROCHLOR-1260	350	ug/kg	350	U	

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2061-24-3	DECACHLOROBIPHENYL	247	ug/kg	260	89	34 - 129
877-08-8	TETRACHLORO-M-XYLENE	245	ug/kg	260	98	47 - 137

U = Less than the Reporting Limit

Aroclors

Method SW8081

Lab Name: Paragon Analytics, Inc.
Work Order Number: 9711247
Client Name: Kaiser-Hill Co., L.L.C.
Client Project ID: 98A0450

Reported on: Tuesday, December 02, 1997

Field ID: 98A0450-001.001	Sample Matrix: Solid	Date Collected: 20-Nov-97	Sample Aliquot: 2
Lab ID: 9711247-1	% Moisture: N/A	Date Extracted: 24-Nov-97	Final Volume: 10
	Cleanup Method: SW8081	Date Analyzed: 26-Nov-97	Dilution: 1
	Report Basis: AS RECEIVED	Prep Batch: 148186	

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12574-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-16-5	AROCHLOR-1232	360	ug/kg	350	U	
53489-21-8	AROCHLOR-1242	350	ug/kg	350	U	
12672-29-6	AROCHLOR-1246	350	ug/kg	350	U	
11087-09-1	AROCHLOR-1254	350	ug/kg	350	U	
11099-82-0	AROCHLOR-1280	320	ug/kg	350	J	

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2051-24-3	DECAChLOROBIPhENYL	242	ug/kg	250	97	34 - 129
877-09-8	TETRAChLORO-M-XYLENE	234	ug/kg	250	93	47 - 137

J = Estimated Value

Aroclors

Method 9W8081

Lab Name: Paragon Analytics, Inc.
 Work Order Number: 0711247
 Client Name: Kaiser-Hill Co., L.L.C.
 Client/Project ID: 98A0480

Reported on: Tuesday, December 02, 1997

Field ID: 68A0480-001.D02	Sample Matrix: Solid	Date Collected: 20-Nov-97	Sample Aliquot: 2
Lab ID: 9711247-2	% Moisture: N/A	Date Extracted: 24-Nov-97	Final Volume: 10
	Cleanup Method: SW3065	Date Analyzed: 28-Nov-97	Dilution: 1
	Report Basis: AS RECEIVED	Prep Batch: 148185	

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12674-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-16-5	AROCHLOR-1232	350	ug/kg	350	U	
83489-21-9	AROCHLOR-1242	350	ug/kg	350	U	
12872-29-6	AROCHLOR-1246	350	ug/kg	350	U	
11097-69-1	AROCHLOR-1254	350	ug/kg	350	U	
11096-82-5	AROCHLOR-1250	350	ug/kg	350	U	

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2061-24-3	DECAChLOROBIPhENYL	234	ug/kg	250	83	34 - 129
877-09-8	TETRAChLORO-M-XYLENE	228	ug/kg	250	90	47 - 137

U = Less than the Reporting Limit

Aroclors

Method SW8081

Lab Name: Paragon Analytics, Inc.
 Work Order Number: 9711247
 Client Name: Kaiser-Hill Co., L.L.C.
 Client Project ID: 98A0450

Reported on: Tuesday, December 02, 1997

Field ID: 98A0450-001.003
 Lab ID: 9711247-3

Sample Matrix: Solid
 % Moisture: N/A
 Cleanup Method: SW3965
 Report Basis: AS RECEIVED

Date Collected: 20-Nov-97
 Date Extracted: 24-Nov-97
 Date Analyzed: 26-Nov-97
 Prep Batch: 146166

Sample Aliquot: 2
 Final Volume: 10
 Dilution: 1

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12674-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-16-5	AROCHLOR-1232	350	ug/kg	350	U	
63469-21-9	AROCHLOR-1242	350	ug/kg	350	U	
12672-29-6	AROCHLOR-1248	350	ug/kg	350	U	
11097-69-1	AROCHLOR-1254	350	ug/kg	350	U	
11096-82-6	AROCHLOR-1260	350	ug/kg	350	U	

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2081-24-3	DECACHLOROBIPHENYL	233	ug/kg	250	93	84 - 129
877-09-8	TETRACHLORO-MXYLENE	229	ug/kg	250	92	47 - 137

U = Less than the Reporting Limit

Aroclors

Method SW8081

Lab Name: Paragon Analytical, Inc.
 Work Order Number: 9711247
 Client Name: Kaiser-Hill Co., L.L.C.
 Client Project ID: 98A0480

Reported on: Tuesday, December 02, 1997

Field ID: 98A0480-001-004	Sample Matrix: Solid	Date Collected: 20-Nov-97	Sample Aliquot: 2
Lab ID: 9711247-4	% Moisture: N/A	Date Extracted: 24-Nov-97	Final Volume: 10
	Cleanup Method: SW3686	Date Analyzed: 26-Nov-97	Dilution: 1
	Report Basis: AS RECEIVED	Prep Batch: 146166	

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12974-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-18-5	AROCHLOR-1232	350	ug/kg	350	U	
63489-21-9	AROCHLOR-1242	350	ug/kg	350	U	
12872-29-6	AROCHLOR-1248	350	ug/kg	350	U	
11097-89-1	AROCHLOR-1254	350	ug/kg	350	U	
11096-82-5	AROCHLOR-1260	270	ug/kg	350	J	

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2051-24-3	DECACHLOROBIPHENYL	230	ug/kg	250	92	34 - 129
877-09-8	TETRACHLORO-M-XYLENE	227	ug/kg	250	91	47 - 137

J = Estimated Value

Aroclors

Method SW8081

Lab Name: Paragon Analytica, Inc.
 Work Order Number: 9711247
 Client Name: Kaiser-Hill Co., L.L.C.
 Client/Project ID: 98A0450


Reported on: Tuesday, December 02, 1997

Field ID: 98A0450-001.000	Sample Matrix: Solid	Date Collected: 20-Nov-97	Sample Aliquot: 2
Lab ID: 9711247-5	% Moisture: N/A	Date Extracted: 24-Nov-97	Final Volume: 10
	Cleanup Method: SW8081	Date Analyzed: 26-Nov-97	Dilution: 1
	Report Basis: As RECEIVED	Prep Batch: 146166	

CASNO	Target Analyte	Result	Units	Reporting Limit	Result Qualifier	Result Footnote
12674-11-2	AROCHLOR-1016	350	ug/kg	350	U	
11104-28-2	AROCHLOR-1221	350	ug/kg	350	U	
11141-18-5	AROCHLOR-1232	350	ug/kg	350	U	
53489-21-9	AROCHLOR-1242	350	ug/kg	350	U	
12672-29-8	AROCHLOR-1248	350	ug/kg	350	U	
11097-89-1	AROCHLOR-1254	350	ug/kg	350	U	
11096-82-5	AROCHLOR-1260	1000	ug/kg	350		

Surrogate Recovery

CASNO	Surrogate Analyte	Result	Units	Spike Amount	Percent Recovery	Control Limits
2091-24-3	DEDACHLOROBIPHENYL	206	ug/kg	250	82	34 - 129
677-09-8	TETRACHLORO-M-XYLENE	240	ug/kg	250	100	47 - 137




BUILDING 886 RLCP
Ali Saleh 12/4/07

Lead Paint Sample Locations - Building 888

12/8/97

Sample Location - Schematic



Illustrated by: M Schluterbusch
Date: 12/8/97
Reviewed by: *[Signature]*
Date: 12/9/97

RADIOLOGICAL CONTAMINATION &/or DOSE SURVEY FORM (A, B, λ, η)

SURVEY/LOG#	971119-7130B-001		
PWRE <input checked="" type="checkbox"/> ROUTINE	RAD. MFL TRANSFER		
R.W.P. OTHER <input type="checkbox"/>	UNRESTRICTED RELEASE		
BUILDING/LOCATION:	886	ROOM:	111
DATE:	11-20-97	TIME:	1500
ITEM / SURVEY DESCRIPTION:	UNRESTRICTED RELEASE OF OFFICE EQUIPMENT - 72		
	Survey of sealed blue top cooler of samples taken from building 886 Room 111.		
Total (Fixed + Removable) Survey Instruments			
Mfg:	NE Electra	Ludlum	
Model:	DP-6	31	
Serial #:	1243		
Date Calib'd:	9-15-97		
Cal Due Date:	3-15-98		
Background:	α 2.0cpm β 681cpm		
Efficiency:	α 22.8% β 31.8%		
Gamma / Neutron Survey Instruments			
Mfg:	Ludlum	Eberline	Victoreen
Model:	12-4	RO-20	450G
Serial #:			1602
Date Calib'd:			8-12-97
Cal Due Date:			2-12-98
Background:			< 0.5 mR/hr
Reviewed by (Rad. Cont. Supervisor)			
Performed by (R.C.T.)			

COMMENTS:

PRE# 971119-7130B-001
 Survey of outside of cooler only.

RADIOLOGICAL DOSE SURVEY FORM

LOG NUMBER PRE # 971119-T1308-001

	GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴		GAMMA X-RAY	NEUT.	TOTAL GAMMA NEUT.	AREA POSTED Y/N	BETA SHALLOW DOSE (OW-CW) ⁴
1	<0.5	NA	NA	N	N/A	39					N/A
2	<0.5	NA	NA	N	N/A	40					N/A
3	<0.5	NA	NA	N	N/A	41					N/A
4	<0.5	NA	NA	N	N/A	42					N/A
5	<0.5	NA	NA	N	N/A	43					N/A
6	<0.5	NA	NA	N	N/A	44					N/A
7					N/A	45					N/A
8					N/A	46					N/A
9					N/A	47					N/A
10					N/A	48					N/A
11					N/A	49					N/A
12					N/A	50					N/A
13					N/A	51					N/A
14					N/A	52					N/A
15					N/A	53					N/A
16					N/A	54					N/A
17					N/A	55					N/A
18					N/A	56					N/A
19					N/A	57					N/A
20					N/A	58					N/A
21					N/A	59					N/A
22					N/A	60					N/A
23					N/A	61					N/A
24					N/A	62					N/A
25					N/A	63					N/A
26					N/A	64					N/A
27					N/A	65					N/A
28					N/A	66					N/A
29					N/A	67					N/A
30					N/A	68					N/A
31					N/A	69					N/A
32					N/A	70					N/A
33					N/A	71					N/A
34					N/A	72					N/A
35					N/A	73					N/A
36					N/A	74					N/A
37					N/A	75					N/A
38					N/A	76					N/A

SAMPLERS (Signature) M Schluterbusch K. Kelly

REPORT IDENTIFICATION NUMBER (RIN) 98A0485 LAB/LOCATION: RECL PA

RFETS CONTRACTOR RMRS

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX
12-8-97	0928	002	003	KK 12-8-97	Building 886	30ml Plastic Paint Chips	Paint Chips
12-8-97	0945	005	003	KK 12-8-97	Building 886	30ml Plastic Paint Chips	Paint Chips

DATE	TIME	RECEIVED BY/ORGANIZATION
12/9/97	9 00	K. Kelly

Relinquished By: Kristi Kelly RTG 12-8-97

Received By/Organization: A. Mahu 12-9-97 0900

Charge # 886020SA

Project Bldg 886 RECL PA

PCPG REC'D/CUSTODY SEALS INTACT

SAMPLE LABELS/COCs AGREE



TEMPERATURE AT TIME OF RECEIPT ___ °C

REMARKS: Ultra Rush TAT

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Billing

SAMPLERS (Signature) M Schluterbusch K. Kelly
 REPORT IDENTIFICATION NUMBER (RIN) 98A0485
 LAB/LOCATION: RECR Linn (PA)

RFETS CONTRACTOR RMRS
ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX	Coated to 4" C	NaOH	HNO3	H2SO4	HCl	Preservation	Analysis
12/8/97	1453	D111	003	KK 12-7-97	Building 888	250 ml 6	Paint + Drywall							
														
														

Relinquished By: Kate Kelly Date: 12-9-97 Time: 1300 Received By/Organization: K. Mah Date: 12/9/97 Time: 1300

LABORATORY USE ONLY
 PKG REC'D/CUSTODY SEALS INTACT
 SAMPLE LABELS/COCs AGREE
 TEMPERATURE AT TIME OF RECEIPT ___ °C

REMARKS:

Charge # 8860205A
 Project 886 RCLP

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill No.

1 0 1

AMPLERS (Signature) MN Schlutschew K. Kelly (paperwork)

LAB/LOCATION: 559 Lab

REPORT IDENTIFICATION NUMBER (RIN) 98A0485

RFETS CONTRACTOR AMBS

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER

Preservation	Analytes
NaOH	
HNO3	
H2SO4	
HCl	
Cooled to 4°C	
SS05 Board	Total Metals Hg
SS03 B006	PCBs

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX
2-5-97	1345	001	002		Bldg 886	30ml Plastic	Paint Chips
KK 12-8-97							

Relinquished By:	Date	Time	Received By/Organization	Date	Time
<u>Kelly Kelly</u>	<u>12-8-97</u>	<u>0915</u>	<u>D. J. ... ASI</u>	<u>12-8-97</u>	<u>0915</u>

REMARKS: 12-8-97 12-8-97 12-8-97 12-8-97 12-8-97 12-8-97

Charge # 8860205A

Project Bldg 886 BCLP

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill No. Hand Deliver

SAMPLERS (Signature) M Schluterbusch K. Kelly of 1
 REPORT IDENTIFICATION NUMBER (RIN) 98A0485 LAB/LOCATION: Paragon (Para)

RFETS CONTRACTOR EMRS

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX	NaOH	HNO3	H2SO4	HCl	Coated to 4°C
12-2-97	1525	002	002		Bldg 886	30ml P	Paint Chips	X				
12-4-97	1405	004	002	AK 12-8-97		↓	Paint Chips	X				
12-4-97	1422	006	002			↓	Vibration Damper	X				
12-8-97	0955	009	002			250ml G	Hexane Swipes	X				

SSU3B006
PCBs

LABORATORY USE ONLY

Relinquished By: Keith Kelly RTG Date: 12-8-97 Time: 15:45 Received By/Organization: P. Valentini SEO Date: 12/8/97 Time: 1545

PCKG REC'D/CUSTODY SEALS INTACT

SAMPLE LABELS/COCs AGREE

TEMPERATURE AT TIME OF RECEIPT ___ °C

REMARKS: Ultra Rush TAT Charge # 886020SA Project Bldg 886 Bldg

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill Hand Deliver

APO COC 615197

FORM 1A-1

INORGANIC ANALYSIS DATA SHEET

Lab Name: Building 559 PA Inorganic Laboratories Sample No.: 1
 Lab Sample ID: 80A0485-001 Bldg 886 Paint Chips
 Section: ICPAES Lab Sample I.D.s beginning with X* indicates TCLP Extract
 % Solids for Sample: 100.0000
 Date Sampled: 12/5/97 SDG No.: DEC08
 Lab Receipt Date: 12/8/97 QC Report No.: SD120867.RPT
 Matrix: Water _____
 Soil _____
 Sludge _____
 Other X _____

Elements Identified and Measured

Concentration Units: mg/Kg

N V * E Q O S +

Analyte	Concentration	C	Q	M
Aluminum	12121.3283	B		P
Antimony	21.0838	B		P
Arsenic	9.0876	U		P
Barium	63.1011	B		P
Beryllium	0.4984	U		P
Cadmium	8.9278	B		P
Calcium	23900.3845	B		P
Chromium	2190.6717			P
Cobalt	282.1174	B		P
Copper	58.8983	B		P
Iron	8098.8288	B		P
Lead	3878.6318			P
Magnesium	542.8817	B		P
Manganese	195.7458	B		P
Molybdenum	33.7778	B		P
Nickel	1412.8845	B		P
Phosphorus	3541.8727	B		P
Selenium	11.9880	U		P
Silver	2.9863	U		P
Strontium	10.8663	B		P
Thallium	13.6829	B	N	P
Titanium	1307.1800	B		P
Vanadium	11.2459	B		P
Zinc	7874.8085	B		P

Color Before: Purple Clarify Before: Cloudy
 Color After: Yellow Clarify After: Clear

Texture:

Artifacts:

Comments: Sample = 100.00 % Solids. Total Metals Digestion only!

78
11
94
78
58
17
74
83
88
18
17
9
11

FORM 1A-1

INORGANIC ANALYSIS DATA SHEET

Lab Name: Building 690 PA Inorganic Laboratories

Sample No.: 2

Lab Sample ID: 88A0485-001 D

Bldg 886 Paint Chips Lab Duplicate

Section: ICPAES

Lab Sample I.D.s beginning with
X indicates TCLP Extract

% Solids for Sample: 100.0000

Date Sampled: 12/5/97

SDG No.: DEC08

Lab Receipt Date: 12/8/97

QC Report No.: SD120887.RPT

Matrix: Water _____
Soil _____
Sludge _____
Other X

Elements Identified and Measured

Concentration Units: mg/Kg

Analyte	Concentration	C	N	V	S	E	O	O	S	+	M
Aluminum	12134.4228	B									P
Antimony	9.9950	U									P
Arsenic	9.9950	U									P
Barium	56.8046	B									P
Beryllium	0.4998	U									P
Cadmium	10.0850	B									P
Calcium	22808.1859	B									P
Chromium	3775.7221	B									P
Cobalt	289.7981	B									P
Copper	68.2659	B									P
Iron	14918.1508	B									P
Lead	3744.8476	B									P
Magnesium	612.2439	B									P
Manganese	338.5122	B									P
Molybdenum	37.0312	B									P
Nickel	2178.4308	B									P
Phosphorus	3507.4883	B									P
Selenium	11.0940	U									P
Silver	2.0885	U									P
Strontium	10.0346	B									P
Thallium	12.6837	B	N								P
Titanium	1284.3978	B									P
Vanadium	6.6171	B									P
Zinc	7558.4308	B									P

Color Before: Purple

Clarity Before: Cloudy

Color After: Yellow

Clarity After: Clear

Texture:

Artifacts:

Comments: Sample = 100.00 % Solids. Total Metals Digestion only

28	
29	
30	
31	
32	
33	
34	
35	
36	
37	
38	
39	
40	
41	
42	
43	
44	
45	
46	
47	
48	
49	
50	
51	
52	
53	
54	
55	
56	
57	
58	
59	
60	
61	
62	
63	
64	
65	
66	
67	
68	
69	
70	
71	
72	
73	
74	
75	
76	
77	
78	
79	
80	
81	
82	
83	
84	
85	
86	
87	
88	
89	
90	
91	
92	
93	
94	
95	
96	
97	
98	
99	
100	

FORM 1A-1

INORGANIC ANALYSIS DATA SHEET

Lab Name: Building 559 PA Inorganic Laboratories Sample No.: 3
 Lab Sample ID: 98A0485-003 Bldg 886 Paint Chips
 Section: ICPAES
 Lab Sample I.D.s beginning with 'X' indicates TOLP Extract.
 % Solids for Sample : 100.0000
 Date Sampled: 12/8/97 SDG No.: DEC08
 Lab Receipt Date: 12/9/97 QC Report No.: 9D120897.RPT
 Matrix: Water _____
 Soil _____
 Sludge _____
 Other X _____

Elements Identified and Measured

Concentration Units: mg/Kg

Analyte	Concentration	C	Q	M
Aluminum	30672.4704	B		P
Antimony	18.1678	B		P
Arsenic	17.1886	B		P
Barium	162.8564	B		P
Beryllium	0.4904	U		P
Cadmium	25.5481			P
Calcium	17390.4919	B		P
Chromium	1862.2871	B		P
Cobalt	107.3059	B		P
Copper	100.6042	B		P
Iron	5910.3171	B		P
Lead	7975.4207	B		P
Magnesium	3809.1166	B		P
Manganese	78.2522	B		P
Molybdenum	4.0938	U		P
Nickel	46.7715	B		P
Phosphorus	6329.6180	B		P
Selenium	11.9860	U		P
Silver	2.0963	U		P
Strontium	14.9014	B		P
Tellurium	9.9875	U	N	P
Titanium	304.2797	B		P
Vanadium	11.5066	B		P
Zinc	14300.4594	B		P

Color Before: Green

Clarity Before: Cloudy

Color After: Yellow

Clarity After: Clear

Texture:

Artifacts:

Comments: Sample = 100.00 % Solids. Total Metals Digestion only!

FORM 1A-1

INORGANIC ANALYSIS DATA SHEET

Lab Name: Building 559 PA Inorganic Laboratories SAMPLE NO. 6
 Lab Sample ID: EPA QC-21 Standard
 Section: ICPAES Lab Sample I.D.s beginning with 'X' indicates TCLP Extract
 % Solids (b - N/A): 0.0000
 Date Sampled: 12/9/97 SDG No.: DEC08
 Lab Receipt Date: 12/9/97 QC Report No.: SD120897.RPT
 Matrix Water Soil Sludge Other

Elements Identified and Measured

Concentration Units: (mg/L)

Analyte	Concentration	C	Q	M
Aluminum				P
Antimony	4.0870	B		P
Arsenic	4.0727	B		P
Barium				P
Beryllium	3.9167	B		P
Cadmium	3.9003	B		P
Calcium	3.7696	B		P
Chromium	3.8702	B		P
Cobalt	4.0116	B		P
Copper	3.8713	B		P
Iron	3.7805	B		P
Lead	4.2041	B		P
Magnesium	4.0673	B		P
Manganese	3.7126	B		P
Molybdenum	3.8822	B		P
Nickel	3.7976	B		P
Phosphorus				P
Selenium	3.9423			P
Silver				P
Strontium				P
Thallium	3.9640	B		P
Titanium	3.7377	B		P
Vanadium	3.8877	B		P
Zinc	3.7507	B		P

Color Before:
 Color After:

Clarity Before:
 Clarity After:

IR: 0000

Texture:

Artifacts:

Comments:

Sample = 0.00 % Solids. Total Metals Digestion only
 EPA QC-21 Trace Metals Aqueous Reference Standard.
 (External Control Standard).

Grid area for additional data or notes.

FORM 1A-1

INORGANIC ANALYSIS DATA SHEET

Lab Name: Building 668 PA Inorganic Laboratories SAMPLE NO. 5
 Lab Sample ID: CRM020-050 Standard, (Metals on Soil)
 Section: ICPAES Lab Sample I.O.s beginning with X indicates TCLP Extract.
 % Solids (0 - N/A): 100.0000
 Date Sampled: 12/9/97 SDG No.: DEC08
 Lab Receipt Date: 12/9/97 QC Report No.: SD120897.RPT
 Matrix: Water Soil Sludge Other

Elements Identified and Measured

Concentration Units: (mg/Kg)

Analyte	Concentration	C	Q	M
Aluminum	1820.6776	B		P
Antimony	19.8302	U		P
Arsenic	408.6301			P
Barium	9.9651	U		P
Beryllium	0.9965	U		P
Cadmium	16.6211	B		P
Calcium	22914.6786	B		P
Chromium	11.0214	B		P
Cobalt	9.9651	U		P
Copper	718.9038	B		P
Iron	156229.3572	B		P
Lead	5395.8928	B		P
Magnesium	2686.6403	B		P
Manganese	885.7508	B		P
Molybdenum	9.9651	U		P
Nickel	20.4066	B		P
Phosphorus	1564.9477	B		P
Selenium	23.9163	U		P
Silver	82.4863	B		P
Strontium	30.4534	B		P
Thallium	53.9512	B		P
Titanium	38.6548	B		P
Vanadium	14.2501	B		P
Zinc	2683.7070	B		P

Color Before:
Color After:

Clarity Before:
Clarity After:

Texture:

Artifacts:

Comments:

Sample = 100.00 % Solids. Total Metals Digestion only!
 CRM020-050 QC Trace Metals Solid Reference Standard.
 (External Control Standard).

RADIOLOGICAL CONTAMINATION SURVEY FORM

LOG NUMBER: Special

PWRE ROUTINE

R.W.P. OTHER

BUILDING/LOCATION: 886 ROOM#: 111

DATE: 11-19-97 TIME: 1000

ITEM DESCRIPTION:
Pre job survey for PCB/Lead
sampling and Post job survey
of areas after sampling

Removable Contamination Counters			
Mfg:	Eberline	Eberline	Eberline
Model:	SAC-4	SAC-4	SAC-4
Serial #:	984	1158	
Date Calib'd:	9-18-97	9-17-97	
Cal. due Date:	3-18-98	3-18-98	

Mfg:	Eberline	Eberline	Eberline
Model:	BC-4	BC-4	BC-4
Serial #:	BC 763	BC 869	
Date Calib'd:	10-6-97	9-29-97	
Cal. due Date:	4-6-98	3-29-98	

Total (Fixed + Removable) Survey Instruments			
Mfg:	NE Electra	NE Electra	Bicron
Model:	DP6	DP6	A-100
Serial #:	1243		
Date Calib'd:	9-15-97		
Cal Due Date:	3-15-98		
Background:	0.20cpm / 633cpm		
Efficiency:	0.22.8% / 31.8%		

Mfg:	Ludlum	Ludlum
Model:	31	31
Serial #:		
Date Calib'd:		
Cal Due Date:		
Background:	N/A	N/A
Efficiency:		

STATUS: RELEASABLE NOT RELEASABLE

POSTED NOT POSTED

WITHIN LIMITS LIMITS EXCEEDED

PROPERTY/WASTE RELEASE EVALUATION

PRE Number: 971119-T130B-001

Charge Number: ME92AARC

EXTENDED: _____ EXPIRES: _____

ART I

SENDER/CUSTODIAN

Description of Property/Waste To Be Released/Transferred:

Five (5) paint chips and swipe samples for PCB analysis. See attached chain of custody for identification and attached contamination survey results.

Property's Current Location:

Building 886.

Property's Destination:

Paragon Analytic, 225 Commerce Drive, Fort Collins, CO 80524

Property's New Recipient/Custodian:

Paragon Analytic

Property History/Process Knowledge:

These five paint chip and swipe samples listed above were generated for PCB characterization on the 886 cluster.

Has the specified property/waste ever been in an RMMA or contacted DOE controlled radioactive materials?

Unknown.

ACKNOWLEDGEMENT:

By signing below, the sender/custodian verifies the information above to be true and correct.

- (1) Samples shall be shipped in accordance with 49 CFR (DOT) requirements.
- (2) The receiving laboratory holds the necessary NRC/State license for the radionuclides being shipped; said license shall be formally documented, retrievable and traceable to each sample shipped.
- (3) Paragon Analytic is licensed to handle nuclear material under Colorado Department of Public Health and Environment Nuclear Material License #847-02. Enclosed is a copy of attached letter for confirmation/renewal.

Date: 11/20/97 Ext: 6047 Pager: N/A

PART II

RADIOLOGICAL ENGINEERING

Radiological Survey for removable and total contamination on the exterior of the packages:

- 1. Alpha
- 2. Beta/gamma

Radiological Survey for dose rate on the exterior of the package:

- 1. Gamma

SPECIFIC REQUIREMENTS AND/OR COMMENTS: The Radiological Control Technician (RCT) shall perform contamination surveys on the area where samples were taken. Surveys will be performed on shipping container (package) surfaces per 49 CFR protocols. Results of radiation level on contact shall be less than .5 millirem/hour (total). This evaluation does not constitute an unrestricted release of the specified PCB samples from the Department of Energy radiological controls, i.e. the specified building material samples are only being provided with authorization for transport in accordance with Department of Transportation 49 CFR requirements. The Sender/Custodian shall provide a copy of the completed contamination

Date: 11/20/97 Ext: 8148 Pager: 3977

APPROVAL FOR TRANSFER/SHIPMENT

The property samples specified above may be transferred to the destination indicated in Part 1 of this Release Evaluation

Date: 11/21/97 Ext: 8451 Page: 5888



225 Commerce Drive Fort Collins, Colorado 80524 (800) 443-1511

Message

Phone (970) 490-1511

Fax (970) 490-1522

August 15, 1997

Mr. Pat Priest
Kaiser-Hill, LLC.
Rocky Flats Environmental Technology Site
Golden, CO

Dear Mr. Priest,

As you know our Colorado Radioactive Materials License # 847-02 reached the end of its 5 year term on June 30, 1997. As a normal course of business operations, Paragon submitted a radioactive materials license renewal package to the Colorado Department of Public Health and Environment Radiation Control Division on May 30, 1997. As per Colorado Rules and Regulations Pertaining to Radiation Control 3.17.2 "In any case in which a licensee, not less than 30 days prior to expiration of his existing license, has filed an application in proper form for renewal or for a new license authorizing the same activities, such existing license shall not expire until final action by the Department". Enclosed please find copy of a letter from the Colorado Department of Public Health and Environment Radiation Control Division stating that Paragon's Colorado Radioactive Material License #847-02 is under timely renewal and remains in full effect. This renewal process is a normal and customary for radioactive material licenses and in no way prohibits Paragon from performing any of its normal business activities.

Please forward a copy of the Colorado Department of Public Health and Environment Radiation Control Division's timely license renewal letter to your radioactive material license compliance officer for their files. If you have any questions regarding this letter, please call me at 970-490-1511. Additionally, this letter was delivered to Ms. Virgene Idecker on July 01, 1997

Sincerely yours,

Edward S. Wallace
Radiation Safety Officer

To	<u>Mr. Pat Priest</u>	Company	<u>Kaiser-Hill, LLC.</u>
Fax No.	<u>303-986-3400</u>	Date	<u>8-15-97</u>
From	<u>Edward S. Wallace</u>	Total Pages	<u>2</u>

If you do not receive all the pages, please call us back as soon as possible.

STATE OF COLORADO

Roy Romo, Governor
Patti Shwartzler, Executive Director

Dedicated to protecting and improving the health and environment of the people of Colorado

4300 Champlain Dr. S.
Denver, Colorado 80222-1530
Phone (303) 692-2100

Sanitary and Radiation Services Division
3100 Lowry Blvd.
Denver CO 80220-6100
(303) 432-0090



Colorado Department
of Public Health
and Environment

JUL 1 1997

Paragon Analytic, Inc
225 Commerce Drive
Fort Collins CO 80521

Attention: Edward S. [Name], Radiation Safety Officer

This letter is to inform you that your application to renew
Colorado 702 has been reviewed and approved timely. Your
radiation license will remain in effect until [Date]

radioactive materials license number
Therefore, all aspects of your current
action from this Department

If you have any questions, please contact the [Name] at (303) 432-0090

A. [Name]

James [Name] Section [Name]
Laboratory and Field Services

JJ

Page 1 of 4 Pages

STATE OF COLORADO
DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT

RADIOACTIVE MATERIALS LICENSE

Pursuant to the Radiation Control Act Title 25, Article 11, CRS 1989, Replacement Volume, as amended, and the Radiation Control Regulations, Part 3, and in reliance on statements and representations heretofore made by the licensee designated below; a license is hereby issued authorizing such licensee to transfer, receive, possess and use the radioactive material(s) designated below; and to use such radioactive material(s) for the purpose(s) and at the place(s) designated below. This license is subject to all applicable rules, regulations, and orders now or hereafter in effect of the Colorado Department of Public Health and Environment and to any conditions specified below.

Licensee		
1. Name: Paragon Analytics, Inc.	3. License Number Colo. 847-02	
2. Address: 225 Commerce Drive Fort Collins, CO 80524	4. Expiration date: June 30, 1997	
	5. Reference number:	
6. Radioactive materials (element and mass no.)	7. Chemical and/or physical form	8. Maximum quantity licensee may possess at any one time
A. Hydrogen 3	A. Any	A. 1000 millicuries
B. Any radionuclide with atomic numbers 3-82, except alpha emitting radionuclides	B. Any	B. 1 millicurie
C. Any alpha emitting radionuclides with atomic numbers 3-82	C. Any	C. 10 microcuries
D. Any radionuclide with atomic numbers 83-98, except as specifically authorized	D. Any	D. 750 microcuries
E. Natural or Depleted Uranium	E. Any	E. 500 millicuries
F. Natural Thorium	F. Any	F. 500 millicuries
G. Any radionuclide with atomic numbers 3-98	G. Sealed sources	G. 1 millicurie total. No single source to exceed 20 microcuries.
H. Cesium 137	H. Sealed source (Nos. 167760, 595255, 598860, or 501095)	H. 1 source not to exceed 40 microcuries

Continued from Page 1

Page 2 of 4 Pages

STATE OF COLORADO
DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENTRADIOACTIVE MATERIALS LICENSELicense Number Colo. 847-02
Expiration Date: June 30, 1997

CONDITIONS

- 9.A. Radioactive material authorized in Items 6.A. through 6.F. to be received as environmental, bioassay and industrial samples, to be stored and processed for qualitative and quantitative analysis in the laboratory. Radioactive materials authorized in Items 6.A. through 6.F. may also be received as chemical standards for the calibration of analytical equipment, and as a tracer in analytical procedures and quality control.
- B. Radioactive materials authorized in Item 6.G. to be used as standards for calibration of laboratory equipment.
- C. Radioactive material authorized in Item 6.H. to be used as a calibration source in a Beckman model LS 6000 Series Liquid Scintillation Counter.
10. Radioactive material may be used and stored only at 225 Commerce Drive, Fort Collins, Colorado 80524.
11. The licensee shall comply with the provisions of the State of Colorado *Rules and Regulations Pertaining to Radiation Control*, Part 10, "Notices, Instructions and Reports to Workers; Inspections" and Part 4, "Standards for Protection Against Radiation."
12. Radioactive material shall be used by, or under the supervision of Douglas J. Van Cleef; Lance R. Steere; Dorothy Stuit; Gus Harris III; or Edward S. Wallace.
13. The designated Radiation Safety Officer is Edward S. Wallace.
14. Radioactive material authorized by Item 6 of this license shall be stored and used in a manner that will preclude use by unauthorized personnel.
15. Each sealed source containing radioactive material authorized in Item 6 shall be tested for leakage and/or contamination in accordance with RH 4.16 of the State of Colorado *Rules and Regulations Pertaining to Radiation Control* at intervals not to exceed six months.
- 16.A. Individuals involved in operations which utilize, at any one time, more than 100 millicuries of Hydrogen 3 in a non-contained form, other than metallic foil, shall have bioassays performed within one week following a single operation and at weekly intervals for continuing operations. Records of the bioassays shall be maintained for inspection by the Department and the action points listed below shall be observed.
- B. (1) Tritium shall not be used in such a manner as to cause any individual to receive a radiation exposure such that urinary excretion rates exceed 28 microcuries of tritium per liter when averaged over a calendar quarter.

Continued from Page 2

Page 3 of 4 Pages

STATE OF COLORADO
DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENTRADIOACTIVE MATERIALS LICENSELicense Number Colo. 847-02
Expiration Date: June 30, 1997

- 16.8. (2) Urinalysis shall be performed at weekly intervals on all individuals who work in the restricted areas of facilities in which tritium is used. If the average concentration of tritium in urine for any single individual during a calendar quarter is less than 10 microcuries per liter, urinalysis may be performed on that individual at monthly intervals for the following calendar quarter and may continue at monthly intervals so long as the average concentration in the calendar quarter remains below 10 microcuries per liter. The urine specimen shall be collected on the same day of the week insofar as possible.
- (3) A report of an average concentration in excess of the limit specified in B. (1) above for any individual shall be filed, in writing, within thirty (30) days of the end of the calendar quarter with the Director, Radiation Control Division, Colorado Department of Public Health and Environment, 4300 Cherry Creek Drive South, Denver, Colorado 80222-1530. The report shall contain the results of all urinalyses for the individual during the calendar quarter, the cause of the excessive concentrations, and the corrective steps taken or planned to assure against a recurrence.
- (4) Any single urinalysis which discloses a concentration of greater than 50 microcuries per liter shall be reported, in writing, within seven (7) days of the licensee's receipt of the results, to the Director, Radiation Control Division, Colorado Department of Public Health and Environment, 4300 Cherry Creek Drive South, Denver, Colorado 80222-1530.
17. The licensee shall not transfer possession and/or control of materials or products containing radioactive material as a contaminant except:
- A. by transfer of waste to an authorized recipient;
 - B. by transfer to a specifically licensed recipient; or,
 - C. as provided otherwise by specific condition of this license pursuant to the requirements of RH 3.22 of the State of Colorado *Rules and Regulations Pertaining to Radiation Control*.
- 18.A. Wipe tests for contamination must be completed weekly when radioactive materials are used.
- B. The analysis of the wipes must be capable of detecting 200 DPM of the radioactive material on the test sample.
19. If an area survey or wipe test detects the presence of radioactive materials in excess of the limits specified below, then the area and/or affected equipment shall be decontaminated until:
- A. the removable contamination is not greater than 200 DPM per 100 square centimeters.
 - B. the average fixed contamination is not greater than 1,000 DPM per 100 square centimeters.
 - C. the maximum fixed contamination is not greater than 3,000 DPM per 100 square centimeters.

Continued from Page 3

Page 4 of 4 Pages

STATE OF COLORADO
DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENTRADIOACTIVE MATERIALS LICENSELicense Number Colo. 847-02
Expiration Date: June 30, 1997

20. The licensee shall maintain in effect the Payment Surety Bond number 8136-30-67 issued in the name of Analytical Technologies, Inc. by Federal Insurance Company, 1221 Avenue of the Americas, New York, NY 10020, effective date January 1, 1994, in the amount of \$750,000.00.
21. The State of Colorado *Rules and Regulations Pertaining to Radiation Control* shall govern the licensee's statements in applications or letters, unless the licensee's statements are more restrictive than the regulations. Except as specifically provided otherwise by this license, the licensee shall possess and use licensed material described in Items 6, 7, and 8 of this license in accordance with statements, representations, and procedures contained in:
- A. the application and attachments dated May 1, 1992; and
 - B. Floor plan sheet No. A-8.1 dated April 26, 1992; and
 - C. the correspondence dated May 27, 1992; December 14, 1992; June 16, 1993; September 7, 1993; January 5, 1994; March 14, 1994; November 6, 1995; and March 13, 1996.

FOR THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT

Date

April 3, 1996

By

W. [Signature]

OR-RH-18

Page 1 of 1 Page

STATE OF COLORADO
DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT

RADIOACTIVE MATERIALS LICENSE

License Number Colo. 847-01
Expiration Date: March 31, 1997
Amendment No. 5

Analytical Technologies, Inc.
225 Commerce Drive
Fort Collins, CO 80524

In accordance with the letter dated March 13, 1996, and concurrently with the issuance of Radioactive Materials License Number Colo. 847-02, Radioactive Materials License Number Colo. 847-01 is hereby TERMINATED.

FOR THE COLORADO DEPARTMENT OF PUBLIC HEALTH AND ENVIRONMENT

Date

April 8, 1996

By

[Signature]

OR-RH-18



Building 886 - CA Sampling (Rm 101, 102, 103)

Sampling Record

Project: 886 Cluster RCLP

Building: 886

Room (if applicable):

Area is classified as (circle as appropriate): Affected Unaffected

Analysis (circle as appropriate): Asbestos PCB Swipe PCB media

Lead/Metals

Rad Screen
e Thermo NuTech

Room
103
103
103+101
102
101
101
entry to 101
entry to 101

Sample Number	Detailed Sample Type and Description (i.e., type of material, equipment, equipment components, media)	Comments
98A0485-001.001	Paint Chips - light/dark purple on HEAVY lines	
98A0485-002.001	Paint Chips - light/dark yellow on skps ^{HS 12/3/97} (w/ brownish red primer coat)	
98A0485-003.001	Paint Chips - green on electrical boxes and piping (w/ brownish red primer coat)	
98A0485-004.001	Paint Chips - bright blue on shelving with light grey primer	
98A0485-005.001	Paint Chips - brown base paint on I beams	
98A0485-006.001	Cutout of Vibration damper	
98A0485-007.001	Paint Chips - white on mint green on grey	on wall
98A0485-008.001	Paint Chips - medium bluish, light bluish, dark bluish and orange	on floor
98A0485-003.004	Paint Chips - green on electrical boxes (w/ light green + white primer)	base primer ca 12-8-97
KK 12-9-97		

Note: These rad screen samples were not required by the RLCP but were required by RADIOLICAL Engineering to support development of a PRE for offsite shipment of the metals, PCB samples. The RIN-Event #'s correspond to the RIN-Event numbers from the PCB and metals (Total and TCLP).

Recorded
Evaluated/Sampled by: *[Signature]*
Date: 12/9/97

Reviewed by: *[Signature]*
Date: 12-9-97

Rad Screen 003.004 needed due to change in paint primer base coats
KK 12-4-97
KK 12-8-97

SAMPLERS (Signature) Matt D. R 24 Hour Rush!
Hopi Salomon (Signature)
 of 1

REPORT IDENTIFICATION NUMBER (RIN) 98A0485

LAB/LOCATION: Thermo NuTech

RFETS CONTRACTOR RMRS

~~488~~ 97120081

**ROCKY FLATS
 ENVIRONMENTAL TECHNOLOGY SITE
 CHAIN OF CUSTODY NUMBER**

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX
12/2/97	1540	001	001		Building 886	30 ml. Plastic	Paint Chips
12/2/97	1525	002	001				Paint Chips
12/3/97	1110	003	001				Paint Chips
12/3/97	1405	004	001				Paint Chips
12/3/97	1505	005	001				Paint Chips
12/3/97	1523	006	001				Vibrations Damper
12/3/97	0900	007	001				Paint Chips
12/2/97	1000	008	001		Building 886		Paint Chips

Preservation	Analysis
HI	
H2SO4	
HNO3	
NaOH	
Cooled to 4° C	

Relinquished By:	Date	Time	Received By/Organization	Date	Time	LABORATORY USE ONLY	Y/N
MATT DESS	12/3/97	3:42 pm	<u>[Signature]</u>	12/3/97	1542	PCKG REC'D/CUSTODY SEALS INTACT	Y
<u>Hopi Salomon</u>	12/3/97	1550	<u>[Signature]</u> TNU	12/3/97	1550	SAMPLE LABELS/COCs AGREE	Y
<u>[Signature]</u>	12/3/97	1555	<u>[Signature]</u> C3	12/3/97	1600	TEMPERATURE AT TIME OF RECEIPT ___ °C	NA
<u>[Signature]</u> C3	12/5/97	1310	<u>[Signature]</u>	12/5/97	1310		NA

REMARKS: X=24 hour rush, Fax results to ARD @ 830D
 Relinquished BY: [Signature] 12/5/97 1310 Received BY: [Signature]
 Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill No. 886
 Charge # Bld 886 Project ALCP
 HAND DELIVER

SAMPLERS (Signature) K. Kelly (RTG) of _____

REPORT IDENTIFICATION NUMBER (RIN) 9870485 LAB/LOCATION: Thermo Nu Tech

REFETS CONTRACTOR RMS

ROCKY FLATS ENVIRONMENTAL TECHNOLOGY SITE CHAIN OF CUSTODY NUMBER _____

DATE	TIME	EVENT	BOTTLE	USER ID	LOCATION	CONTAINER	MATRIX
12-8-97	0948	003	004		Building 886	30ml Plastic Paint Chip	
KK 12-8-97							
KK 12-8-97							

Preservation	Analysis
HI	
H2 SO4	
HNO3	
NaOH	
Cooled to 4 °C	

Relinquished By: Krist Kelly Date: 12-8-97 Time: 1115 Received By/Organization: Molly Burke TNU Date: 12-8-97 Time: 1115

PCKG REC'D/CUSTODY SEALS INTACT Y

SAMPLE LABELS/COCs AGREE Y

TEMPERATURE AT TIME OF RECEIPT NA °C

REMARKS: ASAP Fax results to K. Kelly 6783

Charge # 8860205A

Project Bldg 886 RLCB

Shipping Requirements: Overnight Delivery 2-Day Delivery Air Bill No. Hand deliver

**Thermo Nutech - Rocky Flats
Radscreen Results**

Manifestation: APOF 3408

POB: 96A0485
Radscreen
Analytic
Report Date: 12/05/97

Laboratory Sample ID	RHH	APG Sample ID		Matrix	Gross Alpha		Gross Beta		Total Activity pCi/g	DOT Class
		Sheet	Blade		pCi/g	2σ	pCi/g	2σ		
97120081-01	96A0485	001	001	Waste	252	19	-15	3	274.00	NONRAD
97120081-02	96A0485	002	001	Waste	54	8	-0.1	2.0	62.00	NONRAD
97120081-03	96A0485	003	001	Waste	5	2	3	2	12.00	NONRAD
97120081-04	96A0485	004	001	Waste	37	5	1	2	44.00	NONRAD
97120081-05	96A0485	005	001	Waste	12	2	0.8	1.0	15.80	NONRAD
97120081-06	96A0485	006	001	Waste	26	2	-1.8	0.5	28.50	NONRAD
97120081-07	96A0485	007	001	Waste	1	2	1	2	6.00	NONRAD
97120081-08	96A0485	008	001	Waste	8	2	3	1	14.00	NONRAD

DOT Classification
<2000 pCi/g total activity is NONRAD
>2000 pCi/g total activity is RAD

Total Activity
Calculated as the sum of the gross alpha and beta activities AND the measurement uncertainties for these two measurements.
If the measured activity is negative, 0 pCi/g (instead of the negative value) is used to calculate the total activity.

Analysis Methods
Sample Preparation Procedure: L-6285-A, "Sample Preparation for Radiological Screening of Soil Samples by Gas Proportional Counting".
Counting Procedure: L-6285-A, "Operation of Thermo LB-4100 Gas Proportional Counter".

K.M. Haggard
Technical Director Date 12/15/97

David J. Taylor
Quality Assurance Manager Date 12/05/97

Thermo Nutech - Rocky Flats
9623 - Rocky Flats
9624 - Rocky Flats
9625 - Rocky Flats
9626 - Rocky Flats
9627 - Rocky Flats

RF-0002 9160

Thermo NUtech - Rocky Flats Radscreen Results

RIN: 98A0465
 Analysis: Radscreen
 Report Date: 12/10/97

Distributor/Fax: APO 3400
 K. Kelly 8783

Laboratory Sample ID	APO Sample ID		Matrix	Gross Alpha		Gross Beta		Total Activity pCi/g	DOT Class
	REN	Bottle		pCi/g	2 σ	pCi/g	2 σ		
97120134-01	98A0465	003	Waste	10	2	1	1	14.00	NONRAD

DOT Classification <2000 pCi/g total activity is NONRAD
 >= 2000 pCi/g total activity is RAD

Total Activity

Calculated as the sum of the gross alpha and beta activities AND the measurement uncertainties for these two measurements. If the measured activity is negative, 0 pCi/g (instead of the negative value) is used to calculate the total activity.

Analysis Methods

Sample Preparation Procedure: L-6283-A, "Sample Preparation for Radiological Screening of Soil Samples by Gas Proportional Counting".
 Counting Procedure: L-6285-A, "Operation of Thermoac LB4100 Gas Proportional Counters".

K.M. Haggard Date 12/10/97
 Technical Review

Donald P. Taylor Date 12/10/97
 Quality Assurance Review



APPENDIX C

CERTIFIED ASBESTOS INSPECTOR'S REPORT



Asbestos Characterization Report

Building 886 Cluster

DRAFT

Rocky Mountain Remediation Services

Revision 0

December 1997

TABLE OF CONTENTS

1.0 INTRODUCTION	
2.0 ASBESTOS SURVEY.....	
2.1 INSPECTION PROCEDURES.....	
2.2 SUMMARY OF ACBM DISCOVERED DURING INSPECTION.....	
2.3 DESCRIPTION AND HAZARD ASSESSMENT OF ACM.....	
2.4 DESCRIPTION OF NON-ACM BASED ON SAMPLE RESULTS	

APPENDICES

Appendix A—Inspector Certifications	
Appendix B—Bulk Asbestos Sample Lab/Data Table	

ATTACHMENTS

Attachment 1—Bulk Asbestos Sample Drawing.....	
Attachment 2—Bulk Asbestos Sample Photographs	
Attachment 3—Laboratory Data	

1.0 INTRODUCTION

During the weeks of November 17-21, November 24-28, and December 1-5, 1997 The Building 886 cluster was inspected for the presence of asbestos containing building materials (ACBM). This includes buildings 888, 886, 886A, 875, 828 and 881. The purpose of this inspection was to prepare for the demolition of this structure.

The asbestos inspection was conducted according to the guidelines set forth by the Asbestos Hazard Emergency Response Act (AHERA) and complies with the United States Environmental Protection Agency (EPA), Occupational Safety and Health Administration (OSHA) and State of Colorado regulations covering asbestos inspections.

The enclosed report contains the estimated quantities, physical assessment, location and descriptions of all materials either assumed or identified through sampling and analysis to be asbestos containing.

2.0 ASBESTOS SURVEY

2.1 INSPECTION PROCEDURES

Bulk samples were acquired to determine the presence of asbestos in building materials. Suspect materials were chosen based on historical significance or on the judgement of the accredited inspector. Each sample was assigned an individual number made up of the building number, the date the sample was acquired, the initials of the sampling technician, and a three digit number in sequence. Quality Control samples are designated in the Bulk Sample Data Table as (QC).

A total of 78 samples were acquired from suspected materials. These materials included surfacing materials, thermal systems insulation, and miscellaneous materials. All samples were acquired in a random manner representative of the suspected material.

All bulk samples were analyzed by Reservoirs Environmental Services, Inc. (RESI) of Denver, Colorado. RESI is accredited through the National Institute of Standards and Technology (NIST) and participates in the NIST National Voluntary Laboratory Accreditation Program (NVLAP) as required by the EPA. Bulk samples were analyzed by Polarized Light Microscopy (PLM) in compliance with guidelines established by the EPA 40 CFR 763, Subpart F, Appendix A. Asbestos concentrations were visually estimated and reported in percent by layer of each sample.

2.2 SUMMARY OF ACBM DISCOVERED DURING INSPECTION

During the inspection process of this facility, historical records were accessed and evaluated, along with physical inspection of the cluster. The historical records included original specifications and blueprints, asbestos and lead in paint bulk samples, and interviews with facility occupants including the Facility Manager, Larry Fischer.

2.2.1 BUILDING 886

Building 886 is the main structure of the cluster. It has three construction dates, starting in 1964. The inspection process discovered asbestos containing Thermal Systems Insulation on piping and tanks associated with the domestic water, chiller system, steam system in the interior and exterior of the building, and on a small HVAC system located outside of 886 on the west side. This TSI is generally in good condition and appears to have regular maintenance.

Asbestos containing Surfacing Materials discovered during the inspection were limited to a light

skim coat on the interior cinderblock associated with the oldest section of the structure. This material is covered with a minimum of one coat of paint and is in good condition. Due to the thinness of the application and the relatively low percentage of asbestos (trace to 5%), Point Counting analysis was utilized to more accurately evaluate asbestos content with results indicating levels consistently above 1%. This material must remain as part of the asbestos waste stream even though a composite of this skim coat and the cinderblock would reduce the asbestos percentage to far less than 1%.

Miscellaneous asbestos containing materials discovered during inspection included nine inch and twelve inch floor tiles dispersed throughout the "cold side" of the facility, including under the sheet vinyl in the hallways.. The adhesive associated with the floor tile tested negative for asbestos except in room 110, the janitor's closet. The tiles are in generally good condition and appear to receive regular maintenance.

The predominate pattern of ceiling tiles (2' x 4' white with wide latitudinal grooves, pits and pin holes) tested positive for asbestos. Due to the modular nature of a suspended ceiling, the remaining patterns must be assumed to be contaminated with asbestos. The suspended ceiling system was in good condition at the time of inspection.

A filler between the HVAC ducts and wall penetrations is 98% asbestos. This filler was not observed in all locations, but is predominate throughout the facility. At the time of inspection, the filler was painted and in good condition where observable.

A previous inspector acquired a sample of the electrical wiring in room 114 which indicated asbestos in the insulation. Until the building circuits are de-energized and a comprehensive survey can be completed, it must be assumed that all original wiring insulation for the structure, and for the other original structures in the cluster, is asbestos containing.

Building 886 has a built up roof system that was specified as containing asbestos in the felt and tar. As such, the roof is assumed to be asbestos containing without the need of sampling. Tar impregnated roofing felts may be disposed of with normal demolition debris under most circumstances.

2.2.2 Building 828

Building 828 exterior walls are assumed to be asbestos containing based on historical data from other locations on the site and on the expert judgement of the Certified Asbestos Inspector. The piping associated with the underground storage tanks is uninsulated.

2.2.3 Building 886A

Building 886A is a modular trailer (S.N. 3404) constructed by Elder in 1984. Alan Koenig from G.E. Capital, the parent company of Elder, verified that this particular structure was not constructed with any materials that contained either lead or asbestos.

2.2.4 Building 888

Building 888 is a guard post constructed in the mid 1980's. As such, building materials have a low possibility of containing asbestos. Based on visual inspection, all materials were eliminated as suspect asbestos containing materials except the roofing and the drywall systems. Samples were acquired of the drywall system which indicate no detectable asbestos present. The built-up roofing can be assumed to be asbestos containing tar impregnated roofing felt, which can be disposed of with the regular construction debris in most cases.

2.2.5 Building 875

Building 875 is the Plenum Facility for building 886 and includes the service tunnel to 886. Since this structure is of the same construction date as building 886, suspect asbestos containing

materials are shared. As such, all pipe insulation must be considered to be asbestos containing unless it can be eliminated by physical touch as either a foam or fiberglass product. At the time of inspection, the pipe insulation was a mixture of asbestos containing, foam and fiberglass insulation. The asbestos insulation was predominately confined to the fittings, reductions, hangers, tees and elbows, while the straight runs were predominately foam and fiberglass.

The roof of building 875 is similar in construction as that of building 886. As such, the original specifications called for the use of tar and felt containing asbestos. Based on this information, the roofing materials are assumed to be asbestos containing. These materials may be treated as regular demolition debris in most cases.

2.2.6 Building 880

At the time of inspection, no suspect asbestos containing building materials were discovered in building 880.

2.2.7 Building 888A

Building 888A is the electrical substation for the facility. Due to the inherent safety concerns with sampling live electrical equipment, no samples were acquired. Suspect asbestos containing materials include wiring insulation, arc chutes, arc protection, insulators, and conduit trays. Once the substation is de-energized, samples can be safely acquired of these materials. In the interim, prudence would dictate assuming these materials do contain asbestos.

2.2 DESCRIPTION AND HAZARD ASSESSMENT OF ACM

2.2.1 Building 886

2.2.2.1 Thermal Systems Insulation

2.3 DESCRIPTION OF MATERIALS TESTING NEGATIVE FOR ASBESTOS

2.3.1 Drywall, Tape, and Joint Compound

The drywall, tape and joint compound in the office and restroom areas were sampled and analyzed for asbestos. All sample results indicate there is no detectable asbestos present in the materials.

2.3.2 Concrete

The concrete associated with room 101 was rumored to be asbestos containing. Although not normally a suspect material, three samples were acquired. Results indicate no asbestos above a trace in this material.



Appendix A
Inspector Certifications

Statement of Certification

The asbestos building inspection evaluation performed on **Building 886 Cluster** was performed in accordance with applicable regulations, and employed only EPA AHERA accredited personnel.

INSPECTOR:

[REDACTED]

EPA ACCREDITATION:

[REDACTED]

STATE OF COLORADO CERTIFICATION:

[REDACTED]

I hereby attest and certify that I performed the asbestos building inspection evaluation on **Building 886 Cluster** at Rocky Flats Environmental Technology Site.

Signature: *Michael J. [Signature]* Date: 12/15/97

Appendix B
Bulk Asbestos Sample Lab/Data Table

Bulk Sample Data Table

Sample Number	Sample Description and Location	Lab Result PLM (PC)
886-971119-MS-001	TSI mud (B) and canvass (A); from room 111 condensate tank 3' east of west wall, 2' south of west door, 2' from the floor.	A: ND B: 10%
886-971119-MS-002	TSI mud (B) and canvass (A); from room 111 condensate tank 2' east of west wall, 2' south of west door, 3' from the floor.	A: ND B: 8%
886-971119-MS-003	TSI mud (C,E) and canvass/foil (A,B,D); from room 111 condensate tank 2' east of west wall, 2' south of west door, 3' from the floor.	A: ND B: ND C: 85% D: ND E: 8%
886-971119-MS-004	Cinderblock mortar (B) and skim (A); from room 111 south wall 1' east of south door, 6' from the floor.	A: TR B: ND
886-971119-MS-005	TSI mud (B) and canvass (A); from room 111 chiller return pipe elbow 9' east of west wall 2.5' north of the south wall 6.5' from the floor.	A: ND B: 15%
886-971119-MS-006	TSI mud (B) and canvass (A); from room 111 chiller return pipe valve 15' east of west wall, 2.5' north of south wall, 6.5' from the floor.	A: ND B: 15%
886-971119-MS-007	TSI mud (B) and canvass (A); from room 111 chiller supply pipe elbow 2' west of east wall, 3.5' north of south wall, 3' from the floor.	A: ND B: 15%
886-971119-MS-008	TSI mud (B) and canvass (A); from room 111 steam supply pipe 13.5' east of west wall, 2' north of south wall, 4.5' from the floor.	A: ND B: 30%
886-971119-MS-009	TSI mud (B) and canvass (A); from room 111 steam supply pipe tee 13.5' east of west wall, 2' north of south wall, 4.5' from the floor.	A: ND B: 15%
886-971119-MS-010	TSI mud (B) and canvass (A); from room 111 steam supply pipe 14' east of west wall, 7' north of south wall, 6' from the floor.	A: ND B: 20%
886-971119-MS-011	TSI mud (B) and canvass (A); from room 111 steam supply pipe 3' east of west wall, 6' north of south wall, 5' from the floor.	A: ND B: 20%
886-971119-MS-012	Tan carpet mastic; from room 106, 6.5' east of west wall, 5.5' north of south wall.	A: ND
886-971119-MS-013	White duct/wall penetration filler; from room 106 south wall 2.5' east of west wall, 9' from the floor.	A: 98% B: ND C: ND
886-971119-MS-014	Black 4" cove base and black glue; from room 107 south wall, 5' west of east wall.	A: TR B: ND
886-971119-MS-015	White ceiling tile with longitudinal grooves, pits and pin holes; from room 107, 13' west of east wall, 6' north of south wall.	A: ND
886-971119-MS-016	Brown 9" floor tile (B) and black mastic (A); from room 107, 10' west of east wall, 6' north of south wall.	A: ND B: 5%

886-971119-MS-017	Painted (A) concrete (B,C); from room 107, south wall, 3' west of east wall, 5' from the floor.	A: ND B: ND C: ND
886-971119-MS-018	Cinderblock mortar (B) and skim (A); from room 115 west wall, 2.5' south of north wall, 5' from the floor.	A: 2% (1%) B: ND
886-971119-MS-019	Simulated mosaic sheet vinyl flooring; from room 115, 3' north of south wall, 5' west of east wall.	A: ND B: ND
886-971119-MS-020	Grey cove base (C) and tan resin (A,B); from room 115 east wall, 3' south of north wall.	A: ND B: ND C: ND
886-971119-MS-021	White ceiling tile with light latitudinal grooves and pin holes; from room 115, 4' south of north wall, 2' west of east wall.	A: 4% (2%)
886-971119-MS-022	White ceiling tile with light longitudinal grooves and hashes; from room 115, 5' north of south wall, 4.5' west of east wall.	A: ND B: ND
886-971119-MS-023 (QC)	White ceiling tile with light longitudinal grooves and hashes; from room 115, 5' north of south wall, 4.5' west of east wall.	A: ND B: ND
886-971119-MS-024	TSI mud (B) and canvass (A); from room 110 domestic hot water pipe elbow; NW corner 1.5' from the floor.	A: ND B: 21%
886-971119-MS-025	Tan/white flecks 9" floor tile (B) and black mastic (A); from room 110, 1' north of south wall, 3' east of west wall.	A: 5% B: 4%
886-971119-MS-026	Beige with brown streaks 9" floor tile (B) and black mastic (A); from room 113, 4.5' west of east wall, 0.5' north of south wall.	A: ND B: 4%
886-971119-MS-027	White/grey floor tile (B) and black mastic (A) under carpet; from room 116, 8' west of east wall, 4' north of south wall.	A: ND B: 3%
886-971119-MS-028	Painted wall plaster; from room 116 west wall, 2' north of south wall, 4.5' from the floor.	A: ND B: ND C: ND D: ND
886-971119-MS-029 (QC)	Painted wall plaster; from room 116 west wall, 2' north of south wall, 4.5' from the floor.	A: ND B: ND C: ND D: ND
886-971119-MS-030	Grey and tan checkerboard pattern 9" floor tile (C,D) with black/tan mastic (A,B); from room 119 0.5' west of east wall, 0.5' south of north wall.	A: ND B: ND C: 3% D: 5%
886-971121-MS-031	Cinderblock mortar (B) and skim (A); from room 119 west wall, 4.5' south of north wall, 5' from the floor.	A: ND B: ND
886-971121-MS-032	Painted (A) wall plaster (B,C) and foam (D); from room 119 north wall, 1.5' east of west wall, 4' from the floor.	A: ND B: ND C: ND D: ND

886-971121-MS-033	Red and tan checkerboard 9" floor tile (B) with black/tan mastic (A) under carpet; from room 123, 6.5' east of west wall, 0.5' north of south wall.	A: ND B: ND C: 4% D: 4%
886-971121-MS-034	White ceiling tile with wide, shallow latitudinal grooves and pin holes; from room 123, 6' west of east wall, 2' south of the north wall.	A: 8%
886-971121-MS-035	White ceiling tile with latitudinal moustache and pin holes; from room 123, 2' west of east wall, 2' south of north wall.	A: TR (ND)
886-971121-MS-036	White ceiling tile with latitudinal worm holes and dense pin holes; from room 129, 2' north of south wall, 4' west of east wall.	A: ND
886-971121-MS-037	Tan/brown floor tile (C) with black/tan mastic (A,B) under carpet; from room 129, 0.5' west of east wall, 0.5' north of south wall.	A: ND B: ND C: 8%
886-971121-MS-038	Tan/brown floor tile (C) with black/tan mastic (A,B) under carpet; from room 131, 0.5' west of east wall, 0.5' north of south wall.	A: ND B: ND C: 8%
886-971121-MS-039	Cinderblock mortar (B) and skim (A); from room 131 west wall, 3' north of south wall, 3' from the floor.	A: ND B: ND
886-971121-MS-040	Drywall (D) tape (C) and joint compound (A,B); from room 131 northeast corner, 3.5' from the floor.	A: ND B: ND C: ND D: ND
886-971121-MS-041	Drywall (C) tape (B) and joint compound (A); from main entry north wall, 3' east of the west wall, 3' from the floor.	A: ND B: ND C: ND
886-971121-MS-042	Drywall (D) tape (C) and joint compound (A,B); from main entry north wall, 1' east of west wall, 8' from the floor.	A: ND B: ND C: ND D: ND
886-971121-MS-043	Drywall (D) tape (C) and joint compound (A,B); from main entry north wall, 1' west of east wall, 8' from the floor.	A: ND B: ND C: ND D: ND
886-971121-MS-044	Drywall (D) tape (C) and joint compound (A,B); from room 130 east wall, 5' north of south wall, 5' from the floor.	A: ND B: ND C: ND D: ND
886-971121-MS-045	Brown floor tile (B) and black/tan mastic (A,B) under carpet; from room 130, 0.5' east of west wall, 0.5' south of north wall.	A: ND B: 9%
886-971121-MS-046	Drywall (D) tape (C) and joint compound (A,B); from room 128 southeast corner, 4' from the floor.	A: ND B: ND C: TR (0.5%) D: ND

886-971121-MS-047	Wall plaster; from room 125 east wall, 3' south of north wall, 5' from floor.	A: ND B: ND C: ND D: ND
886-971121-MS-048	Cinderblock mortar (C) and skim (A,B) ; from room 127, west wall, 5' north of south wall, 5' from floor.	A: 5% (2.25%) B: ND C: ND
886-971121-MS-049	Light brown 4" cove base; from room 118 north wall, 6.5' east of west wall.	A: TR B: ND
886-971121-MS-050	Wall plaster; from room 120 east wall, 4.5' south of north wall, 6' from the floor.	A: ND B: ND C: ND
886-971121-MS-051	Dark brown 4" cove base and tan glue; from room 117 south wall, 4.5' east of west wall.	A: TR B: ND
886-971121-MS-052	White ceiling tile with wide latitudinal grooves and pin holes; from room 114, 10' west of east wall, 6.5' north of south wall.	A: 10%
886-971121-MS-053	Cinderblock mortar (C) and skim (A,B); from room 114 south wall, 6' west of east wall, 6' from the floor.	A: 3% (1.75%) B: ND C: ND
886-971121-MS-054 (QC)	Cinderblock mortar (C) and skim (A,B); from room 114 south wall, 6' west of east wall, 6' from the floor.	A: 3% (1.75%) B: ND C: ND
886-971121-MS-055	Grey/black 9" floor tile (B) with black mastic (A); from room 114, 10' west of east wall, 9' north of south wall.	A: ND B: 3%
886-971121-MS-056	Wall plaster; from room 114 east wall, 8' south of north wall, 5' from the floor.	A: ND B: ND C: ND D: ND
886-971121-MS-057	Light brown and beige checkerboard floor tiles (C,D) with tan/black mastic (A,B); from room 117, 6' west of east wall, at south doorway.	A: ND B: ND C: 5% D: 5%
886-971121-MS-058	Grey and blue checkerboard floor tiles (B,C) and tan/black mastic (A); from room 112, 4' north of south wall, 1' west of east wall.	A: ND B: 5% C: 8%
886-971121-MS-059	Wall plaster; from room 112 east wall, 14' south of north wall, 5' from floor.	A: ND B: ND C: ND D: ND
886-971121-MS-060	Simulated mosaic sheet vinyl flooring (C,D) over white tile (B) and black mastic (A); from 126 hall, 0.5' east of west wall, between rooms 110 & 113.	A: ND B: 5% C: ND D: ND
886-971121-MS-061	Cinderblock mortar (B) and skim (A); from 126 hall, south wall, 3.5' east of 116 entry, 5' from the floor.	A: TR (TR) B: ND

886-971121-MS-062	Cinderblock mortar (C) and skim (A,B); from 126 hall east wall, 2' north of 127 entry, 5' from floor.	A: 4% (1.25%) B: ND C: ND
886-971121-MS-063	Cinderblock mortar (C) and skim (A,B); from 126 hall east wall, 1.5' south of 118 entry, 5' from floor.	A: ND B: 5% (3%) C: ND
886-971124-MS-064	TSI canvass (A,B,C) on duct for control room HVAC; west exterior, 20' south of room 140 south wall, 4.5' west of east wall, 10' from ground.	A: ND B: ND C: ND D: 20%
886-971124-MS-065	TSI canvass (A,B) and mud (B) on duct for control room HVAC; west exterior, 20' south of room 140 south wall, 4.5' west of east wall, 10' from ground.	A: ND B: ND C: 20%
886-971124-MS-066	TSI canvass (A,B) and mud/tar (C) on duct for control room HVAC; west exterior, 20' south of room 140 south wall, 4.5' west of east wall, 10' from ground.	A: ND B: ND C: 45%
886-971124-MS-067	Texture on concrete; from 886 exterior, 12.5' north of SW corner, 1.5' from ground.	A: ND B: ND
886-971124-MS-068	Texture on concrete; from 886 exterior, 7' east of SW corner, 3.5' from ground.	A: ND B: ND
886-971124-MS-069	Texture on concrete; from 886 exterior, 19' north of SE corner, 5' from ground.	A: ND B: ND
886-971124-MS-070	Texture on cinderblock; from 886 exterior, 18' north of room 140 wall, 5' from ground.	A: ND B: ND
886-971124-MS-071	Texture on cinderblock; from 886 exterior, 27' north of SW corner, 5' west of wall, 5' from ground.	A: ND B: ND
886-971124-MS-072	Texture on cinderblock; from 886 exterior, 1' north of 886 door 3, east wall, 4' from ground.	A: ND B: ND
886-971124-MS-073 (QC)	Texture on cinderblock; from 886 exterior, 1' north of 886 door 3, east wall, 4' from ground.	A: ND B: ND
886-971124-MS-074	Concrete core; from north wall of entry to room 101, 5' from floor.	A: TR B: ND
886-971124-MS-075	Concrete core; from floor in entry hall to 101 at first turn.	A: ND
886-971124-MS-076	Drywall (D) tape (A,B) and joint compound (C); from Building 888; at SW corner main area, 5' from floor.	A: ND B: ND C: ND D: ND
886-971124-MS-077	Drywall (D) tape (A,B) and joint compound (C); from Building 888; at North edge of devising wall main area, 5' from floor.	A: ND B: ND C: ND D: ND

886-971124-MS-078	Drywall (D) tape (A,B) and joint compound (C); from Building 888; at SW corner restroom, 5' from floor.	A: ND B: ND C: ND D: ND

Note: ND means Non 886-971124-MS-064 e Detected; TR means Trace.




Attachment 1
Bulk Asbestos Sample Drawing

Not to Scale

BUILDING 886 RCLP Asbestos Sampling Locations

= SAMPLE LOCATIONS THAT CORRESPOND TO THE LAST 3 DIGITS OF THE SAMPLE NUMBER.
(886-971121-MS---, 886-971124-MS---)

signed *[Signature]*
Hopi Salomon 11/25/97
M. Schuster
11/25/97



BUILDING 886 RCLP



3

D1

CONDENSATE TANK

CHILLER/STEAM LINGS
5 through 10

140

106

107

109

113

115

110

117

114

122

118

120

127

125

128

126




121

123

129

116


119



Building 886 Asbestos sampling Location


Not to scale

⊕ = sample locations that correspond with last three digits of the sample number
(886-971121-MS- - - -)



Building 886 RLCP

Signed *[Signature]* Hapi Solomon (paper work guy) 11/25/97
[Signature] M. Schlöterbusch CAI 11/25/97



Asbestos Sample Location
 in CA in Building 886
 (#) = sample locations that
 correspond to the last
 3 digits of the
 Sample #

(886-971124-#-#-#)

SAMPLED ON Dec 2, 1997
 Building 886 RLCP

3

Note: These core samples (asbestos)
 were collected at the same locations
 as TCLP metal core samples


Asbestos #	TCLP #
074	98A045-007=004
075	98A045-008.004

SAMPLED 12/2/97

Recorded by
[Signature] 12/3/97
 Reviewed by
[Signature] 10/31/97

Asbestos sample locations on outside of Bld. 886
 Sampled 11/25/97

⊕ = sample locations that correspond to the list
 three digits of the sample number
 (886-971124-MS-)



Samplers - *John Salomon* (paperwork) 11/29/97
 HSI - *AM Salomon* sample acquisition 11/26/97
 HSI - *B. Smith*
 Lead FL + E. Kelly 11-25-97

Building 886 RLCP

BUILDING 886-FIRST FLOOR PLAN
 SCALE: 1"=10'-0"

MASTER DRAWING
 MAINTAIN AS-BUILT PER CODEM 6.6.2



Attachment 2

Bulk Asbestos Sample Photographs



Attachment 3
Laboratory Data

RESERVOIRS ENVIRONMENTAL SERVICES, INC.
 NVLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47649-1
 Client: Kaiser-Jill Company, LLC
 Client Project: RIN 98D0452
 Date Samples Received: November 21, 1997
 Analysis Type: PLM Short Report, Bulk
 Turnaround: 2 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)										Non-Fibrous Components (%)		
				BY LAYER Mineral	Visual Estimate (%)	C G E L L S	S H Y A N T S	H A I R L L S	W O O L L	T A L C E	O A H E R	D T H E R						
886-971119-MS-011	EM 318284	A White fibrous woven material with white paint B Gray fibrous plaster	5 95 100	ND	ND	70	0	0	0	0	0	0	0	0	0	0	0	30
886-971119-MS-012	EM 318285	A Tan resin	1	98	0	0	0	0	0	0	0	0	0	0	0	0	0	2
886-971119-MS-013	EM 318286	A White fibrous material B White paint C White resinous material	4 95	ND	ND	0	0	0	0	0	0	0	0	0	0	0	0	100
886-971119-MS-014	EM 318287	A Brown resin B Black resinous material	10 90	TR	TR	0	0	0	0	0	0	0	0	0	0	0	0	100
886-971119-MS-015	EM 318288	A Gray fibrous perlitic material with white paint	100	ND	ND	25	36	0	0	0	0	0	0	0	0	0	40	
886-971119-MS-016	EM 318289	A Black tar B Tan/white tile	4 96	ND	5	0	0	0	0	0	0	0	0	0	0	0	0	100

ND = None Detected
 TR = Trace, < 1% Visual Estimate
 CELL = Cellulose
 ORG = Organic
 Trem-Act = Tremolite-Actinolite
 WOLL = Wollastonite
 BRUC = Brucite
 GYP = Gypsum
 SYNTH = Synthetic
 Data QA

RESERVOIRS ENVIRONMENTAL SERVICES, INC.

NVLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number:

RES 47646-1

Client:

Kaiser-Hill Company, LLC

RIN98D0452, ME94AA

Date Samples Received:

November 21, 1997

Analysis Type:

PLM Short Report, Bulk

Turnaround:

24 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)	Non-Fibrous Components (%)
				BY LAYER	Visual Estimate (%)		
886-971119-MS-024	EM 318249	A White fibrous woven material w/white paint	4	ND	ND	90	10
		B White fibrous plaster	96	Chrysotile	21	0	40
886-971119-MS-025	EM 318250	A Black tar	5	Chrysotile	5	0	95
		B Tan tile	95	Chrysotile	4	0	0

ND = None Detected CELL = Cellulose ORG = Organic WOLL = Wollastonite GYP = Gypsum
 TR = Trace, < 1% Visual Estimate Trem-Act = Tremolite-Actinolite BRUC = Brucite SYNTH = Synthetic

Date: 01/24/98

RESERVOIRS ENVIRONMENTAL SERVICES, INC.

NVLAP Accredited Laboratory #1898

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number: RES 47964-1
 Client: Kaiser-Hill Company, LLC
 Client Project: RIN 9800452
 Data Samples Received: December 08, 1997
 Analysis Type: PLM Short Report, Bulk
 Turnaround: 24 Hour

Note: The US EPA requires use of stratified analysis for NESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)		Non-Fibrous Components (%)		
				BY LAYER	Mineral Visual Estimate (%)	C G E L L L	S Y A N S S	H A I R S H	T O A L C R	
886-971124-MS-074	EM 320266	A Multicolored paint w/trace gray plaster	3	Chrysotile	TR	0	0	0	0	100
		B Gray granular plaster	97		ND	0	0	0	0	100
886-971124-MS-075	EM 320267	A Gray granular plaster w/gray paint	100		ND	0	0	0	0	100

ND = None Detected
 TR = Trace, < 1% Visual Estimate
 CELL = Cellulose
 WOLL = Wollastonite
 BRUC = Brucite
 GYP = Gypsum
 SYNTH = Synthetic
 Trem-Act = Tremolite-Actinolite
 Analyst: PDL
 Date: 0A

RESERVOIRS ENVIRONMENTAL SERVICES, INC.

NMLAP Accredited Laboratory #1896

TABLE I. PLM BULK ANALYSIS, PERCENTAGE COMPOSITION BY VOLUME

RES Job Number:

Client:

Client Project:

Date Samples Received:

Analysis Type:

Turnaround:

RES 48002-1
Kaiser-Hill Company, LLC
FF332500 / 98D0601,
December 09, 1997
PLM Short Report, Bulk
2 Hour

Note: The US EPA requires use of stratified analysis for MESHAP and AHERA compliance. Composite results only apply for specific exceptions.

Client Sample Number	Lab ID Number	Physical Description	Portion of Total Sample (%)	ASBESTOS CONTENT		Non-Asbestos Fibrous Components (%)										Non-Fibrous Components (%)								
				BY LAYER	Visual Estimate (%)	C	G	S	H	A	O	T	L	A	N		I	L	L	C	E	R		
886-971124-MS-076	EM 320435	A White paint	5	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	
		B Brown fibrous material	15	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2
		C White plaster (mud)	15	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100
		D White plaster (drywall)	65	ND	1	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	96
886-971124-MS-077	EM 320436	A White paint	5	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100
		B Brown fibrous material	10	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	
		C White plaster (mud)	20	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	
		D White plaster (drywall)	65	ND	1	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	96
886-971124-MS-078	EM 320437	A White paint	4	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100
		B Brown fibrous material	10	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	2	
		C White plaster (mud)	20	ND	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	100	
		D White plaster (drywall)	66	ND	1	3	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	96

ND = None Detected
TR = Trace, < 1% Visual Estimate

CELL = Cellulose
Trem-Act = Tremolite-Actinolite

ORG = Organic

WOLL = Wollastonite
BRUC = Brucite

GYP = Gypsum
SYNTH = Synthetic

Analyst: PRK

Site QA