

RECEIVED

CORRES CONTROL
INCOMING LTR NO

2003 NOV - 6 P 2:53

STATE OF COLORADO

01031 RFO3

DUE DATE
ACTION

Bill Owens, Governor
Douglas H. Benevento, Executive Director
CORRESPONDENCE CONTROL
Dedicated to protecting and improving the health and environment of the people of Colorado
4300 Cherry Creek Dr S
Denver, Colorado 80246-1530
Phone (303) 692-2000
TDD Line (303) 691-7700
Located in Glendale, Colorado
Laboratory and Radiation Services Division
8100 Lowry Blvd
Denver, Colorado 80230-6928
(303) 692-3090



Colorado Department
of Public Health
and Environment

DIST	LTR	ENC
BERARDINI, J. H.	X	
BOGNAR, E. S.	X	
BROOKS, L.	X	
BUTLER, I.	X	
CARPENTER, M.	X	
CROCKETT, G. A.	X	
DECK, C. A.	X	
DEGENHART, K. R.	X	
DIETER, T. J.	X	
DIETERLE, S. E.	X	
FERRERA, D. W.	X	
GIACOMINI, J. J.	X	
LINDSAY, D. C.	X	
LONG, J. W.	X	
LYLE, J. L.	X	
MARTINEZ, L. A.	X	
NAGEL, R. E.	X	
NESTA, S.	X	
NORTH, K.	X	
PARKER, A. M.	X	
RODGERS, A. D.	X	
SHELTON, D. C.	X	
SPEARS, M. S.	X	
TRICE, K. D.	X	
TUOR, N. R.	X	
WIEMELT, K.	X	
WILLIAMS, J. L.	X	
ZAHM, C.	X	

October 31, 2003

Mr Joe Legare
Acting Assistant Manager for Environment and Stewardship
U S Department of Energy, Rocky Flats Field Office
10808 Highway 93, Unit A
Golden, CO 80403-8200

RE. Closeout Reports for Buildings 112, 987, and 992

Dear Mr Legare

The Colorado Department of Public Health and Environment, Hazardous Materials and Waste Management Division has reviewed the Closeout Reports for Buildings 112, 987, and 992, dated April 22, 2003 We appreciate being provided these Closeout Reports for our information

As we have previously requested, Closeout Reports should identify all removal activity and include a map of the facility identifying the structures involved, those removed, and the location of remaining infrastructure and its condition. Infrastructure includes all remaining materials and their location, and includes slabs, piers, footings, water pipes, gas lines, electrical conduits, drain lines, PWLs, sewer lines, etc These maps are necessary for possible ER and/or future stewardship concerns

The information provided for B112 does not specifically address the presence of or ultimate disposition of the below grade utility tunnel. Based on the information provided, it is inferred that this tunnel was removed, but this needs to be confirmed. As indicated above, a map of this area should be provided to show the remaining infrastructure, including the remaining slab as discussed It is also assumed, since not discussed, that the sewer lines were properly flushed and have been removed to the main line as indicated in the Facility Disposition RSOP, which is supposed to be followed for all facilities As such, we would appreciate being provided a revised Closeout Report for B112 addressing these concerns

The information provided for B992 should have included a map of this area showing the location of the remaining slab, process waste lines, and other infrastructure This information also does not identify if the PWL and sewer line were flushed prior to plugging, or if the PWL was grouted or filled with epoxy prior to being "cut off" Since it is indicated that ER will perform additional remediation of this site, and this site is a part of the B991 Cluster, the final disposition of this building site needs to be included in the Closeout Report for B991/B991 Cluster

COE CONTROL	X
ADMN RECORD	X
PATS/130	

Reviewed for Addressee
Corres Control RFP

If you have any questions regarding this correspondence please contact me at (303) 692-3367 or David Kruchek at (303) 692-3328

11/6/03
Date By

Sincerely,
David M. Gundersen
Steven H Gundersen
RFCA Project Coordinator

Ref Ltr #

DOE ORDER #
5400.1

cc Steve Tower, DOE
Tim Rehder, EPA
Steve Nesta, KH
Administrative Records Building T130G

Karen Wiemelt, KH
Dave Shelton, KH
David Abelson, RFCLOG



DOCUMENT CLASSIFICATION
REVIEW WAIVER PER
CLASSIFICATION OFFICE

ADMIN RECORD

IA-A-001783