ROCKY FLATS PLANT

4-I50-ENV-OPS-FO.32

REVISION 0

TREATED EFFLUENT DISCHARGE OPERABLE UNIT 1, BUILDING 891

Associate General Manager,

EG&G Environmental Restoration Management

Quality/Assurance Program Manager,

EG&G Environmental Restoration Management

CONCURRENCE B

nvironmental Restoration Division

DOE, Rocky Flats Office

Jessie Roberson

Print Name

Environmental Protection Agency Approval Required: Z Yes

Responsible Organization: Environmental Restoration Management

CONCURRENCE BY THE FOLLOWING DISCIPLINES IS DOCUMENTED IN THE PROCEDURE HISTORY FILE:

Environmental Engineering and Technology Environmental Operations Management Geosciences Remediation Project Management Sample Management Industrial Hygiene Occupational Safety Radiological Engineering

DOCUMENT CLASSIFICATION REVIEW V/A/VER PER CLASSIFICATION OFFICE

USE CATEGORY 3

ORC review not required

Surface Water Division

Periodic review frequency: I year from the effective date

DOGUMENT CLASSIFICATION FOR LAW WAINER PER R.B. HOFFMAN, CLASSIFICATION OFFICE JUNE 11, 1991

LIST OF EFFECTIVE PAGES

Pages Effective Date Change Number

1-19 04 1/3/94 94-Dime-000180

TOTAL NUMBER OF PAGES: 19

TABLE OF CONTENTS

Section	1	<u>Page</u>
	TITLE PAGE	. 1
	LIST OF EFFECTIVE PAGES	. 2
	TABLE OF CONTENTS	. 3
1.	PURPOSE	. 5
2.	SCOPE	. 5
3.	OVERVIEW	. 5
4.	RESPONSIBILITIES	. 5
4.1	Operations Manager	. 5
4.2	Operator	. 6
4.3	Project Manager	. 6
4.4	Shift Foreman	. 6
5.	LIMITATIONS AND PRECAUTIONS	. 6
6.	PREREQUISITE ACTIONS	. 7
6.1	Planning and Coordination	. 7
7.	INSTRUCTIONS—ADMINISTRATIVE	. 8
8.	INSTRUCTIONS—TREATED EFFLUENT OPERATION	. 9
8.1	Valve Position Verification	. 9
8.2	Discharge from T-205	. 9
8.3	Discharge from T-206	. 10
8.4	Discharge from T-207	. 11
9.	RECORDS	. 12
10	REFERENCES	. 13

TABLE OF CONTENTS (continued)

Appendixes

Appendix 1,	OU 1 Building 891 ARARs	14
Appendix 2,	Treated Effluent Discharge Checklist, Operable Unit 1,	
	Building 891	16
Appendix 3,	Effluent Storage System Valve Position	18
Appendix 4,	Building 891 Tank Level/Volume Log	19

1. PURPOSE

This procedure describes the administrative and operations steps used at Rocky Flats Plant (RFP) for discharging treated effluent from the Building 891 Groundwater Treatment Facility for 881 Hillside, Operable Unit (OU) 1 to the South Interceptor Ditch.

2. SCOPE

This procedure applies to all discharges of treated effluent from the Building 891 Groundwater Treatment Facility to the South Interceptor Ditch used by Environmental Operations Management employees and subcontractors.

This procedure addresses the administrative controls of the treated effluent discharge from the Building 891 Groundwater Treatment Facility.

3. OVERVIEW

This procedure describes the steps for discharging treated effluent from the Building 891 Groundwater Treatment Facility. The facility consists of a groundwater recovery and storage system, an ultraviolet/hydrogen peroxide oxidation system, an ion exchange system with units for acid and caustic regeneration of resin, a spent regenerant neutralization system, and a treated effluent storage and discharge system.

This procedure was established to ensure that treated effluent from the Building 891 Groundwater Treatment Facility meets the applicable or relevant and appropriate requirements (ARARs) in the Interim Measures/Interim Remedial Action Plan and Decision Document, 881 Hillside Area, Operable Unit 1, for discharge to the South Interceptor Ditch. The OU 1 Building 891 ARARs, Appendix 1, are included.

4. RESPONSIBILITIES

4.1 Operations Manager

Verifies that the analytical results are in compliance with the OU 1 Building 891 ARARs in Appendix 1.

4.2 Operator

Verifies the valve positions.

Records the discharge information on the daily logs.

Verifies and logs all tank levels.

4.3 Project Manager

Verifies that the analytical results are in compliance with the OU 1 Building 891 ARARs in Appendix 1.

Notifies applicable agencies of the analytical results, and of the intent to discharge.

Instructs the Operator when to discharge an effluent tank.

Locks and unlocks the valves, verifies the valve positions, and records actions on the Treated Effluent Discharge Checklist Operable Unit 1, Building 891, Appendix 2.

4.4 Shift Foreman

Verifies the valve positions.

5. LIMITATIONS AND PRECAUTIONS

- The steps in this procedure shall be followed to ensure that the treated effluent from the Building 891 Groundwater Treatment Facility meets the requirements established for RFP by the U.S. Department of Energy (DOE), the U.S. Environmental Protection Agency (EPA), and the Colorado Department of Health (CDH).
- The effluent outfall shall be visually monitored to verify that the discharge flow does not result in soil erosion or overflow the bounds of the South Interceptor Ditch to minimize the potential for damage to vegetation or soil erosion.

6. PREREQUISITE ACTIONS

6.1 Planning and Coordination

Project Manager

- [1] Ensure that all personnel involved in the field implementation of this procedure are trained in the site-specific health and safety plan.
- [2] Arrange for the collection and analysis of samples of the discharge from the following treated effluent storage tanks:
 - T-205
 - T-206
 - T-207

Samples are collected and analyzed in accordance with the Sampling and Analysis Plan for Operation and Maintenance of the Interim Measures/Interim Remedial Action for the 881 Hillside Operable Unit No. 1 and 4-B35-ER-OPS-FO.13, Containerization, Preserving, Handling and Shipping of Samples.

- [3] Maintain control of the keys to the locks installed on the following effluent valves:
 - HVB-205
 - HVB-206
 - HVB-207

7. INSTRUCTIONS—ADMINISTRATIVE

The following analytical results will come from an RFP approved laboratory. **NOTE**

Project Manager

- Verify that the analytical results are in compliance with the OU 1 Building 891 [1] ARARs in Appendix 1.
- Record the tank number and the sample number(s) for each tank on the Treated [2] Effluent Discharge Checklist Operable Unit 1, Building 891.

Project Manager and Operations Manager

Sign and date the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

Project Manager

- Notify the following of the analytical results, and the intent to discharge treated effluent:
 - DOE
 - CDH
 - **EPA**
 - OU 1 Manager
 - Surface Water Division Manager
 - RFP Shift Supervisor
- WHEN the notifications have been sent, [5] THEN sign and date the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.
- [6] Authorize the discharge of the treated effluent tank.

8. INSTRUCTIONS—TREATED EFFLUENT OPERATION

8.1 <u>Valve Position Verification</u>

Project Manager, Shift Foreman, and Operator

[1] Verify that all system valves on the Effluent Storage System Valve Position, Appendix 3 are CLOSED before discharge of treated effluent from Building 891.

8.2 <u>Discharge from T-205</u>

Project Manager

[1] Unlock valve HVB-205.

Operator

[2] Open valve HVB-205 to approximately 25% of the fully OPEN position.

Project Manager, Shift Foreman, and Operator

[3] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

Operator

- [4] Record the following for each discharge on the Daily Log, and on the Building 891 Tank Level/Volume Log, Appendix 4:
 - Time
 - Date
 - Tank number
- [5] Verify and log all tank levels on the Daily Log, and on the Building 891 Tank Level/Volume Log at least once every 2 hr during the discharge of treated effluent.
- [6] WHEN the level readout for T-205 on the Allen Bradley screen indicates that the tank is empty

OR discharging is stopped for any reason, **THEN** close valve HVB-205.

[7] IF discharging is stopped, THEN log the basis for determination.

8.2 Discharge from T-205 (continued)

Project Manager

- [8] Lock valve HVB-205.
- [9] Notify the RFP Shift Supervisor and the Surface Water Division Manager of the termination of discharge and of the volume of water discharged.

Project Manager, Shift Foreman, and Operator

[10] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

8.3 <u>Discharge from T-206</u>

Project Manager

[1] Unlock valve HVB-206.

Operator

[2] Open valve HVB-206 to approximately 25% of the fully OPEN position.

Project Manager, Shift Foreman, and Operator

[3] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

Operator

- [4] Record the following for each discharge on the Daily Log, and on the Building 891 Tank Level/Volume Log:
 - Time
 - Date
 - Tank number
- [5] Verify and log all tank levels on the Daily Log, and on the Building 891 Tank Level/Volume Log at least once every 2 hr during the discharge of treated effluent.
- [6] WHEN the level readout for T-206 on the Allen Bradley screen indicates that the tank is empty.

OR discharging is stopped for any reason,

THEN close valve HVB-206.

8.3 Discharge from T-206 (continued)

Operator (continued)

[7] IF discharging is stopped,
THEN log the basis for determination.

Project Manager

- [8] Lock valve HVB-206.
- [9] Notify the RFP Shift Supervisor and the Surface Water Division Manager of the termination of discharge and of the volume of water discharged.

Project Manager, Shift Foreman, and Operator

[10] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

8.4 <u>Discharge from T-207</u>

Project Manager

[1] Unlock valve HVB-207.

Operator

- [2] Open isolation effluent valve HVD-207 on T-207.
- [3] Open valve HVB-207 to approximately 25% of the fully OPEN position.

Project Manager, Shift Foreman, and Operator

[4] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

Operator

- [5] Record the following for each discharge on the Daily Log, and on the Building 891 Tank Level/Volume Log:
 - Time
 - Date
 - Tank number

8.4 Discharge from T-207 (continued)

Operator (continued)

- [6] Verify and log all tank levels on the Daily Log, and on the Building 891 Tank
 Level/Volume Log at least once every 2 hr during the discharge of treated effluent.
- [7] WHEN the level readout for T-207 on Allen Bradley screen indicates that the tank is empty,

OR discharging is stopped for any reason, THEN close valve HVB-207.

[8] IF discharging is stopped,THEN log the basis for determination.

Project Manager

- [9] Lock valve HVB-207.
- [10] Notify the RFP Shift Supervisor and the Surface Water Division of the termination of discharge and of the volume of water discharged.

Project Manager, Shift Foreman, and Operator

[11] Record the time and date, and sign the Treated Effluent Discharge Checklist Operable Unit 1, Building 891.

Operator

[12] Close effluent isolation valve HVD-207 on T-207.

9. RECORDS

Management of all records is consistent with 1-77000-RM-001, Records Management Guidance for Records Sources.

The checklists and logs generated as a result of this procedure are considered quality records. These records are managed in accordance with 2-G18-ER-ADM-17.01, Quality Assurance Records Management.

9. RECORDS (continued)

These records are part of the Administrative Record (AR). These ARs are also managed in accordance with 3-21000-ADM-17.02, Administrative Records Screening and Processing in addition to 2-G18-ER-ADM-17.01.

There are no nonquality records generated by this procedure.

Project Manager

- [1] Submit the records listed below for management in accordance with 3-21000-ADM-17.02, and 2-G18-ER-ADM-17.01:
 - Treated Effluent Discharge Checklist Operable Unit 1, Building 891
 - Building 891 Tank Level/Volume Log
 - Daily Log

10. REFERENCES

Interim Measures/Interim Remedial Action Plan and Decision Document, 881 Hillside Area, Operable Unit 1, 1990

Sampling and Analysis Plan for Operation and Maintenance of the Interim Measures/Interim Remedial Action for the 881 Hillside Operable Unit No. 1, 1993

1-77000-RM-001, Records Management Guidance for Records Sources

2-G18-ER-ADM-17.01, Quality Assurance Records Management (until this procedure is issued, use 3-21000-ADM-17.01)

3-21000-ADM-17.02, Administrative Records Screening and Processing

4-B35-ER-OPS-FO.13, Containerization, Preserving, Handling and Shipping of Samples (until this procedure is issued, use 5-21000-OPS-FO.13)

APPENDIX 1 Page 1 of 2

OU 1 BUILDING 891 ARARS

ORGANICS	<u>UNITS</u>	TREATMENT REQUIREMENTS
Methylene Chloride	ug/l	5
Acetone	ug/l	50
Carbon Disulfide	ug/l	5
1,1 Dichloroethene	ug/l	7
1,1 Dichloroethane	ug/l	5
1,2 Dichloroethane	ug/l	5
1,1,1 Trichlorethane	ug/l	200
Carbon Tetrachloride	·ug/l	5
Trichloroethene	ug/l	5
1,1,2 Trichloroethane	ug/l	5
Tetrachloroethene	ug/l	5
Toluene	ug/l	2000
<u>METALS</u>	<u>UNITS</u>	TREATMENT REQUIREMENTS
Aluminum	mg/l	5
Antimony	mg/l	.06
Arsenic	mg/l	.05
Barium	mg/l	1.0
Beryllium	mg/l	0.1
Cadmium	mg/l	0.01
Cesium	mg/l	NS
Chromium	mg/l	0.05
Copper	mg/l	0.03
Iron	mg/l	0.3
. Lead	mg/l	0.05
Lithium	mg/l	2.5
Manganese	mg/l	0.05
Mercury	mg/l	0.002
Molybdenum	mg/l	0.1
Nickel	mg/l	0.2
Selenium	mg/l	0.01
Silver	mg/l	0.05
Strontium	mg/l	NS
Thallium	mg/l	0.01
Vanadium	mg/l	0.1
Zinc	mg/l	2.0

APPENDIX 1 Page 2 of 2

MAJOR IONS	<u>UNITS</u>	TREATMENT REQUIREMENTS
Calcium	mg/l	NS
Magnesium	mg/l	NS
Potassium	mg/l	NS
Sodium	mg/l	NS
Total Dissolved Solids	mg/l	400
Chloride	mg/l	250
Nitrite and Nitrate	mg/l	10
Sulfate	mg/l	250
Bicarbonate as (CaCO ₃)	mg/l	NS
		TREATMENT
RADIONUCLIDES	<u>UNITS</u>	<u>REQUIREMENTS</u>
Gross Alpha	pCi/l	15
Gross Beta	pCi/l	50
Uranium (Total)	pCi/l	40
Strontium (89, 90)	pCi/l	8
Plutonium (239, 240)	pCi/l	15
Americium (241)	pCi/l	4
Tritium	pCi/l	20,000

NS No standard.

APPENDIX 2 Page 1 of 2

TREATED EFFLUENT DISCHARGE CHECKLIST OPERABLE UNIT 1, BUILDING 891

	sures/Interim Remedial	91 nst ARARs	(see Appen	Form FOULA Rev I Small of 2 idix 1 of ion
Acceptable for discharge 'Signature				
Approved for discharge'Signature	Date _			
Notifications to DOE, EPA, CDH, the Surface	e Water Division Manage	_	Manager, a	and the
RFP Shift Supervisor completed	Signature D peravious Management per	Date		
Action UL	Responsible Individual	Time	Date	Initials
Valve Position Verification				
All effluent storage system valves (in Appendix 3 of 4-150-ENV-OPS-FO.32) are closed.				
	Operator			
	Shift Foreman			
	Project Manager			
Effluent Tank No. T-205 discharge				
Discharge made □ Yes □ No		· · · · · · · · · · · · · · · · · · ·		
HVB-205 is unlocked and opened.			Γ	
	Operator			
:	Shift Foreman			
	Project Manager			
HVB-205 is closed and locked.	0->			
	Operator Shift Foreman			
	Project Manager			

APPENDIX 2 Page 2 of 2

				······································
# ·	UENT DISCHARGE CHE LE UNIT 1, BUILDING 89		, ,, ,	Form FO.SZA Rav 1 Sheet 2 of 2
EG&G review of analytical results for tre 4-I50-ENV-OPS-FO.32) in the Interim Mo Document, 881 Hillside Area, Operable U	asures/Interim Remedial			
Tank Number:	Sample Number(s):			
Action	Responsible Individual	Time	Date	Initials
Effluent Tank No. T-206 discharge				
Discharge made □ Yes □ No	- 7 12			
HVB-206 is unlocked and opened	47701115			
@11/1	O eraibr	J		
المارح	Shift Foreman			
	Project Manager		_	
HVB-206 is closed and locked.				
	Operator			·
	Shift Foreman			
	Project Manager			
Effluent Tank No. T-207 discharge				
Discharge made □ Yes □ No				
HVB-207 is unlocked and opened.				
	Operator			
	Shift Foreman	ĺ		
	Project Manager			
HVB-207 is closed and locked.				
	Operator			
	Shift Foreman			
	Project Manager			
HVD-207 is closed.			··_	
	Operator			
	Shift Foreman			
	Project Manager			
Comments:				

APPENDIX 3 Page 1 of 1

EFFLUENT STORAGE SYSTEM VALVE POSITION

Function	HVB 205	HVB 206	HVB 207	HVC 205	HVC 206	HVC 207	HVD 207
DISCHARGE	,						
T-205	0	С	С	С	С	С	С
T-206	С	0	С	С	С	С	С
T-207	С	С	0	С	С	С	0

APPENDIX 4 Page 1 of 1

BUILDING 891 TANK LEVEL/VOLUME LOG

Form FO.32B Rev. 0

BUILDING 891 TANK LEVEL/VOLUME LOG

DATE:	START LEVEL	ENDING LEVEL	COMMENTS
T-201 INPLUENT STORAGE			
T-202 INFLUENT STORAGE			
T-203 INFLUENT STORAGE			3/6)
T-204 INFLUENT			
T-205 EFFLUENT STORAGE (1 Ff = 10,000 GAL)			
T-206 EFFLUENT STORAGE (1 FF = 10,000 GAL)			
T-207 EFFLUENT STORAGE (1 FF = 10,000 GAL)			5
T-210 NEUTRALIZATION			
FRENCH DRAIN			

COMMENTS GALLONS PROCESSED ION EXCITANGE UV/PEROXIDE SYSTEM