ROCKY FLATS PLANT EMD OPERATING PROCEDURES MANUAL VOLUME III: GEOTECHNICAL

Manual No.: Procedure No.: Page:

5-21000-OPS-GT Table of Contents, Rev 48

1 of 3

Effective Date:

10/06/93

Organization:

Environmental Management

THIS IS ONE VOLUME OF A SIX VOLUME SET WHICH INCLUDES:

VOLUME I: FIELD OPERATIONS (FO) VOLUME II: GROUNDWATER (GW) VOLUME III: GEOTECHNICAL (GT) VOLUME IV: SURFACE WATER (SW) SUPERSEDED VOLUME V: ECOLOGY (EE) **VOLUME VI: AIR (AP)**

EG&G DOCUMENT

TABLE OF CONTENTS FOR VOLUME III: GEOTECHNICAL

| Procedure No. | Title | Rev. <u>No.</u> | Effective <u>Date</u> |
|------------------|---|--------------------|--------------------------|
| GT.01 | Logging Alluvial and Bedrock Material | 2 | 05/12/92 |
| DCN 92.01 | Specialized Logging Form | 2 | 11/13/92 |
| DCN 93.01 | Logging | 2 | 01/15/93 |
| DCN 93.02 | Logging Deliverables Standard Practices | 2 | 01/25/93 |
| DCN 93.03 | Core Log QC Change | 2 | 06/18/93 |
| DCN 93.04 | Lithologic Descriptions | 2 | 07/15/93 |
| DCN 93.05 | Logging with Well Points | 2 | 07/28/93 |
| DCN 93.06 | SVE Core Description | 2 | 08/20/93 |
| GT.02 • | Drilling and Sampling Using Hollow Stem | | |
| | Auger Techniques | 2 | 05/12/92 |
| DCN 92.01 | Superseded by DCN 92.03 07/27/92 | 2 | EXPIRED |
| DCN 92.02 | Superseded by DCN 92.03 07/27/92 | 2 | EXPIRED |
| DCN92.03 | EXPIRED | 2 | EXPIRED |
| DCN 92.04 | Prevention of Down Hole Contamination | 2 | 7/28/93 |
| • | EXTENDED | | |
| DCN 92.05 | Field Modification | 2 | 12/04/92 |
| DCN 93.01 | Analytical Samples | 2 | 01/25/93 |
| DCN 93.02 | Drum Characterization | 2 | 03/17/93 |
| DCN 93.03 | New Soil Samplling Method | 2 | 05/27/93 |
| DCN 93.04 | SVE VOC Sampling | 2 | 08/20/93 |

DOCUMENT CLASSIFICATION REVIEW WAIVER PER R.B. HOFFMAN, CLASSIFICATION OFFICE JUNE 11, 1991

ROCKY FLATS PLANT EMD OPERATING PROCEDURES MANUAL VOLUME III: GEOTECHNICAL

Manual No.: Procedure No.: Page:

5-21000-OPS-GT Table of Contents, Rev 48

2 of 3

Effective Date: 10/06/93

Organization: **Environmental Management**

| Bussaldina | | Day | Esta attua | |
|------------|--|-------------|------------|--|
| Procedure | Tiala | Rev. No. | Effective | |
| No. | Title | NO. | Date | |
| GT.03 | Isolating Bedrock from Alluvium with | | | |
| | Grouted Surface Casing | 2 | 05/12/92 | |
| DCN 92.03 | EXPIRED | 2 | EXPIRED | |
| DCN 93.01 | Data Quality Objectives for PLF Investigations | 2 | 02/10/93 | |
| DCN 93.02 | PVC/UHSU/Grout Changes | 2 | 05/10/93 | |
| DCN 93.03 | Isolating Potentially Contaminated Groundwater | 2 | 05/11/93 | |
| DCN 93.04 | SVE Omit Centralizers | 2 | 08/20/93 | |
| GT.04 | Rotary Drilling and Rock Coring | 2 | 05/12/92 | |
| GT.05 | Plugging and Abandonment of Boreholes | 2 | 05/12/92 | |
| DCN 92.01 | Field Modification | 2 | 12/09/92 | |
| DCN 93.01 | 5.2 Revision | 2 | 02/04/93 | |
| GT.06 | Monitoring Wells and Piezometer Installation | 2 | 05/12/92 | |
| DCN 92.05 | EXPIRED | 2 | EXPIRED | |
| DCN 92.06 | EXPIRED (replaced with DCN 93.01) | 2 | EXPIRED | |
| DCN 92.07 | Provide Consistency | 2 | 12/17/92 | |
| DCN 93.01 | Borehole Advancement | 2 | 01/04/93 | |
| DCN 93.02 | Well Point Installation | 2 | 01/28/93 | |
| DCN 93.03 | Piezometer Logging Modification | 2 | 02/04/93 | |
| DCN 93.04 | Wells - 5.3.2.2 Revised | 2 | 02/10/93 | |
| DCN 93.05 | Temperatures - 5.3.2.3 Revised | 2 | 02/10/93 | |
| DCN 93.06 | Provide Numbers to Reference Corresponding Items | 2 | 02/23/93 | |
| DCN 93.07 | DCN 93.01 Modification | 2 | 03/17/93 | |
| DCN 93.08 | PVC Schedule Change | 2 | 05/10/93 | |
| DCN 93.09 | Change to PVC Casing Thickness | 2 | 05/11/93 | |
| DCN 93.10 | SVE Bentonite Chips | 2 | 08/20/93 | |
| DCN 93.11 | SVE Well Specifications | 2 | 08/20/93 | |
| DCN 93.12 | Riser Installation | 2 | 09/02/93 | |
| *DCN 93.13 | Cancel DCN 93.11, Item #I for OU 2 SVE Study | 2 | 10/06/93 | |
| *DCN 93.14 | Revision of Figure GT.6-3 | 2 | 10/06/93 | |
| GT.07 | Logging and Sampling of Test Pits and | | | |
| | Trenches | 2 | 05/12/92 | |

ROCKY FLATS PLANT
EMD OPERATING
PROCEDURES MANUAL
VOLUME III: GEOTECHNICAL

Manual No.: Procedure No.: Page: 5-21000-OPS-GT Table of Contents, Rev 48

Effective Date:

3 of 3 10/06/93

Organization:

Environmental Management

| Procedure No. | <u>Title</u> | Rev. No. | Effective Date | | | |
|------------------|--|-------------|-------------------|--|--|--|
| | | | | | | |
| GT.08 | Surface Soil Sampling | 2 | 05/12/92 | | | |
| DCN 92.01 | EXPIRED | 2 | EXPIRED | | | |
| DCN 92.02 | Consistency Change | 2 | 10/12/92 | | | |
| DCN 93.01 | Work Plan Consistency | 2 | 01/05/93 | | | |
| DCN 93.02 | New Section-Surficial Profiling | 2 | 01/15/93 | | | |
| DCN 93.03 | CDH Compliance | 2 | 01/25/93 | | | |
| DCN 93.04 | Site Identification | 2 | 04/13/93 | | | |
| DCN 93.05 | Sample Volumes | 2 | 04/13/93 | | | |
| *DCN 93.06 | Data Form Replacement | 2 | 10/06/93 | | | |
| GT.09 | Soil Gas Sampling and Field Analysis | 2 | 05/12/92 | | | |
| GT.10 | Borehole Clearing | 2 | 05/12/92 | | | |
| GT.11 | Plugging and Abandonment of Wells | 2 | 05/12/92 | | | |
| GT.15 | Geophysical Borehole Logging | 2 | 05/12/92 | | | |
| GT.17 | Land Surveying | 2 | 05/12/92 | | | |
| *DCN 93.01 | Land Surveying Clarification | 2 | 09/02/93 | | | |
| GT.18 | Surface Geophysical Surveys | 2 | 05/12/92 | | | |
| DCN 92.01 | Surface Magnetic Surveys Procedure | 2 | 09/30/92 | | | |
| DCN 92.02 | Modification to Stacking Requirements | 2 | 10/15/92 | | | |
| DCN 92.03 | Modification to Method of Taking Readings | 2 | 10/15/92 | | | |
| DCN 93.01 | 5.4 Field Procedure Revisions | 2 | 01/25/93 | | | |
| GT.19 | Field Gas Chromatographs | 2 | 05/12/92 | | | |
| GT.20 | Procedures for Soil Interstitial Water | | | | | |
| | Sampling and Sampler Installation | 2 | 05/12/92 | | | |
| GT.21 | Cone Penetrometer Testing | 1 | 05/12/92 | | | |
| DCN 93.01 | CPT Rods | 1 | 01/15/93 | | | |
| DCN 93.02 | Offsets | 1 | 03/17/93 | | | |
| GT.24 | Approval Process for Construction Activities | | | | | |
| | on or Near Individual Hazardous Substance | • | AB114.00 | | | |
| | Sites (IHSSs) | 0 | 05/12/92 | | | |

ENVIRONMENTAL MANAGEMENT DOCUMENT CHANGE NOTICE (DCN)

Procedure Number 5-21000-OPS-GT.17 Rev 2

Page 1 of 1

| Title Land Surveying | | | | | | Date 9-02-93 | 1 . | Number | clr |
|--|-----------------|----------------------|---|----------------------------------|--|--|-----------|--------|-----|
| Expires 9-02-94 Procedure Revision Required | | | | | | | | | |
| Scope Lim | - itation: N | NONE | | | | | | | _ |
| | | | | | | | | | |
| Item Number | Page | Step or Paragraph | Changes (Use DCN CONTINUATION SHEET for additional space) | | | | | | |
| 1 | 5 OF 6 | 5.2 | (ground level |) to the nor | ments will be made: the th side of the well casing tion of the top of the pr | g, the elevation of th | | | |
| | | | | | DOCUMENT CLAS | EGGG IPERSED SIFICATION REVIEW AN, CLASSIFICATION INE 11, 1991 | V WAIVER | } | |
| Justification (Reason for change - Provide numbers to reference corresponding items above.) 1 - The base of the concrete apron (pad) also is ground level. All well construction measurements and recorded sample/core depths are referenced to ground level. The top of the concrete pad is not a reference datum. | | | | | | | | | |
| Concur | rence | Organizatio | on Req. | Date | Concurrence | Organization | Req. | Date | |
| State | | QAPM _A | K.a. X | 8.31.23 | Imot shousety | User | X | 8/31/0 | 13 |
| // | | | | | 8 mil | User | × | 8/31/9 | 3 |
| | | | | | | | | | |
| Approval of Responsible Manager | | Date/3 | /93 | Is Posting required? ☐ Yes ☐ No | If Yes, by what da | ite? | Date post | ted | |

5.4.2.2 Field Procedures

A standard field procedure is described below. Prior to magnetic data collection, five preliminary procedures must be conducted. These are:

- * Design the appropriate field survey parameters given the purpose of coverage, contained areas of magnetic interference, grid-traverse spacing, direction of traverse, magnetometer reading interval.
- * The surface geophysical survey grid-traverse lines will controlled from the surveyed baseline provided by RFP plant personnel. The provided baseline will be staked each 25 feet. At these stakes grid-traverse line endpoints will be marked with flagged lath. The baseline and grid-traverse line stations of the magnetic survey will be transferred to the appropriate base map.
- * The magnetic base station location will be selected, after consulting site utility maps, to assure minimal magnetic interference due to electric power lines, railroad, fencing, vehicular traffic, subsurface utilities, and air monitoring stations, or other metallic objects, The site should also be cleared with a portable
- * The geophysical field instrument operator will check that personal clothing including watches, and boots, do not contain interfering ferromagnetic materials.
- * Initiate the magnetic survey only after an in situ gamma radiation survey has been completed by RFP plant personnel at each IHSS 115 and 133 groups.
- *Initiate the magnetic survey after a radiation survey has been completed in the Solar fonds area.

Design of appropriate field parameters must consider the following:

- * The roving magnetometer will be suspended on a staff 8 feet above ground surface at each station on the IHSS 115 survey area.
- * The roving magnetometer will be suspended on a staff 4 feet above ground surface at each station on the IHSS 133 group survey area, and in the Solar Ponds area.
- * Spacing between stations along each grid-traverse line stations will be 10 feet.
- * Spacing between adjacent grid-traverse lines will be 25 feet at the IHSS 115 survey area.
- * Spacing between adjacent grid-traverse lines will be 12 1/2 feet at the IHSS 133 group survey area.

 * Spacing between adjacent grid-traverse lines will be 10 feet in the Solar Ponds area.
 - * Grid-traverse line will be extended an additional 50 feet along significant anomaly indications. Where such anomalies are attributed directly to known pipeline, fences, or other visible and mapped anthropogenic ferromagnetic structures, the survey need not be extended.